

142902

***Remedial Investigation/Feasibility Study  
Phase I Technical Memorandum***

***Appendices A-C,E-M***

***Waukegan Manufactured Gas  
and Coke Plant Site  
Waukegan, Illinois***

***Prepared for  
North Shore Gas Company***

***Under the Administrative Order on Consent Re: Remedial Investigation and  
Feasibility Study for the Waukegan Manufactured Gas and Coke Plant Site  
Waukegan, Illinois***

***April 1993***

*Engineering Company*

***Remedial Investigation/Feasibility Study  
Phase I Technical Memorandum***

***Appendices A-C, E-M***

***Waukegan Manufactured Gas  
and Coke Plant Site  
Waukegan, Illinois***

***Prepared for  
North Shore Gas Company***

***Under the Administrative Order on Consent Re: Remedial Investigation and  
Feasibility Study for the Waukegan Manufactured Gas and Coke Plant Site  
Waukegan, Illinois***

***April 1993***

***Barr***

***Engineering Company***

***8300 Norman Center Drive***

***Minneapolis, MN 55437***

***Phone: (612) 832-2600***

***Fax: (612) 835-0186***

## ***Appendices***

## DOCUMENT CONTENTS

Appendix A	Test Trench Logs
Appendix B	Survey Notes
Appendix C	Soil Boring Logs <ul style="list-style-type: none"><li>- Potential Source Area Investigation Shallow Borings</li><li>- Background Soil Borings</li><li>- Surficial Soil Borings</li><li>- Pilot Borings</li></ul>
Appendix E	Monitoring Well and Piezometer Construction Logs
Appendix F	Field Log Data Sheets - Well Development and Water Level Data Sheets
Appendix G	Slug Test Data and Evaluation
Appendix H	Phase I Groundwater Sampling Field Log Data Sheets
Appendix I	Hydrogeologic Model Development
Appendix J	IEPA Investigation Soil Quality Data
Appendix K	Laboratory Standard Operating Procedures
Appendix L	HydroPunch Method
Appendix M	Surface Water Sampling Standard Operating Procedures



## ***Appendix A***

### ***Test Trench Logs***

PROJECT NO. 13/49-003JSL			TEST PIT NO. TT-00B		SHEET 1 OF 1		TEST PIT WALL LOG	
ELEVATION	DEPTH BELOW SURFACE (Ft.)	SAMPLE		PROJECT	LOCATION	MAP OF		
		TYPE AND NUMBER	INTERVAL	Northshore Gas Waukegan Coke Plant	Waukegan, IL.	NW WALL OF PIT		
ELEVATION				CONTRACTOR		DATE EXCAVATED		
				Kirshoffer		3/11/92		
WATER LEVEL AND DATE				EXCAVATION METHOD		LOGGER		
				B-Hoe		JMF		
APPROXIMATE DIMENSIONS				LENGTH	WIDTH	DEPTH	REMARKS	
				50'	3-4'	5'		
				0+00 0+10 0+20 0+30 0+40			COMMENTS	
				SOUTHWEST NORTHEAST				
				Grass on Surface				
0				Silty Sand With Gravel (SM) Fine Grained, Grey (10YR 5/1), Moist (Fill)				
				Cobbles				
				Crushed Rock Base Material				
1				Coal Fines, Black, Moist				
2				Poorly Graded Sand With Silt (SP-SM/SM), Fine Grained, Yellowish Brown (10YR 5/6) To GreenishGrey (5GY 6/1), Moist (Fill)				
3								
4				▽ 3.5'			No Sheen on Groundwater	
5				Poorly Graded Sand (SP) Fine to Medium Grained, Black (10YR 2/1) To Very Dark Grey (10YR 3/1), Wet (Fill)				
6								
7								
				LENGTH				

PROJECT NO.

13/49-003JSL

TEST PIT NO.

TT-01

SHEET 1 OF 5

## TEST PIT WALL LOG

ELEVATION

DEPTH  
BELOW  
SURFACE (Ft. )SAMPLE  
TYPE AND  
NUMBER

INTERVAL

PROJECT Northshore Gas Waukegan Coke Plant

ELEVATION

WATER LEVEL AND DATE

APPROXIMATE DIMENSIONS

CONTRACTOR Krushoffer

EXCAVATION METHOD B-Hoe

LENGTH 220' WIDTH 3-4'

DEPTH 1 - 6 1/2'

REMARKS

DATE EXCAVATED 3-6-92

LOGGER SEM

MAP OF NW WALL OF PIT

NORTHEAST

SOUTHWEST

COMMENTS

Spoon Test Location  
and Result:Oil Sheen Test: N=None,  
T=Trace, M=Moderate,  
H=Heavy

Headspace Reading, ppm

Moderate To Heavy  
Sheen on GroundwaterPoorly Graded  
Sand (SP/SP-SM)  
w/a Trace of Silt,  
Fine to Coarse  
Grained, Black,  
Moist (Fill)  
With Furnace  
Clinkers.Poorly Graded Sand With Silt (SP-SM)  
Fine to Medium Grained, Brown  
(10YR 5/3) With Demolition DebrisPoorly Graded Sand  
With Silt and Gravel  
(SP-SM), Medium to  
Coarse Grained Very  
Dark Grey (10 YR 3/1),  
Moist (Fill) w/  
Demolition DebrisT  
0  
TT-01-01

▽

▽

LENGTH

PROJECT NO. 13/49-003JSL			TEST PIT NO. TT-01		SHEET 2 OF 5		TEST PIT WALL LOG	
ELEVATION	DEPTH BELOW SURFACE (Ft.)	SAMPLE		PROJECT <u>Northshore Gas Waukegan Coke Plant</u>		LOCATION <u>Waukegan, IL.</u>		MAP OF <u>NW</u> WALL OF PIT
		TYPE AND NUMBER	INTERVAL	ELEVATION _____		CONTRACTOR <u>Kirshhoffer</u>		DATE EXCAVATED <u>3-9-92</u>
				WATER LEVEL AND DATE _____		EXCAVATION METHOD <u>B-Hoe</u>		LOGGER <u>SEM</u>
				APPROXIMATE DIMENSIONS		LENGTH <u>220'</u>	WIDTH <u>3-4'</u>	DEPTH <u>1 - 6 1/2'</u>
				<div style="display: flex; justify-content: space-between; padding: 5px;"> <span>0+40</span> <span>0+50</span> <span>0+60</span> <span>0+70</span> <span>0+80</span> </div> <div style="display: flex; justify-content: space-between; padding: 5px;"> <span>NORTHEAST</span> <span>SOUTHWEST</span> </div>				
				LENGTH				

PROJECT NO.

13/49-003JSL

TEST PIT NO.

TT-01

SHEET 3 OF 5

## TEST PIT WALL LOG

ELEVATION

DEPTH  
BELOW  
SURFACE (Ft.)

SAMPLE

TYPE AND  
NUMBER

INTERVAL

PROJECT Northshore Gas Waukegan Coke PlantLOCATION Waukegan, IL.MAP OF NW WALL OF PIT

ELEVATION \_\_\_\_\_

CONTRACTOR KirshhofferDATE EXCAVATED 3-6-92

WATER LEVEL AND DATE \_\_\_\_\_

EXCAVATION METHOD B-HoeLOGGER JMF

APPROXIMATE DIMENSIONS

LENGTH 220'WIDTH 3-4'DEPTH 1 - 6 1/2'

REMARKS \_\_\_\_\_

0+80

0+90

1+00

1+10

1+20

NORTHEAST

SOUTHWEST

COMMENTS

Spoon Test Location  
and Result:Oil Sheen Test: N=None,  
T=Trace, M=Moderate,  
H=HeavyM  
10

Headspace Reading, ppm

Moderate Sheen  
on Groundwater

MATCH 2 OF 5

Poorly Graded Sand With Silt (SP-SM) Medium To Coarse Grained,  
Pale Brown (10YR 6/3), Moist (Fill)Poorly Graded Sand With Silt & Gravel (SP-SM)  
Medium to Coarse Grained, Pale Brown (10YR 6/3),  
Moist (Fill)M  
1 TT-01-03Poorly Graded  
Sand (SP/SP-SM)  
W/A Trace of Silt  
and Fine to Coarse  
Grained and  
Furnace Clinkers,  
Black, Moist (Fill)

LENGTH

PROJECT NO.		TEST PIT NO.		TEST PIT WALL LOG	
13/49-003JSL		TT-01		SHEET 4 OF 5	
ELEVATION	DEPTH BELOW SURFACE (Ft.)	SAMPLE		PROJECT <u>Northshore Gas Waukegan Coke Plant</u> LOCATION <u>Waukegan, IL.</u> MAP OF <u>NW</u> WALL OF PIT	
		TYPE AND NUMBER	INTERVAL	ELEVATION _____ CONTRACTOR <u>Kirshhoffer</u> DATE EXCAVATED <u>3-6-92</u>	
				WATER LEVEL AND DATE _____ EXCAVATION METHOD <u>B-Hoe</u> LOGGER <u>SEM</u>	
				APPROXIMATE DIMENSIONS LENGTH <u>220'</u> WIDTH <u>3-4'</u> DEPTH <u>1-6 1/2'</u> REMARKS _____	
		1+30 1+40 1+50 1+60 1+70		NORTHEAST SOUTHWEST	
0		Poorly Graded Sand With Silt (SP-SM) Medium To Coarse Grained, Pale Brown (10YR 6/3), Moist (Fill)		Root Zone	
1		Poorly Graded Sand With Silt and Gravel (SP-SM) Coarse Grained, Black, Moist (Fill) With Tar Chunks, Rebar.		Poorly Graded Sand With Silt and Gravel (SP-SM) Fine to Medium Grained, Black, Moist (Fill)	
2					
3		MATCH 3 OF 5			
4		▽			
5					
6		TT-01-04 M/80			
7					
				LENGTH	

Spoon Test Location and Result:

Oil Sheen Test: N=None, T=Trace, M=Moderate, H=Heavy

Headspace Reading. ppm

M/10

PROJECT NO.

13/49-003JSL

TEST PIT NO.

TT-01

SHEET 5 OF 5

## TEST PIT WALL LOG

ELEVATION

DEPTH  
BELOW  
SURFACE (Ft.)

SAMPLE

TYPE AND  
NUMBER

INTERVAL

PROJECT Northshore Gas Waukegan Coke Plant

LOCATION Waukegan, IL.

MAP OF NW WALL OF PIT

ELEVATION

CONTRACTOR Kirshhoffer

DATE EXCAVATED 3-9-92

WATER LEVEL AND DATE

EXCAVATION METHOD B-Hoe

LOGGER JMF

APPROXIMATE DIMENSIONS

LENGTH 220'

WIDTH 3-4'

DEPTH 1 - 6 1/2'

REMARKS

1+80

1+90

2+00

2+10

2+20

NORTHEAST

SOUTHWEST

COMMENTS

Spoon Test Location  
and Result:Oil Sheen Test: N=None,  
T=Trace, M=Moderate,  
H=HeavyM  
10

Headspace Reading, ppm

0

1

2

3

4

5

6

7

Root Zone

Grass and Weed Surface Vegetation

Poorly Graded  
Sand (SP/SP-SM)  
W/A Trace of Silt  
and Fine to Coarse  
Grained Black Moist-  
(Fill) With  
Furnace Clinkers,Gravel With Sand (Base Like)  
Greyish Brown (2.5 Y 5/2)  
W/Demolition Debris Bricks,  
Concrete, Rebar

Ash: Light Grey (2.5 YR4/0) (Fill)

Silty Sand With Gravel (SM)  
Greyish Brown (2.5 Y 5/2) to  
Very Dark Grey (2.5 N4/0)  
(Fill) With Debris: Bricks Concrete

TT-01-05

N  
1Poorly Graded Sand (SM)  
Fine To Medium Grained  
Very Pale Brown (10YR 7/3)  
Moist (Fill)Industrial Pond Deposit: Silty Clay (CL/ML) Light Grey (1.5 YN 7/0)  
To White (2.5 YN 8/0)Sandy Lean Clay (CL-SC)  
With Fine Grained Sand  
Dark Grey, Moist (2.5 N 4/0)  
(Alluvium)Poorly Graded Sand (SP/SP-SM) Fine Grained  
Black, wet (2.5 YR 2/0) (Alluvium)Moderate Sheen  
on Groundwater

LENGTH

PROJECT NO.

13/49-003JSL

TEST PIT NO.

TT-02

SHEET 1 OF 5

## TEST PIT WALL LOG

ELEVATION

DEPTH  
BELOW  
SURFACE (FL.)

SAMPLE

TYPE AND  
NUMBER

INTERVAL

PROJECT Northshore Gas Waukegan Coke PlantLOCATION Waukegan, IL.MAP OF NE WALL OF PIT

ELEVATION

CONTRACTOR KirshofferDATE EXCAVATED 3/5/92WATER LEVEL AND DATE 3'EXCAVATION METHOD B-HoeLOGGER SEM

APPROXIMATE DIMENSIONS

LENGTH 185'WIDTH 3-4'DEPTH 3-3.5'

REMARKS

0+00

0+10

0+20

0+30

0+40

SOUTHEAST

Bricks

NORTHWEST

COMMENTS

Spoon Test Location  
and Result:Oil Sheen Test: N=None,  
T=Trace, M=Moderate,  
H=HeavyM  
10

Headspace Reading, ppm

Poorly Graded Sand (SP/SW), Fine to Coarse  
Grained, W/Gravel (Fill) With SlagN  
6.5

TT-02-01

N  
0.5

TT-02-02

Trace Sheen on  
Groundwater  
Between 0+24 and  
0+33NW.Moderate Sheen on  
Groundwater Between  
0+35 and 0+4NW.

LENGTH



PROJECT NO.

13/49-003JSL

TEST PIT NO.

TT-02

SHEET 2 OF 5

## TEST PIT WALL LOG

ELEVATION

DEPTH  
BELOW  
SURFACE (Ft.)

SAMPLE

TYPE AND  
NUMBER

INTERVAL

PROJECT Northshore Gas Waukegan Coke Plant

LOCATION Waukegan, IL.

MAP OF NE WALL OF PIT

ELEVATION

CONTRACTOR Kirshoffer

DATE EXCAVATED 3/5/92

WATER LEVEL AND DATE 3'

EXCAVATION METHOD B-Hoe

LOGGER SEM

APPROXIMATE DIMENSIONS

LENGTH 185'

WIDTH 3-4'

DEPTH 3-3.5'

REMARKS

0+40

0+50

0+60

0+70

0+80

SOUTHEAST

NORTHWEST

COMMENTS

Spoon Test Location  
and Result:Oil Sheen Test: N=None,  
T=Trace, M=Moderate,  
H=HeavyM  
10

Headspace Reading, ppm

Slight Odor

N  
23

TT-02-03

MATCH 1 OF 5





Poorly Graded Sand  
(SP/SW) Fine to Coarse  
Grained, With Gravel  
(Fill) with SlagPoorly Graded Sand,  
(SP-SP/SM) Coarse  
Grained, W/Gravel  
(SP-SP/SM) (Fill)  
W/Demolition Debris:  
Concrete Chunks,  
Bricks, RebarPoorly Graded  
Coarse Sand (SP),  
Brown (Fill)Moderate Sheen on  
Groundwater Between  
0+60 and 0 +70 NW

LENGTH

PROJECT NO.		TEST PIT NO.		SHEET 3 OF 5		TEST PIT WALL LOG	
13/49-0031SL		TT-02					
PROJECT		Northshore Gas Waukegan Coke Plant		LOCATION		Waukegan, IL.	
ELEVATION				CONTRACTOR		Kishoffer	
WATER LEVEL AND DATE		3'		EXCAVATION METHOD		B-Hoe	
APPROXIMATE DIMENSIONS		LENGTH 185'		WIDTH 3-4'		DEPTH 3-3.5'	
REMARKS				DATE EXCAVATED		3/5/92	
LOGGER		SEM		MAP OF		NE WALL OF PIT	
ELEVATION		DEPTH BELOW SURFACE (FT.)		SAMPLE			
TYPE AND NUMBER		INTERVAL					
0		0+80		0+90		1+00	
1		1+10		1+20			
2							
3							
4							
5							
6							
7							
SOUTHEAST		NORTHWEST					
MATCH 2 OF 5		Poorly Graded Sand (SP, SP/SM), Coarse Grained, With Demolition Debris: Concrete Chunks, Bricks, Rebar		M/90		TT-02-04	
COMMENTS		Spoon Test Location and Result:		Oil Sheen Test: N=None, T=Trace, M=Moderate, H=Heavy		Headspace Reading, ppm	
LENGTH							

PROJECT NO. 13/49-003JSL		TEST PIT NO. TT-02		SHEET 4 OF 5		TEST PIT WALL LOG	
ELEVATION	DEPTH BELOW SURFACE (Ft.)	SAMPLE		PROJECT <u>Northshore Gas Waukegan Coke Plant</u>		LOCATION <u>Waukegan, IL.</u>	
		TYPE AND NUMBER	INTERVAL	ELEVATION _____		CONTRACTOR <u>Kirshoffer</u>	
				WATER LEVEL AND DATE <u>3'</u>		EXCAVATION METHOD <u>B-Hoe</u>	
				DATE EXCAVATED <u>3/5/92</u>		LOGGER <u>SEM</u>	
				APPROXIMATE DIMENSIONS		REMARKS	
				LENGTH <u>185'</u> WIDTH <u>3-4'</u> DEPTH <u>3-3.5'</u>			


  

			1+20	1+30	1+40	1+50	1+60	
			SOUTHEAST				NORTHWEST	
0			<div style="display: flex; justify-content: space-between;"> <div style="width: 45%;"> <p>Poorly Graded Sand W/ Gravel (SP-SP/SM), Black (Fill) With Demolition Debris: Concrete Chunks, Bricks, Rebar</p> </div> <div style="width: 45%;"> <p>Poorly Graded Sand (SP-SM), Coarse Grained, Dark Greyish-Brown (10YR 4/2), 1/4" Dia. Slag Pellets Present</p> </div> </div> <div style="display: flex; justify-content: space-around; margin-top: 20px;"> <div style="text-align: center;">  TT-02-06 </div> <div style="text-align: center;">  TT-02-09 </div> <div style="text-align: center;">  TT-02-10 </div> <div style="text-align: center;">  TT-02-05 </div> </div> <div style="margin-top: 20px;"> <p>Poorly Graded Sand (SP-SM), Coarse-Grained Black (Fill)</p> </div>					
1								
2								
3								
4								
5								
6								
7								
			LENGTH					

**COMMENTS**

Spoon Test Location and Result:

Oil Sheen Test: N=None, T=Trace, M=Moderate, H=Heavy

 Headspace Reading, ppm

Moderate Sheen on Groundwater Between 1+35 and 1+68 NW Streaks Present.

Heavy Sheen on Groundwater Between 1+53 and 1+68 NW Blotches present.

PROJECT NO.

13/49-003JSL

TEST PIT NO.

TT-02

SHEET 5 OF 5

## TEST PIT WALL LOG

ELEVATION

DEPTH  
BELOW  
SURFACE (FT.)

SAMPLE

TYPE AND  
NUMBER

INTERVAL

PROJECT

Northshore Gas Waukegan Coke Plant

LOCATION

Waukegan, IL.

MAP OF

NE

WALL OF PIT

ELEVATION

CONTRACTOR

Kirshoffer

DATE EXCAVATED

3/5/92

WATER LEVEL AND DATE

3'

EXCAVATION METHOD

B-Hoe

LOGGER

SEM

APPROXIMATE DIMENSIONS

LENGTH

185'

WIDTH

3-4'

DEPTH

3-3.5'

REMARKS

1+60

1+70

1+80

1+90

2+00

SOUTHEAST

NORTHWEST

## COMMENTS

Spoon Test Location  
and Result:Oil Sheen Test: N=None,  
T=Trace, M=Moderate,  
H=HeavyM  
10

Headspace Reading, ppm

This log is "Backwards"  
-Stationing was from Right  
to Left.Heavy Sheen on Groundwater  
Between 1+53 and 1+68 NW  
Blotches present.Tar, Tar in Pore  
Spaces of SoilOil in Pore Spaces  
of Soil

MATCH 4 OF 5

Poorly Graded  
Sand (SP-SM)  
Coarse Grained  
Dark Greyish Brown  
(10YR 4/2) .1/4"  
Dia. Slag Pellets  
PresentPoorly Graded Sand  
(SP-SM), Coarse-  
Grained BlackEnd of Trench  
@ 1+85NW


Tar


Tar

LENGTH

PROJECT NO. 13/49-003JSL			TEST PIT NO. TT-03			SHEET 1 OF 5			TEST PIT WALL LOG		
ELEVATION	DEPTH BELOW SURFACE (Ft.)	SAMPLE		PROJECT <u>Northshore Gas Waukegan Coke Plant</u>			LOCATION <u>Waukegan, IL.</u>			MAP OF <u>W</u> WALL OF PIT	
		TYPE AND NUMBER	INTERVAL	ELEVATION _____			CONTRACTOR <u>Kirshoffer</u>			DATE EXCAVATED <u>3-10-92</u>	
				WATER LEVEL AND DATE _____			EXCAVATION METHOD <u>B-Hoe</u>			LOGGER <u>JMF</u>	
				APPROXIMATE DIMENSIONS			LENGTH <u>185</u> WIDTH <u>3-4'</u> DEPTH <u>6'</u>			REMARKS _____	
<div style="display: flex; justify-content: space-between;"> <span>S</span> <span>0+00</span> <span>0+10</span> <span>0+20</span> <span>0+30</span> <span>0+40</span> <span>N</span> </div> <div style="position: absolute; top: 100px; left: 100px; width: 600px; height: 600px;"> <!-- Soil Layer 1 --> <div style="position: absolute; top: 100px; left: 100px; width: 600px; height: 100px; border: 1px solid black; background-color: white;"> <p style="text-align: center;">Silty Sand (SM) Fine Grained Dark Grey (10YR 4/1), Moist (Fill)</p> </div> <!-- Soil Layer 2 --> <div style="position: absolute; top: 150px; left: 100px; width: 600px; height: 150px; border: 1px solid black; background-color: white;"> <p style="text-align: center;">100% Furnace Clinkers: Poorly Graded Gravel (GP-SP) Fine Grained With Coarse and Medium Grained Sand, Very Dark Grayish Brown (10YR 3/2), Moist (Fill).</p> </div> <!-- Soil Layer 3 --> <div style="position: absolute; top: 300px; left: 100px; width: 600px; height: 100px; border: 1px solid black; background-color: white;"> <p style="text-align: center;">Silty Sand (SM) With Trace of Gravel, Fine Grained, Very Dark Grey (10YR 3/1)</p> </div> <!-- Soil Layer 4 --> <div style="position: absolute; top: 350px; left: 100px; width: 600px; height: 100px; border: 1px solid black; background-color: white;"> <p style="text-align: center;">Poorly Graded Sand w/Silt (SP-SM) Fine Grained, Pale Brown Wet (Fill or Alluvium)</p> </div> <!-- Soil Layer 5 --> <div style="position: absolute; top: 450px; left: 100px; width: 600px; height: 100px; border: 1px solid black; background-color: white;"> <p style="text-align: center;">Lean Clay (CL) Discolored Black (10YR 2/1) Wet, Oily w/Strong Coal Tar Odor</p> </div> <!-- Groundwater --> <div style="position: absolute; top: 400px; left: 100px; width: 600px; height: 100px; border: 1px solid black; background-color: white;"> <p style="text-align: center;">Heavy Rainbow Sheen on Groundwater</p> </div> </div>											

PROJECT NO.		TEST PIT NO.		SHEET		OF		TEST PIT WALL LOG			
13/49-003JSL		TT-03		2		5					
DEPTH BELOW SURFACE (Ft.)	SAMPLE		PROJECT		LOCATION		MAP OF				
	TYPE AND NUMBER	INTERVAL	Northshore Gas Waukegan Coke Plant		Waukegan, IL.		W WALL OF PIT				
			ELEVATION		CONTRACTOR		DATE EXCAVATED				
					Kirshoffer		3-10-92				
			WATER LEVEL AND DATE		EXCAVATION METHOD		LOGGER				
					B-Hoe		JMF				
			APPROXIMATE DIMENSIONS		LENGTH		WIDTH		DEPTH		
					185		3-4'		5'		
									REMARKS		
			<p>The diagram shows a cross-section of a test pit wall. The vertical axis represents depth below the surface in feet, ranging from 0 to 7. The horizontal axis represents distance along the wall, with markers at 0+40, 0+50, 0+60, 0+70, and 0+80. The wall is labeled 'MATCH 1 OF 5' on the left and 'S' on the right. The soil layers are described as follows:</p> <ul style="list-style-type: none"> <li><b>Top Layer (0 to ~1.5 ft):</b> Silty Sand (SM)- Fine Grained, Dark Gray (10YR 4/1), Moist (Fill)</li> <li><b>Second Layer (~1.5 to ~3.5 ft):</b> 100% Furnace Clinkers: Poorly Graded Gravel (GP-SP) Fine Grained, With Coarse and Medium Sand, Very Dark Grayish Brown, (10YR 3/2), Moist (Fill)</li> <li><b>Third Layer (~3.5 to ~4.5 ft):</b> Silty Sand (SM/ML)- Fine Grained, Discolored Black (10YR 3/1), Moist (Fill) W/Pieces of Glass, Wood</li> <li><b>Fourth Layer (~4.5 to ~5.5 ft):</b> Lean Clay (CL) Discolored Black (10YR 3/1) Wet, Oily (Golden Brown-Greenish Brown), Strong Coal Tar Odor (Alluvium)</li> <li><b>Fifth Layer (~5.5 to ~6.5 ft):</b> Lean Clay Black Interbedded With Silt Laminations White (Industrial Pond Deposit)</li> </ul> <p>The groundwater level is indicated by a dashed line at approximately 4.5 ft depth. A spoon test location is marked with a circle containing 'M/10' and 'H/12'. The test result is 'M/10' and the headspace reading is 'H/12'.</p>							<p>COMMENTS</p> <p>Spoon Test Location and Result:</p> <p>Oil Sheen Test: N=None, T=Trace, M=Moderate, H=Heavy</p> <p>Headspace Reading, ppm</p> <p>Tar, Tar in Pore Spaces of Soil</p> <p>Oil in Pore Spaces of Soil</p> <p>Heavy Rainbow Sheen On Groundwater W/Golden Brown Oily Blebs</p>	
			LENGTH								








PROJECT NO. 13/49-003JSL			TEST PIT NO. TT-03			SHEET 5 OF 5			TEST PIT WALL LOG				
ELEVATION	DEPTH BELOW SURFACE (ft.)	SAMPLE		PROJECT <u>Northshore Gas Waukegan Coke Plant</u>			LOCATION <u>Waukegan, IL.</u>			MAP OF <u>W</u> WALL OF PIT			
		TYPE AND NUMBER	INTERVAL	ELEVATION _____			CONTRACTOR <u>Kirshoffer</u>			DATE EXCAVATED <u>3/11/92</u>			
				WATER LEVEL AND DATE _____			EXCAVATION METHOD <u>B-Hoe</u>			LOGGER <u>JMF</u>			
				APPROXIMATE DIMENSIONS			LENGTH <u>185</u> WIDTH <u>3-4'</u> DEPTH <u>6'</u>			REMARKS _____			
				<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="text-align: center;">S</p> <p style="text-align: center;">1+70</p> <p style="text-align: center;">1+80</p> <p style="text-align: center;">N</p> </div> <div style="width: 70%; position: relative;"> <div style="position: absolute; left: 50px; top: 50%; transform: rotate(-90deg); white-space: nowrap;">MATCH 4 OF 5</div> <div style="position: absolute; left: 20%; top: 10%;"> <p>Silty Sand (SM) Fine Grained, Black (10YR 2/0) Moist (Fill)</p> </div> <div style="position: absolute; left: 20%; top: 25%;"> <p>100% Furnace Clinkers: Poorly Graded Gravel (SP-SP) Fine Grained With Coarse and Medium Sand, Very Dark Greyish Brown (10YR 3/2) Moist (Fill)</p> </div> <div style="position: absolute; left: 20%; top: 45%;"> <p>Lean Clay (CL) Brown (10YR 3/3) Moist (Alluvium)</p> </div> <div style="position: absolute; left: 20%; top: 65%;"> <p>Poorly Graded Sand (SP) Fine to Medium Grained, Pale Brown (10YR 6/3), Moist (Alluvium)</p> </div> <div style="position: absolute; left: 40%; top: 55%;"> <p>TT-03-03</p> <div style="border: 1px solid black; border-radius: 50%; width: 30px; height: 30px; display: flex; align-items: center; justify-content: center;"> <div style="writing-mode: vertical-rl; transform: rotate(180deg);">N</div> <div style="writing-mode: vertical-rl; transform: rotate(180deg);">1</div> </div> </div> <div style="position: absolute; right: 10%; top: 25%;"> <p>End of Trench 1+85</p> </div> </div> </div> <div style="width: 15%; vertical-align: top;"> <p>Spoon Test Location and Result:</p> <div style="margin-top: 20px;"> <p>Oil Sheen Test: N=None, T=Trace, M=Moderate, H=Heavy</p> <div style="border: 1px solid black; border-radius: 50%; width: 40px; height: 40px; display: flex; align-items: center; justify-content: center; margin: 10px 0;"> <div style="writing-mode: vertical-rl; transform: rotate(180deg);">M</div> <div style="writing-mode: vertical-rl; transform: rotate(180deg);">10</div> </div> <p>Headspace Reading, ppm</p> </div> </div>									

LENGTH



PROJECT NO. 13/49-003JSL			TEST PIT NO. TT-03W			SHEET 2 OF 5			TEST PIT WALL LOG		
ELEVATION	DEPTH BELOW SURFACE (F.L.)	SAMPLE		PROJECT <u>Northshore Gas Waukegan Coke Plant</u>			LOCATION <u>Waukegan, IL.</u>			MAP OF <u>S</u> WALL OF PIT	
		TYPE AND NUMBER	INTERVAL	ELEVATION _____			CONTRACTOR <u>Kirshoffer</u>			DATE EXCAVATED <u>3/13/92</u>	
				WATER LEVEL AND DATE _____			EXCAVATION METHOD <u>B-Hoe</u>			LOGGER <u>JMF</u>	
				APPROXIMATE DIMENSIONS			LENGTH <u>210</u> WIDTH <u>3-4'</u> DEPTH <u>5-6'</u>			REMARKS _____	

COMMENTS

Spoon Test Location and Result:

Oil Sheen Test: N=None, T=Trace, M=Moderate, H=Heavy

Headspace Reading, ppm


Spoon Test Location and Result:

(N) None  
(T) Trace  
(M) Moderate  
(H) Heavy

Heavy Oil Sheen on Groundwater With a Trace of Golden Brown Oily Blebs


Tar, Tar in Pore Spaces of Soil

Oil in Pore Spaces of Soil



PROJECT NO. 13/49-003JSL	TEST PIT NO. TT-03W	SHEET 4 OF 5	TEST PIT WALL LOG
-----------------------------	------------------------	--------------	-------------------

ELEVATION	DEPTH BELOW SURFACE (Ft.)	SAMPLE		PROJECT <u>Northshore Gas Waukegan Coke Plant</u>	LOCATION <u>Waukegan, IL.</u>	MAP OF <u>S</u> WALL OF PIT	
		TYPE AND NUMBER	INTERVAL	ELEVATION _____	CONTRACTOR <u>Kirshoffer</u>	DATE EXCAVATED <u>3/13/92</u>	
				WATER LEVEL AND DATE _____		EXCAVATION METHOD <u>B-Hoe</u>	LOGGER <u>JMF</u>
				APPROXIMATE DIMENSIONS		LENGTH <u>210</u>	WIDTH <u>3-4'</u>



**COMMENTS**

Spoon Test Location and Result:

Oil Sheen Test: N=None, T=Trace, M=Moderate, H=Heavy

Headspace Reading, ppm

End Of Trench @ 1+70'

Tar, Tar in Pore Spaces of Soil

Oil in Pore Spaces of Soil

Groundwater @ 4' W/Heavy Rainbow Sheen Oily Blebs.

Porespaces Filled W/Oil: Oily Zone @ Base Of Coal Tar Saturated Sand and in Sand Below and In Interbedded Layer

LENGTH

PROJECT NO.

13/49-003JSL

TEST PIT NO.

TT-03W

SHEET 5 OF 5

## TEST PIT WALL LOG

ELEVATION

DEPTH  
BELOW  
SURFACE (Ft.)

SAMPLE

TYPE AND  
NUMBER

INTERVAL

PROJECT Northshore Gas Waukegan Coke Plant

LOCATION Waukegan, IL.

MAP OF S WALL OF PIT

ELEVATION

CONTRACTOR Kirshoffer

DATE EXCAVATED 3/13/92

WATER LEVEL AND DATE

EXCAVATION METHOD B-Hoe

LOGGER JMF

APPROXIMATE DIMENSIONS

LENGTH 210

WIDTH 3-4'

DEPTH 5-6'

REMARKS

1+70

1+80

1+90

2+00

2+10

EAST

WEST

## COMMENTS

Spoon Test Location  
and Result:Oil Sheen Test: N=None,  
T=Trace, M=Moderate,  
H=HeavyM  
10

Headspace Reading, ppm

Spoon Test Location  
and Result:

(N) - None  
 (T) - Trace  
 (M) - Moderate  
 (H) - Heavy

■ Tar, Tar in Pore  
 Spaces of Soil

▨ Oil in Pore Spaces  
 of Soil

Groundwater @ 4'  
 W/Moderate Oil Sheen

End of  
 Trench  
 @ 2+10'

Poorly Graded Sand With  
 Silt (SP-SM) Black/Orange  
 W/Demolition Debris

Sandy Lean Clay (CL-SC)  
 With a Trace of Gravel  
 Brown (10YR) Moist (Fill)

Poorly Graded Sand (SP)  
 Fine to Medium Grained  
 Discolored Dark Gray Oily

Slightly Oily Coat

(T)

TT-03W-01A

N  
0

Poorly Graded Sand (SP-SM),  
 Fine to Medium Grained, Black-  
 Stained

(N)

TT-03W-02A

N  
3

(H)

(M)

Poorly Graded Sand (SP)  
 Fine to Medium Grained,  
 Black and Greenish Grey  
 Stained, Wet (Alluvium)

Oily

Match 4 of 5

LENGTH

PROJECT NO. 13/49-003JSL			TEST PIT NO. TT-04			SHEET 1 OF 1			TEST PIT WALL LOG			
ELEVATION	DEPTH BELOW SURFACE (Ft.)	SAMPLE		PROJECT <u>Northshore Gas Waukegan Coke Plant</u>			LOCATION <u>Waukegan, IL.</u>			MAP OF <u>NW</u> WALL OF PIT		
		TYPE AND NUMBER	INTERVAL	ELEVATION _____			CONTRACTOR <u>Kirshoffer</u>			DATE EXCAVATED <u>3/5/92</u>		
				WATER LEVEL AND DATE _____			EXCAVATION METHOD <u>B-Hoc</u>			LOGGER <u>SEM</u>		
				APPROXIMATE DIMENSIONS			LENGTH <u>45</u> WIDTH <u>3-4'</u> DEPTH <u>3-7'</u>			REMARKS _____		
<div style="display: flex; justify-content: space-between;"> <span>SOUTHWEST</span> <span>NORTHEAST</span> </div>												
LENGTH												

PROJECT NO.

13/49-003JSL

TEST PIT NO.

TT-05

SHEET 1 OF 2

## TEST PIT WALL LOG

ELEVATION

DEPTH  
BELOW  
SURFACE (Ft.)

SAMPLE

TYPE AND  
NUMBER

INTERVAL

PROJECT Northshore Gas Waukegan Coke Plant

LOCATION Waukegan, IL.

MAP OF E WALL OF PIT

ELEVATION

CONTRACTOR Kirshoffer

DATE EXCAVATED 3/9/92

WATER LEVEL AND DATE

EXCAVATION METHOD B-Hoe

LOGGER JMF

APPROXIMATE DIMENSIONS

LENGTH 70'

WIDTH 3-4'

DEPTH 5-6'

REMARKS

0+00

0+10

0+20

0+30

0+40

NORTH

SOUTH

0

Poorly Graded Sand With Silt (SP-SM)- Fine to medium grained, Dark Brown (10YR) Moist (Fill)

1

Coal Fines, Black, Moist (Fill)

2

3

Poorly Graded Sand (SP) Fine to Medium Grained Light Yellowish Brown, (10YR 6/4) Wet Below 4' (Coarse Alluvium)

TT-05-02

H/21

4

▽

H/2

TT-05-01

5

Poorly Graded Sand (SP) Fine to Medium Grained, Discolored Grey to Black, Oily Coating on Grains (Alluvium)

6

7

## COMMENTS

Spoon Test Location and Result:

Oil Sheen Test: N=None, T=Trace, M=Moderate, H=Heavy

M/10

Headspace Reading, ppm



Tar, Tar in Pore Spaces of Soil



Oil in Pore Spaces of Soil

Groundwater @ 4' W/Heavy Rainbow Sheen

LENGTH



PROJECT NO.		TEST PIT NO.		TEST PIT WALL LOG		
13/49-003JSL		TT-05		SHEET 2 OF 2		
DEPTH BELOW SURFACE (Ft.)	SAMPLE		PROJECT Northshore Gas Waukegan Coke Plant			
	TYPE AND NUMBER	INTERVAL	LOCATION Waukegan, IL.			
ELEVATION			CONTRACTOR Kirshoffer			
WATER LEVEL AND DATE			DATE EXCAVATED 3/9/92-3/10/92			
APPROXIMATE DIMENSIONS			EXCAVATION METHOD B-Hoe			
			LOGGER JMF			
			REMARKS			
			<div style="display: flex; justify-content: space-between;"> <span>0+40</span> <span>0+50</span> <span>0+60</span> <span>0+70</span> <span>0+80</span> </div> <div style="display: flex; justify-content: space-between;"> <span>NORTH</span> <span>SOUTH</span> </div>			COMMENTS
0			<div style="border: 1px solid black; padding: 5px;"> Poorly Graded Sand (SP) and Poorly Graded Sand With Silt (SP-SM)-  Fine Grained Dark Brown (10 YR 3/3) Moist (Fill) </div>			
1			<div style="border: 1px solid black; padding: 5px;"> Coal Fines, Black, Moist (Fill) </div>			Trench End @ 0+70 SW
2			<div style="border: 1px solid black; padding: 5px;"> Poorly Graded Sand (SP) Fine to Medium  Grained Light Yellowish Brown (10YR 6/4),  Moist-Wet Below 4' (Fill) </div>			
3			<div style="border: 1px solid black; padding: 5px;"> <div style="background-color: #cccccc; height: 20px; width: 100%;"></div> </div>			
4			<div style="border: 1px solid black; padding: 5px;"> <div style="background-color: #cccccc; height: 20px; width: 100%;"></div> </div>			
5			<div style="border: 1px solid black; padding: 5px;"> <div style="background-color: #cccccc; height: 20px; width: 100%;"></div> </div>			
6			<div style="border: 1px solid black; padding: 5px;"> <div style="background-color: #cccccc; height: 20px; width: 100%;"></div> </div>			
7			<div style="border: 1px solid black; padding: 5px;"> <div style="background-color: #cccccc; height: 20px; width: 100%;"></div> </div>			
			LENGTH			

PROJECT NO. 13/49-003JSL			TEST PIT NO. TT-05E			SHEET 1 OF 3			TEST PIT WALL LOG			
ELEVATION	DEPTH BELOW SURFACE (Ft.)	SAMPLE		PROJECT <u>Northshore Gas Waukegan Coke Plant</u>			LOCATION <u>Waukegan, IL.</u>			MAP OF <u>N</u> WALL OF PIT		
		TYPE AND NUMBER	INTERVAL	ELEVATION _____			CONTRACTOR <u>Kirshoffer</u>			DATE EXCAVATED <u>3/10/92</u>		
				WATER LEVEL AND DATE _____			EXCAVATION METHOD <u>B-Hoe</u>			LOGGER <u>JMF</u>		
				APPROXIMATE DIMENSIONS			LENGTH <u>120</u> WIDTH <u>3-4'</u> DEPTH <u>2 1/2-6'</u>			REMARKS _____		

			0+00	0+10	0+20	0+30	0+40	EAST	COMMENTS
WEST			Sand @ Surface						
0			Silty Sand (SM)- Fine Grained, Black, Moist (Fill) With Concrete, Wood, Braided Steel Cables Plant Roots (Woody) in Upper 1'.						
1			Coal Fines Black (Fill)						
2			Poorly Graded Sand (SP)- Fine to Medium Grained, Light Yellowish Brown, Moist (Alluvium)						
3			Poorly Graded Sand W/Silt (SP-SW)-Fine Grained Moist and (SP) Pale Brown, Moist						
4			Poorly Graded Sand (SP)- Fine to Medium Grained, Light Yellowish Brown, Moist (Alluvium) With Black and Greenish Brown Discoloration, Grey, Oily Wet						
5			Grey Below Water						
6									
7									
			LENGTH						

Tar, Tar in Pore Spaces of Soil

Oil in Pore Spaces of Soil

Heavy Rainbow Sheen On Groundwater

[illegible]

PROJECT NO. 13/49-003JSL		TEST PIT NO. TT-05E		SHEET 3 OF 3		<b>TEST PIT WALL LOG</b>	
ELEVATION	DEPTH BELOW SURFACE (Ft. )	SAMPLE		PROJECT <u>Northshore Gas Waukegan Coke Plant</u> LOCATION <u>Waukegan, IL.</u> MAP OF <u>N</u> WALL OF PIT			
		TYPE AND NUMBER	INTERVAL	ELEVATION _____ CONTRACTOR <u>Kirshoffer</u> DATE EXCAVATED <u>3/10/92</u>			
				WATER LEVEL AND DATE _____ EXCAVATION METHOD <u>B-Hoe</u> LOGGER <u>JMF</u>			
				APPROXIMATE DIMENSIONS LENGTH <u>120</u> WIDTH <u>3-4'</u> DEPTH <u>2 1/2-6'</u> REMARKS _____			
		<div style="display: flex; justify-content: space-between; padding: 5px;"> <span>0+80</span> <span>0+90</span> <span>1+00</span> <span>1+10</span> <span>1+20</span> </div> <div style="display: flex; justify-content: space-between; padding: 5px;"> <span>WEST</span> <span>Sand @ Surface</span> <span>EAST</span> </div>					
		LENGTH					

PROJECT NO.

13/49-003JSL

TEST PIT NO.

TT-06

SHEET 1 OF 2

## TEST PIT WALL LOG

ELEVATION DEPTH BELOW SURFACE (FL.)	SAMPLE		PROJECT	LOCATION	MAP OF	WALL OF PIT
	TYPE AND NUMBER	INTERVAL				
			Northshore Gas Waukegan Coke Plant	Waukegan, IL.	N	
			ELEVATION	CONTRACTOR	DATE EXCAVATED	
			WATER LEVEL AND DATE	EXCAVATION METHOD	LOGGER	
			APPROXIMATE DIMENSIONS	LENGTH	WIDTH	DEPTH
				78'	3-4'	4.5-5.5'
			REMARKS			
			<div style="display: flex; justify-content: space-between;"> <span>0+00</span> <span>0+10</span> <span>0+20</span> </div> <div style="display: flex; justify-content: space-between;"> <span>EAST</span> <span>Sand Drive @ Surface</span> <span>WEST</span> </div> <div style="border: 1px solid black; padding: 5px; margin-top: 10px;"> <p>Poorly Graded Sand (SP)- With a Trace of Silt, Fine Grained, Pale Brown (16YR 6/3), and Poorly Graded Sand (SP)- Fine to Medium Grained Very Pale Brown, (10YR 7/4) Moist (Fill)</p> <p>Coal Fines Black (Fill)</p> <p>Base Material Crushed Rock Medium To Coarse Gravel, Light Yellowish Brown (10YR 6/4)</p> <div style="display: flex; justify-content: space-between;"> <div style="width: 45%;"> <p>Poorly Graded Sand (SP)- Fine to Medium Grained, Light Yellowish Brown, Moist (Coarse Alluvium)</p> </div> <div style="width: 45%;"> <p>Poorly Graded Sand With Silt (SP-SM)- Fine to Medium Grained, Grey (10YR 5/1), Moist (Fill)</p> </div> </div> <p>TT-06-01</p> <p>Concrete Footing</p> <p>Poorly Graded Sand (SP)- Fine to Medium Grained, Light Brownish Grey, Wet (Coarse Alluvium)</p> </div>			
			<div style="display: flex; justify-content: space-between;"> <span>0</span> <span>1</span> <span>2</span> <span>3</span> <span>4</span> <span>5</span> <span>6</span> <span>7</span> </div>			
			LENGTH			

## COMMENTS

Spoon Test Location and Result:

Oil Sheen Test: N=None, T=Trace, M=Moderate, H=Heavy

M  
10

Headspace Reading, ppm

 Tar, Tar in Pore Spaces of Soil

 Oil in Pore Spaces of Soil

Concrete Footing

Heavy Rainbow Sheen on Groundwater @ 0+10 Oily

PROJECT NO.		TEST PIT NO.		TEST PIT WALL LOG	
13/49-003JSL		TT-06		SHEET 2 OF 2	
PROJECT Northshore Gas Waukegan Coke Plant		LOCATION Waukegan, IL.		MAP OF N WALL OF PIT	
ELEVATION		CONTRACTOR Kirshoffer		DATE EXCAVATED 3/9/92	
WATER LEVEL AND DATE		EXCAVATION METHOD B-Hoe		LOGGER JMF	
APPROXIMATE DIMENSIONS		LENGTH 78' WIDTH 3-4' DEPTH 5 1/2'		REMARKS	
DEPTH BELOW SURFACE (ft.)	SAMPLE TYPE AND NUMBER	INTERVAL			
0			0+30	0+40	0+50 Sand Drive @ Surface
0			0+60	0+70	WEST
0			EAST		
1			Poorly Graded Sand With Silt (SP-SM)- Fine Grained, Pale Brown (10YR 6/3), Moist (Fill) and Poorly Graded Sand (SP)- Fine Grained, Very Pale Brown, (10YR 7/4), Moist (Fill)		
2			Coal Fines, Black (Fill)		
2			Base Material Crushed Rock, Medium to Coarse Gravel Light Yellowish Brown (10YR 6/4)		
3			Poorly Graded Sand (SP)- Fine to Medium Grained, Light Yellowish Brown (Fill)		
4			Poorly Graded Sand (SP) Fine to medium Grained, Discolored Black With Strong Fuel Oil & Tar Odor. Moist (Fill).		
4			Concrete		
4			TT-06-02		
4			TT-06-03		
5					
6					
7					
			LENGTH		

COMMENTS

End of Trench @ 0+78

Spoon Test Location and Result:

Oil Sheen Test: N=None, T=Trace, M=Moderate, H=Heavy

Headspace Reading, ppm







Tar, Tar in Pore Spaces of Soil

Oil in Pore Spaces of Soil

Heavy Rainbow Sheen on Groundwater


PROJECT NO. 13/49-003JSL		TEST PIT NO. TT-07		SHEET 1 OF 2		TEST PIT WALL LOG			
ELEVATION	DEPTH BELOW SURFACE (Ft.)	SAMPLE		PROJECT <u>Northshore Gas Waukegan Coke Plant</u>		LOCATION <u>Waukegan, IL.</u>		MAP OF <u>NE</u> WALL OF PIT	
		TYPE AND NUMBER	INTERVAL	ELEVATION _____		CONTRACTOR <u>Kirshoffer</u>		DATE EXCAVATED <u>3/19/92</u>	
				WATER LEVEL AND DATE _____		EXCAVATION METHOD <u>B-Hoe</u>		LOGGER <u>JMF</u>	
				APPROXIMATE DIMENSIONS		LENGTH <u>80'</u> WIDTH <u>3-4'</u> DEPTH <u>6'</u>		REMARKS _____	

			0+00	0+10	0+20	0+30	0+40	
			SOUTHEAST				NORTHWEST	COMMENTS
0			Silty Sand (SM)- Fine Grained, Black (10YR ) Slightly Organic, Moist (Fill)					Spoon Test Location and Result:   Oil Sheen Test: N=None, T=Trace, M=Moderate, H=Heavy  Headspace Reading, ppm
1								
2			Industrial Pond Deposit: Silt Sized (ML), Pale Yellow (5Y8/3), Moist (Fill), With Some Blue Zones					 Tar, Tar in Pore Spaces of Soil   Oil in Pore Spaces of Soil
3			<div style="display: flex; align-items: center;"> <div style="text-align: center; margin-right: 10px;">               TT-07-02           </div> <div>             Tar Saturated Sand    </div> </div>					
4			<div style="display: flex; align-items: center;"> <div style="text-align: center; margin-right: 10px;">               TT-07-01 Blue Sample           </div> <div>             Zone of Blue and Yellow On Top of Groundwater               Poorly Graded Sand (SP)- Fine to Medium Grained, Light Brownish Grey (10YR), Wet, Mottled Reddish Brown 4-4.5', W/Blue Discolored Zone           </div> </div>					Moderate Sheen in Groundwater 0+00 to 0+30 Heavy Sheen W/Oily Blebs, Golden Brown 0+31
5								
6								
7								
			LENGTH					


PROJECT NO. 13/49-003JSL		TEST PIT NO. TT-07		SHEET 2 OF 2		TEST PIT WALL LOG	
ELEVATION	DEPTH BELOW SURFACE (Ft.)	SAMPLE		PROJECT <u>Northshore Gas Waukegan Coke Plant</u>		LOCATION <u>Waukegan, IL.</u>	
		TYPE AND NUMBER	INTERVAL	ELEVATION _____		CONTRACTOR <u>Kirshoffer</u>	
				WATER LEVEL AND DATE _____		DATE EXCAVATED <u>3/19/92</u>	
				APPROXIMATE DIMENSIONS		LOGGER <u>JMF</u>	
				LENGTH <u>80'</u>	WIDTH <u>3-4'</u>	DEPTH <u>6'</u>	REMARKS _____


		0+40	0+50	0+60	0+70	0+80	
		SOUTHEAST				NORTHWEST	<div style="text-align: center;">COMMENTS</div> <p>End of Trench @ 0+80' NW</p> <p>Spoon Test Location and Result:</p> <div style="display: flex; align-items: center; margin-top: 10px;"> <div style="text-align: center; margin-right: 10px;">  </div> <div>Oil Sheen Test: N=None, T=Trace, M=Moderate, H=Heavy</div> </div> <p style="margin-top: 10px;">Headspace Reading, ppm</p> <div style="margin-top: 20px;"> <div style="display: flex; align-items: center; margin-bottom: 5px;"> <div style="width: 15px; height: 15px; background-color: black; margin-right: 5px;"></div> <div>Tar, Tar in Pore Spaces of Soil</div> </div> <div style="display: flex; align-items: center;"> <div style="width: 15px; height: 15px; background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); margin-right: 5px;"></div> <div>Oil in Pore Spaces of Soil</div> </div> </div>
0		Silty Sand (SM)- Fine Grained, Black (10YR ) Slightly Organic Moist (Fill)					
1		Industrial Pond Deposit: Silt Sized (ML) Pale Yellow (5Y8/3), Moist (Fill), With Some Blue Zones					
2		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
3							
4		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
5		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
6		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
7		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> <div style="background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); padding: 2px; margin-bottom: 2px;">Tar - Oily Sand (SP) f-m (Fill)</div> <div style="text-align: center;">Grading to Oily Sand</div> </div> </div>					
		<div style="display: flex; justify-content: space-between;"> <div style="width: 15%;"> <p style="writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</p> </div> <div style="width: 85%;"> <div style="background-color: black; padding: 2px; margin-bottom: 2px;">Tar- Saturated Sand</div> </div></div>					





PROJECT NO. 13/49-003JSL		TEST PIT NO. TT-08		SHEET 1 OF 1		<b>TEST PIT WALL LOG</b>	
ELEVATION	DEPTH BELOW SURFACE (Ft.)	SAMPLE		PROJECT <u>Northshore Gas Waukegan Coke Plant</u> LOCATION <u>Waukegan, IL.</u> MAP OF <u>W</u> WALL OF PIT			
		TYPE AND NUMBER	INTERVAL	ELEVATION _____ CONTRACTOR <u>Kirshoffer</u> DATE EXCAVATED <u>3/21/92</u>			
				WATER LEVEL AND DATE <u>5'</u> EXCAVATION METHOD <u>B-Hoe</u> LOGGER <u>SEM</u>			
				APPROXIMATE DIMENSIONS LENGTH <u>22'</u> WIDTH <u>3-4'</u> DEPTH <u>5.5'</u> REMARKS _____			
		<div style="display: flex; justify-content: space-between; padding: 5px;"> <span>0+00</span> <span>0+10</span> <span>0+20</span> <span>0+30</span> <span>0+40</span> </div> <div style="display: flex; justify-content: space-between; padding: 5px;"> <span>SOUTH</span> <span>NORTH</span> </div> <div style="position: absolute; top: 270px; left: 750px; font-size: small;">       Spoon Test Location and Result:         Oil Sheen Test: N=None, T=Trace, M=Moderate, H=Heavy        (M/10)        Headspace Reading, ppm         Rubble Consists of Mostly Masonry Bricks, Large 3' x 4' of Sheet Metal, Wood         Heavy Sheen on Groundwater     </div>					



ELEVATION	DEPTH BELOW SURFACE (Ft.)	SAMPLE TYPE AND NUMBER	INTERVAL	PROJECT Northshore Gas Waukegan Coke Plant		LOCATION Waukegan, IL.		MAP OF E WALL OF PIT	
				ELEVATION	CONTRACTOR Kishoffer	EXCAVATION METHOD B-Hoe	DATE EXCAVATED 3/11/92		
WATER LEVEL AND DATE				LENGTH 70'	WIDTH 3-4'	DEPTH 5-7'	REMARKS	LOGGER SEM	
APPROXIMATE DIMENSIONS									



PROJECT NO. 13/49-003JSL		TEST PIT NO. TT-09		SHEET 2 OF 2		TEST PIT WALL LOG	
ELEVATION	DEPTH BELOW SURFACE (Ft.)	SAMPLE TYPE AND NUMBER	INTERVAL	PROJECT Northshore Gas Waukegan Coke Plant	LOCATION Waukegan, IL.	MAP OF E	WALL OF PIT
				ELEVATION _____	CONTRACTOR Kirshoffer	DATE EXCAVATED 3/11/92	
				WATER LEVEL AND DATE _____	EXCAVATION METHOD B-Hoe	LOGGER JMF	
				APPROXIMATE DIMENSIONS	LENGTH 70' WIDTH 3-4' DEPTH 6-7'	REMARKS	
0				0+40	0+50	0+60	0+70
1				NORTH Sand @ Surface SOUTH			
2				Poorly Graded Sand (SP)- Fine to Medium Grained, Pale Brown (10YR 6/1) Moist (Fill) W/Demolition Debris: Concrete, Wood, Bricks			
3				Poorly Graded Sand (SP)- Fine Grained Pale Brown (10YR 6/3) Moist (Alluvium)			
4				End of Trench @ 0+70' S			
5				 TT-09-02			
6				Slight to Moderate Sheen on Groundwater 0+40 to End of Trench			
7				COMMENTS Spoon Test Location and Result: Oil Sheen Test: N=None, T=Trace, M=Moderate, H=Heavy  Headspace Reading, ppm			

PROJECT NO. 13/49-003JSL			TEST PIT NO. TT-10			SHEET 1 OF 1			<b>TEST PIT WALL LOG</b>		
ELEVATION	DEPTH BELOW SURFACE (Ft.)	SAMPLE		PROJECT <u>Northshore Gas Waukegan Coke Plant</u>			LOCATION <u>Waukegan, IL.</u>			MAP OF <u>S</u> WALL OF PIT	
		TYPE AND NUMBER	INTERVAL	ELEVATION _____			CONTRACTOR <u>Kirshoffer</u>			DATE EXCAVATED <u>3/21/92</u>	
				WATER LEVEL AND DATE <u>6-1/2'</u>			EXCAVATION METHOD <u>B-Hoe</u>			LOGGER <u>SEM</u>	
				APPROXIMATE DIMENSIONS			LENGTH <u>45'</u> WIDTH <u>4-5'</u> DEPTH <u>5-7'</u>			REMARKS _____	

	0+00	0+10	0+20	0+30	0+40	WEST	
EAST							<b>COMMENTS</b>  Spoon Test Location and Result:  <div style="display: flex; align-items: center; margin-top: 10px;"> <div style="border: 1px solid black; border-radius: 50%; width: 30px; height: 30px; display: flex; align-items: center; justify-content: center; margin-right: 10px;"> M 10 </div> <div>             Oil Sheen Test: N=None, T=Trace, M=Moderate, H=Heavy               Headspace Reading, ppm           </div> </div> Trench is Full of Demolition Debris of Masonry Bricks, Large Dia. (72") Concrete chunks, pipes (Not Connected to Any- thing, Varying Dia.) Wire, Wood, Concrete Chunks <2' Dia., Rubble Varies Up 40-50% of Fill.  End of Trench @ 0+ 45'
0	Fill, Light Yellowish Brown (10YR 6/4) Silty Sand W/Gravel (SP/SM), Black Heavy Sheen, Slight Odor						
1	Fine, to Medium Grained Sand (SP) Very Pale Brown (10YR 7/4) Black Silty Sand w/Gravel and Rubble (SP-SM)						
2	Moderate Sheen Moderate Odor In Fill (Gasoline)						
3	Heavy Sheen Poorly Graded Fine-Moderate Grained Sand (SP) (10YR 4/3) Dark Brown						
4	Poorly Graded Fine-Medium Grained Sand (SP) Very Dark Brown (10YR 2/2)					<div style="border: 1px solid black; border-radius: 50%; width: 30px; height: 30px; display: flex; align-items: center; justify-content: center;"> H 4740 </div> TT-10-02	
5	Very Heavy Sheen on Groundwater						
6							
7							
<div style="display: flex; align-items: center; justify-content: center;"> <div style="width: 100%; border-bottom: 1px solid black; margin-bottom: 5px;"></div> <div style="margin-left: 10px;">LENGTH</div> </div>							

[illegible]

PROJECT NO. 13/49-003JSL		TEST PIT NO. TT-12		SHEET 1 OF 1		TEST PIT WALL LOG	
ELEVATION DEPTH BELOW SURFACE (ft.)	SAMPLE		PROJECT Northshore Gas Waukegan Coke Plant		LOCATION Waukegan, IL.		MAP OF S WALL OF PIT
	TYPE AND NUMBER	INTERVAL	ELEVATION _____		CONTRACTOR Kirshoffer		DATE EXCAVATED 3/18/92
			WATER LEVEL AND DATE _____		EXCAVATION METHOD B-Hoe		LOGGER JMF
			APPROXIMATE DIMENSIONS		LENGTH 42'	WIDTH 3-4"	DEPTH 5-6'

	0+00	0+10	0+20	0+30	0+40	
	EAST					WEST
0	Gravelly Sand Base Material					<p>COMMENTS</p> <p>Spoon Test Location and Result:</p> <p>Oil Sheen Test: N=None, T=Trace, M=Moderate, H=Heavy</p> <p>Headspace Reading, ppm</p> <p>Spoon Test Location and Result:</p> <p>(N) None (T) Trace (M) Moderate (H) Heavy</p> <p>Very Heavy Sheen on Groundwater With Thick Black Oily Blebs</p> <p>No Static Groundwater Level Recorded-Rising When Backfilled-Slow Recovery Due to Oil/Tar Saturated Soils.</p> <p>Tar, Tar in Pore Spaces of Soil</p> <p>Oil in Pore Spaces of Soil</p>
1	Silty Sand (SM) Fine Grained, Dark Gray, Moist (Fill) W/Demolition Debris: Bricks, Concrete, Iron Pieces, Square Rebar					
2	Silty Sand (SM) Fine Grained, Black (Stained, Coated, Saturated), Moist (Fill) W/Demolition Debris: Concrete, Iron Pieces, Square Rebar. Oily-Tarry Coating of Grains, With Zones of Oil/Tar Saturation					
3						
4						
5						
6						
7						
LENGTH						

PROJECT NO.

13/49-003JSL

TEST PIT NO.

TT-13

SHEET 1 OF 1

## TEST PIT WALL LOG

ELEVATION	DEPTH BELOW SURFACE (FT.)	SAMPLE		PROJECT	LOCATION	MAP OF	WALL OF PIT
		TYPE AND NUMBER	INTERVAL				
				ELEVATION	CONTRACTOR	DATE EXCAVATED	
				WATER LEVEL AND DATE	EXCAVATION METHOD	LOGGER	
				APPROXIMATE DIMENSIONS	LENGTH	WIDTH	DEPTH
					50'	3-4"	7.5'
				REMARKS			


  

		COMMENTS
		Spoon Test Location and Result:
		Oil Sheen Test: N=None, T=Trace, M=Moderate, H=Heavy
		Headspace Reading, ppm
		End of Trench @ 0+50 W

		LENGTH





PROJECT NO. 13/49-003JSL		TEST PIT NO. TT-14		SHEET 2 OF 2		TEST PIT WALL LOG	
ELEVATION	DEPTH BELOW SURFACE (FL.)	PROJECT <u>Northshore Gas Waukegan Coke Plant</u>		LOCATION <u>Waukegan, IL.</u>		MAP OF <u>NW</u> WALL OF PIT	
		ELEVATION _____		CONTRACTOR <u>Kirshoffer</u>		DATE EXCAVATED <u>3/18/92</u>	
		WATER LEVEL AND DATE _____		EXCAVATION METHOD <u>B-Hoe</u>		LOGGER <u>JMF</u>	
		APPROXIMATE DIMENSIONS		LENGTH <u>70'</u> WIDTH <u>3-4"</u> DEPTH <u>6'</u>		REMARKS _____	
		TYPE AND NUMBER	INTERVAL				
		<div style="display: flex; justify-content: space-between;"> <span>0+40</span> <span>0+50</span> <span>0+60</span> <span>0+70</span> <span>0+80</span> </div> <div style="display: flex; justify-content: space-between;"> <span>SOUTHWEST</span> <span>NORTHEAST</span> </div>				COMMENTS  Spoon Test Location and Result:  <div style="display: flex; align-items: center;"> <div style="border: 1px solid black; border-radius: 50%; width: 30px; height: 30px; display: flex; align-items: center; justify-content: center; margin-right: 10px;"> M 10 </div> <div> <p>Oil Sheen Test: N=None, T=Trace, M=Moderate, H=Heavy</p> <p>Headspace Reading, ppm</p> </div> </div> <div style="margin-top: 20px;"> <div style="display: flex; justify-content: space-between;"> <div> <div style="width: 15px; height: 15px; background-color: black; margin-bottom: 5px;"></div> Tar, Tar in Pore Spaces of Soil <div style="width: 15px; height: 15px; border: 1px solid black; margin-top: 5px;"></div> Oil in Pore Spaces of Soil </div> </div> </div>	
		<div style="position: relative; height: 600px;"> <div style="position: absolute; left: -40px; top: 50%; transform: translateY(-50%); writing-mode: vertical-rl; transform: rotate(180deg);">Match 1 of 2</div> <div style="position: absolute; right: 0; top: 0;">End of Trench @ 0+70 NE</div> <div style="position: absolute; top: 10%; left: 10%;">           Poorly Graded Sand W/Silt (SP-SM)- W/Gravel Pale Brown (10YR 6/3), Moist (Fill) </div> <div style="position: absolute; top: 20%; left: 10%;">           Silty Sand (SM) Fine Grained Dark Grey to Black W/Demolition Debris </div> <div style="position: absolute; top: 20%; right: 10%;">           Silty Sand (SM) Fine Grained, Dark Grey to Black, With Demolition Debris             Oily Coated Grains and Saturated Zone </div> <div style="position: absolute; top: 35%; right: 10%;">           4" Clay Tile W/White-Silver Crystal-form Particles in a Oily Sand Matrix (Could Not Sample Due to Safety) </div> <div style="position: absolute; top: 40%; left: 20%;"> <div style="border: 1px solid black; border-radius: 50%; width: 30px; height: 30px; display: flex; align-items: center; justify-content: center;"> H 1360 </div>           TT-14-03 </div> <div style="position: absolute; top: 60%; left: 20%;">           Below 4' Oil-Tar Coated Grains and Saturated Areas </div> <div style="position: absolute; top: 70%; left: 10%;">           Poorly Graded Sand (SP) Very Dark Grey Saturated With Oil Water (Alluvium) </div> </div>					
		LENGTH					

PROJECT NO.


13/49-003JSL

TEST PIT NO.

TT-15

SHEET 1 OF 3

## TEST PIT WALL LOG



PROJECT NO.		TEST PIT NO.		TEST PIT WALL LOG	
13/49-003JSL		TT-15		SHEET 2 OF 3	
DEPTH BELOW SURFACE (ft.)	SAMPLE		PROJECT Northshore Gas Waukegan Coke Plant		
	TYPE AND NUMBER	INTERVAL	LOCATION Waukegan, IL.		
			MAP OF S WALL OF PIT		
			ELEVATION _____ CONTRACTOR Kirshoffer		
			DATE EXCAVATED 3/17/92		
			WATER LEVEL AND DATE _____ EXCAVATION METHOD B-Hoe		
			LOGGER JMF		
			APPROXIMATE DIMENSIONS LENGTH 125' WIDTH 3-4' DEPTH 5-10' REMARKS _____		
			<div style="display: flex; justify-content: space-between;"> <span>0+40</span> <span>0+50</span> <span>0+60</span> <span>0+70</span> <span>0+80</span> </div> <div style="display: flex; justify-content: space-between;"> <span>EAST</span> <span>WEST</span> </div> <div style="border: 1px solid black; padding: 10px; margin: 10px;"> <p>0 Silty Sand (SM) Fine to Medium Grained</p> <p>1 Silty Sand (SM) Fine Grained, W/Brick Moist W/Gravel (Fill) (M)</p> <p>2 Poorly Graded Sand (SP) Fine to Medium Grained, Light Gray (Fill) W/Some Demolition Debris: Concrete</p> <p>3</p> <p>4 Poorly Graded Sand (SP)- Fine Grained, Pale Brown (10YR 4/3), Moist (Alluvium) (N)</p> <p>5</p> <p>6 Poorly Graded Sand (SP)- Dark Grey to Black, Oil Coated Grains (H) ▽</p> <p>7 Poorly Graded Sand (SP)- Fine Grained, Grey, Wet (Alluvium) (M)</p> </div> <div style="margin-top: 10px;"> <p>End of Trench @ 1+25W</p> </div>		
			<p>COMMENTS</p> <p>Spoon Test Location and Result:</p> <p>(N) None</p> <p>(T) Trace</p> <p>(M) Moderate</p> <p>(H) Heavy</p> <p>■ Tar, Tar in Pore Spaces of Soil</p> <p>□ Oil in Pore Spaces of Soil</p> <p>Heavy Sheen on Groundwater</p>		
			LENGTH		

PROJECT NO.		TEST PIT NO.		TEST PIT WALL LOG	
13/49-003JSL		TT-15 EXT		SHEET 3 OF 3	
PROJECT		LOCATION		MAP OF S WALL OF PIT	
Northshore Gas Waukegan Coke Plant		Waukegan, IL.		DATE EXCAVATED 3/18/92	
CONTRACTOR		EXCAVATION METHOD		LOGGER	
Kirshoffer		B-Hoe		JMF	
WATER LEVEL AND DATE		LENGTH		DEPTH	
APPROXIMATE DIMENSIONS		125'		3-4" 5 - 10'	
REMARKS					
ELEVATION	DEPTH BELOW SURFACE (Ft.)	TYPE AND NUMBER			
		INTERVAL			
0	0+00	WEST			
1	0-10	EAST			
2	0-20				
3	0-30				
4	0-40				
5					
6					
7					
MATCH TT-15 1 OF 3 @ 0+00		<p>Crushed Rock Base Material</p> <p>Poorly Graded Sand (SP)- Fine Grained, Pale Brown (10YR 6/5), Moist (Fill)</p> <p>Mixed Fill: Mostly Poorly Graded Sand With Silt (SP-SM), Fine Grained, Light Brown (10YR 6/4), Moist, W/Demolition Debris Including: Wood, Concrete, Bricks, Square Rebar, and Pieces of 4" and 2" Stainless Steel Pipe and 4" Cast Iron Pipe.</p> <p>Zones of: Oily Coated Grains and Saturation</p> <p>TT-15-01A</p>			
COMMENTS		<p>Spoon Test Location and Result:</p> <p>Oil Sheen Test: N=None, T=Trace, M=Moderate, H=Heavy</p> <p>Headspace Reading, ppm</p> <p>Tar, Tar in Pore Spaces of Soil</p> <p>Oil in Pore Spaces of Soil</p>			

PROJECT NO. <b>13/49-003JSL</b>			TEST PIT NO. <b>TT-16</b>			SHEET <b>1</b> OF <b>1</b>			<b>TEST PIT WALL LOG</b>			
ELEVATION	DEPTH BELOW SURFACE (Ft.)	SAMPLE		PROJECT <b>Northshore Gas Waukegan Coke Plant</b>			LOCATION <b>Waukegan, IL.</b>			MAP OF <b>E</b> WALL OF PIT		
		TYPE AND NUMBER	INTERVAL	ELEVATION _____			CONTRACTOR <b>Kirshoffer</b>			DATE EXCAVATED <b>3/12/92</b>		
				WATER LEVEL AND DATE _____			EXCAVATION METHOD <b>B-Hoe</b>			LOGGER <b>JMF</b>		
				APPROXIMATE DIMENSIONS			LENGTH <b>48'</b> WIDTH <b>3-4'</b> DEPTH <b>5'</b>			REMARKS _____		

	0+00	0+10	0+20	0+30	0+40		COMMENTS
	NORTH					SOUTH	
0						<p>Spoon Test Location and Result:</p> <p>Oil Sheen Test: N=None, T=Trace, M=Moderate, H=Heavy</p> <p>Headspace Reading, ppm</p> <p>End of Trench @ 0 + 48S</p> <p>4" Stainless Steel Pipe In Wooden Box-Duct</p> <p>Tar, Tar in Pore Spaces of Soil</p> <p>Oil in Pore Spaces of Soil</p>	
1							
2							
3							
4							
5							
6							
7							
	LENGTH						

PROJECT NO. 13/49-003JSL		TEST PIT NO. TT-17		SHEET 1 OF 2		<b>TEST PIT WALL LOG</b>	
ELEVATION DEPTH BELOW SURFACE (Ft.)	SAMPLE		PROJECT <u>Northshore Gas Waukegan Coke Plant</u>		LOCATION <u>Waukegan, IL.</u>		MAP OF <u>SE</u> WALL OF PIT
	TYPE AND NUMBER	INTERVAL	ELEVATION _____		CONTRACTOR <u>Kirshoffer</u>		DATE EXCAVATED <u>3/12/92</u>
			WATER LEVEL AND DATE _____		EXCAVATION METHOD <u>B-Hoe</u>		LOGGER <u>JMF</u>
			APPROXIMATE DIMENSIONS		LENGTH <u>80'</u>	WIDTH <u>3-4'</u>	DEPTH <u>5-6'</u>

The diagram shows a cross-section of a test pit wall. The vertical axis on the left represents elevation/depth below surface in feet, ranging from 0 to 7. The horizontal axis at the top represents stationing from 0+00 to 0+40. The wall is labeled 'SOUTHWEST' on the left and 'NORTHEAST' on the right. Soil layers are identified with text labels and patterns: 
 

- Surface: Grass & Weeds at Surface
- Top layer (approx. 0.5 to 1.5 ft): Poorly Graded Sand (SP) - Pale Brown
- Layer below (approx. 1.5 to 2.5 ft): Poorly Graded Sand With Silt (SP-SM) Fine to Medium Grained, Discolored Black, Moist (Fill)
- Layer below (approx. 2.5 to 3.5 ft): Gravelly Sand (SP-GP); Fine to Coarse Grained, Dark Greyish Brown, (10YR 3/2) Moist (Fill) Composed 100% of Furnace Slag
- Layer below (approx. 3.5 to 4.5 ft): Silty Sand & Gravelly (SP-GP) Fine to Coarse Grained, Dark Grey. Brown (10YR 3/2) Moist (Fill)
- Layer below (approx. 4.5 to 5.5 ft): Poorly Graded Sand (SP) Not Excavated
- Layer below (approx. 5.5 to 6.5 ft): Lean Clay With Silt (CL/ML)
- Bottom layer (approx. 6.5 to 7.5 ft): Poorly Graded Sand (SP) Fine to Medium Grained, Black, Oily (Alluvium)
- Other features: Crushed Rock Base Material, Coal Fines, Mixed Demolition Debris, Cement, Poured Wall With Wood Forms In Place NE-SW Line, Olive Yellow (2.5Y 6/6) Moist (Alluvium), Poorly Graded Sand (SP).

COMMENTS

Spoon Test Location and Result:

Oil Sheen Test: N=None, T=Trace, M=Moderate, H=Heavy

M/10  
Headspace Reading, ppm

Tar, Tar in Pore Spaces of Soil  
 Oil in Pore Spaces of Soil

Poorly Graded Sand (SP), Fine to Medium Grained, Pale Brown (10YR) Moist, (Alluvium)

Heavy Rainbow Sheen On Groundwater

0+00 to 0+45 Groundwater May Be Confined Below Clay Layer

LENGTH

PROJECT NO. 13/49-003JSL		TEST PIT NO. TT-17		SHEET 2 OF 2		TEST PIT WALL LOG					
ELEVATION	DEPTH BELOW SURFACE (Ft.)	SAMPLE		PROJECT <u>Northshore Gas Waukegan Coke Plant</u>		LOCATION <u>Waukegan, IL.</u>					
		TYPE AND NUMBER	INTERVAL	ELEVATION _____		CONTRACTOR <u>Kirshoffer</u>					
				WATER LEVEL AND DATE _____		EXCAVATION METHOD <u>B-Hoe</u>					
				APPROXIMATE DIMENSIONS		DATE EXCAVATED <u>3/12/92</u>					
				LENGTH <u>80'</u>	WIDTH <u>3-4'</u>	DEPTH <u>5-6'</u>	REMARKS _____				
				<div style="display: flex; justify-content: space-between;"> <span>0+50</span> <span>0+60</span> <span>0+70</span> <span>0+80</span> <span>0+90</span> </div>							
				<div style="display: flex; justify-content: space-between;"> <span>SOUTHWEST</span> <span>NORTHEAST</span> </div>							
<div style="display: flex;"> <div style="writing-mode: vertical-rl; transform: rotate(180deg); text-align: center; margin-right: 5px;">           Match 1 of 2         </div> </div>				<div>             Spoon Test Location and Result:   </div>							
LENGTH											




[illegible]

PROJECT NO. 13/49-003JSL		TEST PIT NO. TT-19		SHEET 1 OF 2		TEST PIT WALL LOG		
ELEVATION	DEPTH BELOW SURFACE (Ft.)	SAMPLE		PROJECT Northshore Gas Waukegan Coke Plant		LOCATION Waukegan, IL.		MAP OF <u>W</u> WALL OF PIT
		TYPE AND NUMBER	INTERVAL	ELEVATION _____		CONTRACTOR Kirshoffer		DATE EXCAVATED 3/17/92
				WATER LEVEL AND DATE _____		EXCAVATION METHOD B-Hoe		LOGGER JMF
				APPROXIMATE DIMENSIONS		LENGTH 70'	WIDTH 3-4'	DEPTH 6'

	0+00	0+10	0+20	0+30	0+40	
	SOUTH			NORTH		
0	<p style="margin-top: 10px;">Silty Sand (SM) Fine Grained, Black (10YR) Moist (Fill) With Demolition Debris: Bricks Wood, Concrete, RR Ties, Timbers &amp; Chunks of Tar</p> <p style="margin-top: 10px;">Tar Solid With Slag</p> <p style="margin-top: 10px;">2" Stainless Steel Pipe E-W</p> <p style="margin-top: 10px;">Gravelly Sand (SP-GP) Medium Grained, Pale Brown (10YR 6/3) Moist (Fill)</p> <p style="margin-top: 10px;">Sandy Lean Clay (CL-SC) With Gravel, Greenish-Grey, Moist.</p> <p style="margin-top: 10px;">Poorly Graded Sand (SP) Fine To Medium Grained, Grey (10YR ), Wet (Alluvium)</p>					<p>Spoon Test Location and Result:</p> <p>(N) None</p> <p>(T) Trace</p> <p>(M) Moderate</p> <p>(H) Heavy</p> <p style="margin-top: 10px;">  Tar, Tar in Pore Spaces of Soil   Oil in Pore Spaces of Soil         </p> <p style="margin-top: 10px;">Heavy Rainbow Sheen on Groundwater</p>
1						
2						
3						
4						
5						
6						
7						
LENGTH						

PROJECT NO.		TEST PIT NO.		TEST PIT WALL LOG	
13/49-003JSL		TT-19		SHEET 2 OF 2	
PROJECT		LOCATION		MAP OF	
Northshore Gas Waukegan Coke Plant		Waukegan, IL.		W WALL OF PIT	
ELEVATION		CONTRACTOR		DATE EXCAVATED	
		Kirshoffer		3/17/92	
WATER LEVEL AND DATE		EXCAVATION METHOD		LOGGER	
		B-Hoe		JMF	
APPROXIMATE DIMENSIONS		LENGTH		REMARKS	
		70'		6'	
DEPTH BELOW SURFACE (Ft.)	SAMPLE TYPE AND NUMBER	INTERVAL	COMMENTS		
0			SOUTH		NORTH
0			Silty Sand (SM)- Fine Grained Black (10YR) Moist (Fill) With Demolition Debris: Bricks, Wood, Concrete, RR Ties, Timbers and Chunks of Tar		End of Trench @ 0+70N
1			Gravelly Sand (SP-GP) Medium Grained, Pale Brown (10yr 6/4) Moist (Fill)		
2			Tar-Solid Sandy Aggregate, With Some Tar Chunks		
3			Sandy Lean Clay (CL-SC) With Gravel, Greenish Grey Moist		
4			Poorly Graded Sand (SP) Fine to Medium Grained, Grey (10YR ), Wet (Alluvium)		
5			TT-19-01		
6					
7					
			LENGTH		



[illegible]

PROJECT NO. 13/49-003JSL			TEST PIT NO. TT-19W			SHEET 3 OF 4			<b>TEST PIT WALL LOG</b>		
ELEVATION	DEPTH BELOW SURFACE (Ft.)	SAMPLE		PROJECT <u>Northshore Gas Waukegan Coke Plant</u>			LOCATION <u>Waukegan, IL.</u>			MAP OF <u>S</u> WALL OF PIT	
		TYPE AND NUMBER	INTERVAL	ELEVATION _____			CONTRACTOR <u>Kirshoffer</u>			DATE EXCAVATED <u>3/20/92</u>	
				WATER LEVEL AND DATE _____			EXCAVATION METHOD <u>B-Hoe</u>			LOGGER <u>JMF</u>	
				APPROXIMATE DIMENSIONS			LENGTH <u>160'</u> WIDTH <u>3-4'</u> DEPTH <u>5-6'</u>			REMARKS _____	
				<div style="display: flex; justify-content: space-between;"> <span>0+90</span> <span>1+00</span> <span>1+10</span> <span>1+20</span> <span>1+30</span> </div> <div style="display: flex; justify-content: space-between;"> <span>EAST</span> <span></span> <span></span> <span></span> <span>WEST</span> </div>						COMMENTS	
				<div style="text-align: center;">Sand @ Surface</div> <div style="border: 1px solid black; padding: 5px; margin-top: 5px;"> Silty Sand (SM) Fine Grained, Black, Moist (Fill) </div> <div style="border: 1px solid black; padding: 5px; margin-top: 5px;"> Poorly Graded Sand W/Gravel (SP-GP)- Brown, 100% Furnace Clinkers moist (Fill) </div> <div style="border: 1px solid black; padding: 5px; margin-top: 5px;"> Poorly Graded Sand With Silt (SP-SM) Pale Yellowish Brown, Moist W/Demolition Debris </div> <div style="border: 1px solid black; padding: 5px; margin-top: 5px;"> Tar (Solid) </div> <div style="border: 1px solid black; padding: 5px; margin-top: 5px;"> Tar (Plastic) W/Furnace Slag </div> <div style="border: 1px solid black; padding: 5px; margin-top: 5px;"> Tar Saturated Sand (Plastic) </div> <div style="border: 1px solid black; padding: 5px; margin-top: 5px;"> Oily </div> <div style="border: 1px solid black; padding: 5px; margin-top: 5px;"> Poorly Graded Sand (SP) Fine Grained, Light Grey, Wet (Alluvium) </div> <div style="position: absolute; left: 10%; top: 40%; transform: rotate(-90deg); font-size: small;"> Match 2 of 4 </div> <div style="position: absolute; left: 25%; top: 35%;"> ○ 6" SS </div>						<div style="display: flex; flex-direction: column; align-items: flex-start;"> <div style="width: 20px; height: 20px; background-color: black; margin-bottom: 5px;"></div> Tar, Tar in Pore Spaces of Soil </div> <div style="display: flex; flex-direction: column; align-items: flex-start;"> <div style="width: 20px; height: 20px; border: 1px solid black; margin-bottom: 5px;"></div> Oil in Pore Spaces of Soil </div> <div style="margin-top: 20px;"> Groundwater @ 3.5-4.0' W/Heavy Oil Sheen and Oily Blebs </div>	
				LENGTH							

PROJECT NO. 13/49-003JSL		TEST PIT NO. TT-19W		SHEET 4 OF 4		<b>TEST PIT WALL LOG</b>	
ELEVATION	DEPTH BELOW SURFACE (Ft.)	SAMPLE		PROJECT <u>Northshore Gas Waukegan Coke Plant</u> LOCATION <u>Waukegan, IL.</u> MAP OF <u>S</u> WALL OF PIT			
		TYPE AND NUMBER	INTERVAL	ELEVATION _____ CONTRACTOR <u>Kirshoffer</u> DATE EXCAVATED <u>3/20/92</u>			
				WATER LEVEL AND DATE _____ EXCAVATION METHOD <u>B-Hoe</u> LOGGER <u>JMF</u>			
				APPROXIMATE DIMENSIONS LENGTH <u>160'</u> WIDTH <u>3-4'</u> DEPTH <u>5-6'</u> REMARKS _____			

	1+30	1+40	1+50	1+60	1+70	
	EAST			WEST		
0	<div style="display: flex; justify-content: space-between;"> <div> <p>Silty Sand (SM) Fine Grained, Black, Moist (Fill)</p> <p><b>Tar (Solid)</b></p> </div> <div> <p>Sand @ Surface</p> <p><b>Solid Tar @ Surface</b></p> <p>Concrete Slab</p> </div> </div>				<p>Spoon Test Location and Result:</p> <div style="border: 1px solid black; border-radius: 50%; width: 40px; height: 40px; margin: 10px auto; display: flex; align-items: center; justify-content: center;"> <div style="writing-mode: vertical-rl; transform: rotate(180deg);">M</div> <div style="margin: 0 5px;">/</div> <div>10</div> </div> <p>Oil Sheen Test: N=None, T=Trace, M=Moderate, H=Heavy</p> <p>Headspace Reading, ppm</p> <div style="display: flex; align-items: center;"> <div style="width: 20px; height: 20px; background-color: black; margin-right: 5px;"></div> <p>Tar, Tar in Pore Spaces of Soil</p> </div> <div style="display: flex; align-items: center;"> <div style="width: 20px; height: 20px; border: 1px solid black; margin-right: 5px;"></div> <p>Oil in Pore Spaces of Soil</p> </div> <p>Heavy Sheen On Groundwater W/ Oily Blebs</p>	
1						
2	<div style="display: flex; justify-content: space-between;"> <div> <p>Poorly Graded Sand W/Gravel (SP-GP), Brown, Moist Oily 100% Furnace Slag</p> <p><b>Tar (Plastic)</b></p> <p><b>Tar Saturated Sand</b></p> </div> <div> <p>TT-19W-01A</p> <p>TT-19W-03A</p> <p>TT-19W-02A</p> </div> </div>					
3						
4	<p>Poorly Graded Sand (SP) Fine Grained, Dark Grey, Wet (Alluvium)</p>					
5						
6						
7						
LENGTH						

PROJECT NO.

13/49-003JSL

TEST PIT NO.

TT-20

SHEET 1 OF 2

## TEST PIT WALL LOG

ELEVATION

DEPTH  
BELOW  
SURFACE (Ft.)

SAMPLE

TYPE AND  
NUMBER

INTERVAL

PROJECT Northshore Gas Waukegan Coke Plant

LOCATION Waukegan, IL.

MAP OF E WALL OF PIT

ELEVATION

CONTRACTOR Kirshoffer

DATE EXCAVATED 3/16/92

WATER LEVEL AND DATE

EXCAVATION METHOD B-Hoe

LOGGER JMF

APPROXIMATE DIMENSIONS

LENGTH 60'

WIDTH 3-4'

DEPTH 5 - 5.5'

REMARKS

0+00

0+10

0+20

0+30

0+40

SOUTH

Fence

Grass @ Surface

NORTH

0

Silty Sand (SM) Fine Grained, Pale Brown (10YR 6/3)

Poorly Graded Sand  
With Silt (SP-SM) Fine  
Grained, Dark Grey,  
Moist W/Demolition  
Debris: Bricks, Concrete  
Chunks of Coal Tar,  
Wood (Fill)

1

N

Poorly Graded Sand (SP)  
Fine to Medium Grained,  
Pale Brown (10YR 6/3)  
Moist (Fill)

2

N

Sand W/Coal Fines, Black (Fill),  
W/Chunks of Coal Tar

Tar

3

N

Lean Clay W/Sand (CL-SC)  
With a Trace of Gravel,  
Yellowish Brown (10YR 5/6),  
Moist (Fill)

TT-20-01

4

T

5

Poorly Graded Sand (SP)  
Fine Grained Grey (10YR 5/1),  
Wet (Alluvium)

6

7

LENGTH

## COMMENTS

Spoon Test Location  
and Result:

Oil Sheen Test: N=None,  
T=Trace, M=Moderate,  
H=Heavy

M/10

Headspace Reading, ppm

Spoon Test Location  
and Result:

N None

T Trace

M Moderate

H Heavy

Moderate Sheen on  
Groundwater Heavy  
Sheen @ 0+20

Tar, Tar in Pore  
Spaces of Soil

Oil in Pore Spaces  
of Soil



PROJECT NO.		TEST PIT NO.		SHEET 2 OF 2		TEST PIT WALL LOG	
13/49-003JSL		TT-20					
ELEVATION	DEPTH BELOW SURFACE (Ft.)	SAMPLE TYPE AND NUMBER	INTERVAL	PROJECT		LOCATION	
				Northshore Gas Waukegan Coke Plant		Waukegan, IL.	
				CONTRACTOR		Kishoffer	
				ELEVATION			
				WATER LEVEL AND DATE			
				APPROXIMATE DIMENSIONS		LENGTH 60' WIDTH 3-4' DEPTH 5 - 5.5'	
				EXCAVATION METHOD		B-Hoe	
				REMARKS		DATE EXCAVATED 3/16/92	
				LOGGER		JMF	
				MAP OF E		WALL OF PIT	
				<div style="display: flex; justify-content: space-between;"> <div> <p>Grass @ Surface</p> <p>Silty Sand (SM)- Fine, Pale Brown (10YR 6/3)</p> <p>Tar Aggregate- Solid W/Foundry Slag</p> <p>Foundry Slag Sand to Gravel Sized, Slight Oily Coating on Grains Below Tar</p> <p>Match 1 of 2</p> <p>TI-20-01</p> <p>Sandy Lean Clay (CL-SC) Yellowish-Brown, Moist (Fill)</p> <p>Poorly Graded Sand (SP) Fine Grained Grey (10YR 5/1), Wet (Alluvium)</p> </div> <div> <p>End of Trench @ 0 + 60'N</p> <p>Gravelly Sand (SP-GP) Medium Grained, Brown, Moist (Fill)</p> </div> </div>			
				<p>COMMENTS</p> <p>Spoon Test Location and Result:</p> <p>Oil Sheen Test: N=None, T=Trace, M=Moderate, H=Heavy</p> <p>Headspace Reading, ppm</p> <p>Oil in Pore Spaces of Soil</p> <p>Tar, Tar in Pore Spaces of Soil</p>			

PROJECT NO.

13/49-003JSL

TEST PIT NO.

TT-21

SHEET 1 OF 1

## TEST PIT WALL LOG

ELEVATION

DEPTH  
BELOW  
SURFACE (Ft.)

SAMPLE

TYPE AND  
NUMBER

INTERVAL

PROJECT Northshore Gas Waukegan Coke PlantLOCATION Waukegan, IL.MAP OF NE WALL OF PIT

ELEVATION

CONTRACTOR KirshofferDATE EXCAVATED 3/16/92

WATER LEVEL AND DATE

EXCAVATION METHOD B-HoeLOGGER JMF

APPROXIMATE DIMENSIONS

LENGTH 50'WIDTH 3-4'DEPTH 5-6'

REMARKS

0+00

0+10

0+40

0+50

SOUTHEAST

NORTHWEST

Grass @ Surface

Concrete

Silty Sand (SM) Fine  
Grained With a Trace  
of Gravel Pale Brown  
(10YR 6/3) Moist (Fill)

Coal Fines and  
Sand, Black, Moist  
(Fill)

Gravelly Sand (SP-GP)  
Medium Grained, Light  
Brownish Gray (10YR 6/2)  
Moist (Fill)

Lean Clay w/Sand (CL-SC)  
With a Trace of Gravel  
Yellowish Brown (10YR 5/6)  
Moist -Wet Below 4.5' (Fill)

TT-21-01

N  
0

Poorly Graded Sand (SP)  
Fine to Medium Grained  
Grey (10YR 5/1), Wet

3'

30'

Tar

T  
0

TT-21-02

Poorly Graded Sand (SP)  
Fine Grained, Brownish  
Grey (10YR) Wet Below  
4.0' (Alluvium)

1 1/2'

COMMENTS

End of Trench  
@ 0 +50' NW

Spoon Test Location  
and Result:

Oil Sheen Test: N=None,  
T=Trace, M=Moderate,  
H=Heavy

M  
10

Headspace Reading. ppm

■ Tar, Tar in Pore  
Spaces of Soil

□ Oil in Pore Spaces  
of Soil

Heavy Rainbow Sheen  
on Groundwater

LENGTH

PROJECT NO. 13/49-003JSL		TEST PIT NO. TT-22		SHEET 1 OF 2		TEST PIT WALL LOG	
ELEVATION	DEPTH BELOW SURFACE (Ft.)	SAMPLE		PROJECT <u>Northshore Gas Waukegan Coke Plant</u>		LOCATION <u>Waukegan, IL.</u>	
		TYPE AND NUMBER	INTERVAL	ELEVATION _____		CONTRACTOR <u>Kirshoffer</u>	
				WATER LEVEL AND DATE _____		EXCAVATION METHOD <u>B-Hoe</u>	
				APPROXIMATE DIMENSIONS		DATE EXCAVATED <u>3/12/92</u>	
				LENGTH <u>65'</u>		WIDTH <u>3-4'</u>	
				DEPTH <u>5'</u>		LOGGERS <u>JMF</u>	
				REMARKS _____			


  

		0+00	0+10	0+20	0+30	0+40	
		EAST				WEST	
0		Grass @ Surface					
1		Coal Fines					
2		Coal and Coal Fines					
3		100% Furnace Slag: Poorly Graded Sand With Gravel (SP-GP) Medium to Coarse Grained, Dark Brown					
4		Poorly Graded Sand (SP) Fine to Medium Grained, Pale Brown (10YR 6/3) Wet (Alluvium)					
5		Heavy Sheen on Groundwater 0+30 to 0+50					
6							
7							
		LENGTH					

PROJECT NO.		TEST PIT NO.		SHEET 2 OF 2		TEST PIT WALL LOG	
13/49-003JSL		TT-22		Northshore Gas Waukegan Coke Plant		LOCATION Waukegan, IL.	
PROJECT		ELEVATION		CONTRACTOR		MAP OF N WALL OF PIT	
Northshore Gas Waukegan Coke Plant		_____		Kishoffer		DATE EXCAVATED 3/12/92	
WATER LEVEL AND DATE		EXCAVATION METHOD		B-Hoe		LOGGER JMF	
APPROXIMATE DIMENSIONS		LENGTH 65' WIDTH 3-4'		DEPTH 5'		REMARKS	
0+40		0+50		0+60		0+70	
EAST		Grass @ Surface		WEST		End of Trench @ 0+65W	
0		Coal Fines		100% Furnace Slag (SP-GP)		Poorly Graded Sand (SP) Fine to Medium Grained, Pale Brown, Wet (Alluvium)	
1		JT-22-01		N 0.5		Spoon Test Location and Result:	
2						Oil Sheen Test: N=None, T=Trace, M=Moderate, H=Heavy	
3						M 10	
4						Headspace Reading, ppm	
5							
6							
7							
LENGTH							


PROJECT NO. 13/49-003JSL		TEST PIT NO. TT-22N		SHEET 1 OF 2		TEST PIT WALL LOG	
ELEVATION	DEPTH BELOW SURFACE (Ft.)	PROJECT <u>Northshore Gas Waukegan Coke Plant</u>		LOCATION <u>Waukegan, IL.</u>		MAP OF <u>W</u> WALL OF PIT	
		ELEVATION _____		CONTRACTOR <u>Kirshoffer</u>		DATE EXCAVATED <u>3/12/92</u>	
		WATER LEVEL AND DATE _____		EXCAVATION METHOD <u>B-Hoe</u>		LOGGER <u>JMF</u>	
		APPROXIMATE DIMENSIONS		LENGTH <u>60'</u> WIDTH <u>3-4'</u> DEPTH <u>5'</u>		REMARKS _____	
		TYPE AND NUMBER	INTERVAL	<p>The diagram shows a cross-section of Test Trench TT-22. The vertical axis represents depth below the surface in feet, ranging from 0 to 7. The horizontal axis represents the length of the trench, with markers at 0+00, 0+10, 0+20, 0+30, and 0+40. The trench is oriented SOUTH to NORTH. The soil profile is as follows:           <ul style="list-style-type: none"> <li>0 to 0.5 feet: Coal and Coal Fines</li> <li>0.5 to 1.5 feet: Furnace Slag (SP-GP)</li> <li>1.5 to 3.5 feet: Poorly Graded Sand (SP), Fine Grained, Light Brown, Moist (Fill)</li> <li>3.5 to 4.0 feet: Furnace Slag (SP-GP)</li> <li>4.0 to 5.0 feet: Poorly Graded Sand (SP), Fine to Medium Grained, Pale Brown (10YR 6/2), Wet (Alluvium)</li> </ul>           A dashed line at 3.5 feet depth indicates the groundwater level, labeled 'Moderate Sheen on Groundwater'. A 'Dike NW Corner' is noted at the 0+00 surface. The trench is labeled 'Test Trench TT-22' at the bottom.         </p>			
				LENGTH			

PROJECT NO. 13/49-003JSL		TEST PIT NO. TT-22N		SHEET 2 OF 2		TEST PIT WALL LOG	
ELEVATION	DEPTH BELOW SURFACE (F. )	SAMPLE		PROJECT <u>Northshore Gas Waukegan Coke Plant</u>		LOCATION <u>Waukegan, IL.</u>	
		TYPE AND NUMBER	INTERVAL	ELEVATION _____		CONTRACTOR <u>Kirshoffer</u>	
				WATER LEVEL AND DATE _____		DATE EXCAVATED <u>3/12/92</u>	
				APPROXIMATE DIMENSIONS		LOGGER <u>JMF</u>	
				LENGTH <u>60'</u>	WIDTH <u>3-4'</u>	DEPTH <u>5'</u>	REMARKS _____
				0+40                      0+50                      0+60		SOUTH                      NORTH	
0				<div style="display: flex; justify-content: space-between;"> <div style="width: 45%;"> <p>Poorly Graded Sand (SP) Fine Grained, Light Brown Moist (Fill)</p> <p>Coal and Coal Fines</p> <p>100% Furnace Slag Poorly Graded Gravel With Sand (SP-GP)</p> <p>Poorly Graded Sand (SP) Fine to Medium Grained Pale Brown (10YR 6/2) Wet (Alluvium)</p> </div> <div style="width: 50%; text-align: right;"> <p>End of Trench @ 0 +60' N</p> <p>TT-22N-01</p> </div> </div>		<p>Spoon Test Location and Result:</p> <p>Oil Sheen Test: N=None, T=Trace, M=Moderate, H=Heavy</p> <p>Headspace Reading, ppm</p>	
1							
2							
3							
4							
5							
6							
7							
				LENGTH			



PROJECT NO. 13/49-003JSL		TEST PIT NO. TT-00A		SHEET 1 OF 1		TEST PIT WALL LOG	
ELEVATION	DEPTH BELOW SURFACE (Ft.)	SAMPLE		PROJECT <u>Northshore Gas Waukegan Coke Plant</u>		LOCATION <u>Waukegan, IL.</u>	
		TYPE AND NUMBER	INTERVAL	ELEVATION _____		CONTRACTOR <u>Kirshoffer</u>	
				WATER LEVEL AND DATE _____		EXCAVATION METHOD <u>B-Hoe</u>	
				APPROXIMATE DIMENSIONS		DATE EXCAVATED <u>3/11/92</u>	
				LENGTH <u>22'</u> WIDTH <u>3-4'</u> DEPTH <u>4-5'</u>		LOGGER <u>JMF</u>	
				0+00 SOUTH		0+22 NORTH	
				Grass @ Surface		<div style="display: flex; justify-content: space-between;"> <div style="width: 40%;"> <p>Tar @ Surface</p> <p>Tar Black - Solid, Plastic</p> <p>Poorly Graded Sand (SP) Coarse Grained, White (10YR 8/2), Moist (Fill)</p> <p>Poorly Graded Sand (SP) Fine Grained, Black (10YR 2/1) Wet (Fill)</p> <p style="text-align: center;">▽</p> </div> <div style="width: 40%;"> <p>Silty Sand (SM) Fine Grained, Black (10 YR 2/1) Moist (Fill) W/Steel Braided Cables, Wood, Bricks</p> </div> </div> <div style="margin-top: 20px;"> <div style="display: inline-block; width: 20px; height: 20px; background-color: black; margin-right: 5px;"></div> Tar, Tar in Pore Spaces of Soil <div style="display: inline-block; width: 20px; height: 20px; background: repeating-linear-gradient(45deg, transparent, transparent 2px, black 2px, black 4px); margin-right: 5px;"></div> Oil in Pore Spaces of Soil </div>	
				2'			
				LENGTH			





PROJECT NO.

13/49-003JSL

TEST PIT NO.

TT-00C

SHEET 2 OF 3

## TEST PIT WALL LOG

ELEVATION

DEPTH  
BELOW  
SURFACE (Ft.)

SAMPLE

TYPE AND  
NUMBER

INTERVAL

PROJECT Northshore Gas Waukegan Coke Plant

LOCATION Waukegan, IL.

MAP OF SE WALL OF PIT

ELEVATION

CONTRACTOR Kirshoffer

DATE EXCAVATED 3/20/92

WATER LEVEL AND DATE

EXCAVATION METHOD B-Hoe

LOGGER JMF

APPROXIMATE DIMENSIONS

LENGTH 100'

WIDTH 3-4'

DEPTH 4-6'

REMARKS

0+40

0+50

0+60

0+70

0+80

NORTHEAST

SOUTHWEST

COMMENTS

Spoon Test Location  
and Result:Oil Sheen Test: N=None,  
T=Trace, M=Moderate,  
H=HeavyM  
10

Headspace Reading, ppm

Tar, Tar in Pore  
Spaces of SoilOil in Pore Spaces  
of SoilHeavy Sheen on  
Groundwater With  
Golden-Brown Oily  
BlebsSilty Sand (SM) Fine Grained,  
Very Dark Grey, Moist (Fill)

Tar Saturated Sand W/Demolition Debris

Tar (Solid)

100% Furnace Slag:  
Poorly Graded Gravel  
With Sand (GP-SP) Fine  
to Medium Grained, Very  
Dark Grey, Moist (Fill)Oil Saturated Furnace Slag  
W/Demolition DebrisPoorly Graded Sand (SP)  
Fine to Medium Grained,  
Grey, Wet (Alluvium), Oil  
Saturated

TT-00C-02

Match 1 of 3

LENGTH


PROJECT NO. 13/49-003JSL			TEST PIT NO. TT-00C			SHEET 3 OF 3			<b>TEST PIT WALL LOG</b>			
ELEVATION	DEPTH BELOW SURFACE (Ft.)	SAMPLE		PROJECT <u>Northshore Gas Waukegan Coke Plant</u>			LOCATION <u>Waukegan, IL.</u>			MAP OF <u>SE</u> WALL OF PIT		
		TYPE AND NUMBER	INTERVAL	ELEVATION _____			CONTRACTOR <u>Kirshoffer</u>			DATE EXCAVATED <u>3/20/92</u>		
				WATER LEVEL AND DATE _____			EXCAVATION METHOD <u>B-Hoe</u>			LOGGER <u>JMF</u>		
				APPROXIMATE DIMENSIONS			LENGTH <u>100'</u> WIDTH <u>3-4'</u> DEPTH <u>4-6'</u>			REMARKS _____		

	0+80	0+90	1+00	1+10	1+20	
	NORTHEAST			SOUTHWEST		COMMENTS
0	<div style="position: relative; height: 400px;"> <div style="position: absolute; top: 10px; left: 10px; border: 1px solid black; padding: 5px;">Silty Sand (SM) Fine Grained, Very Dark Grey, Moist (Fill)</div> <div style="position: absolute; top: 100px; left: 10px; border: 1px solid black; padding: 5px;">100% Furnace Slag: Poorly Graded Gravel With Sand (GP-SP) Fine to Medium Grained, Very Dark Grey, Moist (Fill)</div> <div style="position: absolute; top: 380px; left: 10px; border: 1px solid black; padding: 5px;">Poorly Graded Sand (SP)- Fine to Medium Grained, Grey, Wet (Alluvium), Oil Saturated</div> <div style="position: absolute; top: 150px; left: 150px; transform: rotate(-90deg); font-size: small;">Match 2 of 3</div> <div style="position: absolute; top: 300px; left: 400px;">End of Trench @ 1+00SW</div> </div>					
1						
2						
3						
4						
5						
6						
7						
	LENGTH					

- Tar, Tar in Pore Spaces of Soil
- Oil in Pore Spaces of Soil

Heavy Sheen on  
Groundwater With  
Brown Oily Blebs



PROJECT NO.		TEST PIT NO.		TEST PIT WALL LOG	
13/49-003JSL		TT-00D		SHEET 2 OF 3	
DEPTH BELOW SURFACE (Ft.)	SAMPLE		PROJECT Northshore Gas Waukegan Coke Plant		
	TYPE AND NUMBER	INTERVAL	LOCATION Waukegan, IL.		
			MAP OF W WALL OF PIT		
			ELEVATION _____ CONTRACTOR Kirshoffer		
			DATE EXCAVATED 3/20/92		
			WATER LEVEL AND DATE _____ EXCAVATION METHOD B-Hoe		
			LOGGER JMF		
			APPROXIMATE DIMENSIONS LENGTH 100' WIDTH 3-4' DEPTH 5'		
			REMARKS		
			<div style="display: flex; justify-content: space-between;"> <span>0+40</span> <span>0+50</span> <span>0+60</span> <span>0+70</span> <span>0+80</span> </div> <div style="display: flex; justify-content: space-between;"> <span>NORTH</span> <span>SOUTH</span> </div>		
			<div style="display: flex; justify-content: space-between;"> <span>0+40</span> <span>0+50</span> <span>0+60</span> <span>0+70</span> <span>0+80</span> </div> <div style="display: flex; justify-content: space-between;"> <span>NORTH</span> <span>SOUTH</span> </div>		

PROJECT NO.		TEST PIT NO.		TEST PIT WALL LOG					
13/49-003JSL		TT-00D		SHEET 3 OF 3					
ELEVATION	DEPTH BELOW SURFACE (Ft.)	SAMPLE		PROJECT		LOCATION		MAP OF	
		TYPE AND NUMBER	INTERVAL					W	WALL OF PIT
				Northshore Gas Waukegan Coke Plant		Waukegan, IL.		DATE EXCAVATED 3/20/92	
				CONTRACTOR Kirshoffer		EXCAVATION METHOD B-Hoe		LOGGER JMF	
				APPROXIMATE DIMENSIONS LENGTH 100' WIDTH 3-4' DEPTH 5'		REMARKS			
				0+80		0+90		1+00	
				NORTH		SOUTH			
0				Poorly Graded Sand (SP) Fine to Medium Grained, Dark Grey Moist (Alluvium)					
1				100% Furnace Slag: Poorly Graded Gravel With Sand (GP-SP) Fine to Medium Grained, Dark Grey, Moist (Fill)					
2				Tar Saturated Slag					
3				Tar Saturated Sand					
4				Poorly Graded Sand (SP) Fine to Medium Grained, Grey Wet (Alluvium)					
5									
6									
7									
				LENGTH					

## ***Appendix B***

### ***Survey Notes***

TABLE B-1

WAUKEGAN MANUFACTURED GAS AND COKE PLANT  
August 20, 1992

Soil Samples	Elevation	Location Coordinates		Survey Book Page
		North	East	
SS-01	585.4	4971.8	5553.3	26
SS-02	585.3	4920.5	5392.1	4/40
SS-03	585.5	4934.9	5206.2	4/40
SS-04	584.8	4737.9	5064.3	4/40
SS-05	584.6	4740.8	5266.9	4/40
SS-06	585.8	4733.2	5529.7	28
SS-07	584.7	4727.4	5665.5	27
SS-08	585.5	4527.0	5627.6	27
SS-09	586.9	4348.0	5505.0	27
SS-10	585.8	4176.9	5363.0	28
SS-11	585.6	4047.1	5235.5	32
SS-12	583.9	3835.7	5001.2	32
SS-13	585.1	3840.3	5193.6	32
SS-14	585.2	3788.1	5389.9	30
SS-15	585.4	3647.0	5272.4	33
SS-16	585.2	3649.8	5075.4	33
SS-17	585.1	3653.1	4865.6	33
SC-01	584.4	3599.4	5600.9	33
SC-02	585.8	4263.4	5828.9	33
BS-06	586.3	5146.6	4955.6	36
BS-07	584.8	5128.7	5525.8	36
BS-08	585.6	5444.6	6198.8	37
SB-03	585.9	4975.8	5528.3	41



WAUKEGAN MANUFACTURED GAS AND COKE PLANT  
August 20, 1992

Monitoring Well	Elevation			Location Coordinates		Survey Book Page
	Ground	Casing	Riser	North	East	
MW-3D	585.5	588.23	588.23	4961.8	5552.0	21/26
MW-3S	585.2	588.31	588.24	4971.8	5553.3	21/26
MW-4D	586.1	589.07	589.06	4118.3	5874.1	34/39
MW-4S	586.2	589.29	589.17	4109.5	5870.6	34/39
MW-5D	585.7	588.49	588.47	3807.9	4811.6	22/32
MW-5S	585.4	587.91	587.89	3802.6	4811.1	23/32
MW-6D	585.7	588.56	588.51	4442.1	4921.0	23/28
MW-6S	585.7	588.48	588.45	4431.7	4920.3	23/28
P-101	585.0	588.21	588.14	4994.2	5036.0	36/41
P-102	585.6	588.57	588.52	4963.9	5958.3	21/26
P-103	586.4	589.47	589.44	4004.9	5467.3	29/39
P-104	586.0	589.10	589.07	4499.9	5574.5	22/27
Existing 1D	585.8	587.74	587.62	4412.7	5326.1	6/24
Existing 1S	586.0	587.83	587.76	4418.1	5328.4	6/24

Bench Mark (BM): "X" on seawall northwest corner of slip at Larson Marine, 7 feet east of and 41 feet south of Larson Marine storage building.

EL. Given = 584.65

Coordinate: 4675N, 4939E

BM was established by Mid America Survey Company in 1988 for Canonie and Hi Tech.

Elevations are USGS mean sea level datum elevations.

WAUKEGAN

COKE  
PLANT

①

RI/FS

 TELEDYNE

400  
LEVEL BOOK

NOTE:

REVISED NAME

AUGUST 26, 1992

PAGES 25 & 38

WAUKEGAN

COKE ~~HARBOR~~ ~~PLANT~~

DATE: FEB <sup>25</sup> 24, 1992

WEATHER: CLOUDY COLD 35°/CHANCE RAIN

CREW: DERRICK MITCHELL

JIM STABERG

~~STEVE M~~

INST: LIETZ TOTAL STATION SET

- PURPOSE:
- 1) SET BASELINE & CONTROL
  - 2) LOCATE SOIL BORING
  - 3) LOCATE TEST TRENCH
  - 4) LOCATE EXISTING & PROPOSED MONITORING WELLS



Pt NO	NORTHING	EASTING	VERT DIST	HT ROD	ELEV	DESCRIPTION	②
1	5000.0	5475	-	-	-	SET-UP POINT A (PROPERTY)	
2	4921.33	5475	-	-	-	BACK SIGHT B (PROPERTY LINE)	
3	-	-	-	-	-	BM =	
4	6067.0	4862.9	-	-	-	CHECK NW COR BEACH HOUSE	
5	6059.5	4809.5	-	-	-	CHECK SW " " " "	
6	-	-	-	-	-	1-1/2" D C 495.02 (SET 1)	
7	5975.7	4936.7	-	-	-	TEST TRENCH TT-1	
8	5806.5	4874.6	-	-	-	" " TT-1	
9	5923.9	4580.3	-	-	-	" " TT-2	
10	5795.8	4712.1	-	-	-	" " TT-2	
11	5600.3	4918.1	-	-	-	Soil Boring SB-1	
12	5665.6	4727.5	-	-	-	" " SB-7	
13	-	-	-	-	-		
14	-	-	-	-	-		
15	-	-	-	-	-		
16	-	-	-	-	-		
17	-	-	-	-	-		

[illegible]

MAKING

ERASING

④

DESCRIPTION

XC BINT HERON 5600E

BACKSIGHT : NORTH

SB-1 HUB - PINK PIPERU LATH

SB-2

SB-3

SB-4

SB-5

SB-6

SB-7

SB-8

SB-9

SB-10

SB-11

SB-12

1. 4918.1 5602.3

2. 4920.5 5392.1

3. 4934.9 5206.2

4. 4737.9 5064.3

5. 4740.8 5216.9

6. 4736.3 5460.6

7. 4727.5 5665.6

8. 4528.1 5627.8

9. 4350.2 5503.6

10. 4175.1 5317.3

11. 4046.4 5233.3

12. 3835.0 4999.9

	NORTHING	EASTING	H. DIST	DESCRIPTION	(S)
(12)	3840.3	5193.7		SB-13	100' PINK RIBBON LATH
(14)	3785.9	5390.1		SB-14	" " " "
(15)	3646.9	5270.9		SB-15	" " " "
(16)	3650.0	5095.1 (PK)	PAINTED ORANGE	SB-16	" " " "
(17)	3653.1	4865.8 (PK)	via yellow parking line. hard to see. 4th still from end.	SB-17	" " " "
(18)	4972.7	5036.1	★ SET UNDER FEET OF BOAT (PAINTED HUB)	P-101	BLUE RIBBON LATH
(19)	4962.9	5158.4	MARK ON FENCE APPROX LOCATION 27' S	P-102	" " " "
(19A)	4005.2	5467.6		P-103	" " " "
(19B)	4498.9	5574.1		P-104	" " " "
(20)	4969.9	5530.0		MW-30	BLUE RIBBON LATH
(21)	4768.8	5560.8		MW-35	" " " "
(22)	4139.5	5879.1		MW-40	" " " "
(23)	4109.4	5870.7		MW-45	" " " "
(24)	3842.4	4835.8		MW-50	" " " "
(25)	3872.5	4846.2		MW-55	" " " "



	WEAVING	ENDING			DESCRIPTION	
	4408.10	4921.5				⑥
	4442.106	5326.14				
26	4408.1	4924.5			44	
	4448.09	5228.51			MW - 6 D	44B BLUE ORGAN CATH
27	4444.0	4929.7			MW - 6 S	" " "
	4441.0	4929.7				
28	4418.09	5328.39				
29	4412.16	5326.14				
					WEAVING	
30	4936.7	5915.65			WEAVING	
	4712.1	5755.8			WEAVING	
31	4712.1	5755.8			WEAVING	
32	44520.7	5719.1			WEAVING	
	44537.6	5553.8			WEAVING	
33	44537.6	5553.8			WEAVING	
34	44516.4	5295.5			WEAVING	
	4488.6	4962.8			WEAVING	
35	4488.6	4962.8			WEAVING	
36	4272.5	5643.7			WEAVING	
	4152.8	5613.0			WEAVING	
37	4152.8	5613.0			WEAVING	
38	4201.1	5500.9			WEAVING	
	4093.1	5648.9			WEAVING	
39	4093.1	5648.9			WEAVING	

WEAVING

WEAVING

2

3

4

5

6

7

8

9

10

⑥

7

NORTHING EASTING

DESCRIPTION

CORNER OF 9" C" WIRE  
END OF FENCE 9 PIER

LOCATED

CORNER

FENCE

9" C" WIRE

2-27-92

40 4453.5 4899.0

41 4474.9 5177.1

42 4499.0 5175.2

43 4013.6 5647.3 3976.4 5646.6

44 4019.9 5584.3 3996.3 5549.7

45 4022.5 5492.5 4021.0 5443.5

46 3957.0 5630.3 3915.4 5578.8

47 3887.6 5638.5 3873.3 5567.5

48 3952.3 5411.7 3952.3 5400.1

49 3957.5 5387.9 3909.1 5333.7

50 3768.8 5626.5 3765.1 5602.3

51 3797.3 5579.1 3732.4 5555.9

52 3738.1 5601.0 3674.9 5585.8 (PK.) \*

53 3726.3 5537.8 3682.1 5570.7

54 3847.3 5344.8 3845.6 5284.1

TEST TRENCH -

11

12

13

14

15

16

17

18

19

20

21

22

NORTHING EASTING

⑧  
2-27-72

55

3973.6

5562.2

3930.3

5548.6

TEST TRENCH - 23

LOCATION OF TRAILERS ON SITE

4194.4 5677.4

NW CORNER

4194.3 5701.0

NE "

4134.0 5676.7

SW "

4067.2 5653.7

+

+

NE CORNER

4167.1 5625.3

NW "

4158.9 5625.4

SW "

4150.5 5608.5

NW CORNER

4138.6 5608.6

SW "

4151.0 5654.8

NE "

[illegible]

(10)

• Set 90° - 50' ⑤ Hubs  
FROM 88-23 W/ Right angle glass  
• Set one 100' ⑤ 174.0  
ON LINE W/ ⑤ 50' south  
• Levels on all hubs  
TBM = SOUTH 50' ⑤

3-5-9

OVERCAST 400 LINE RAIN

JMF

Paul Dickenson (WTD)

②

(12)

3/26/92

JMF, WWM/TWW

RUN LEVEL LOOP

OF WELLS & PIEZOMETERS

Bm @ NORTH SIDE OF

LARSEN SLIP. ———

"X" in LARSEN ON

SEEWALL.

40° RAIN GREY

HAIL, SUNNY (5min.),

Sleet, more RAIN.

HEAVY SNOW WITH

accumulation.

well & piez: <sup>P-101,</sup> MW-6S, MW-6D,

MW-1 NORTH, MW-1 SOUTH, P-104,

P-102, MW-3S, MW-3D,

P-103, MW-4S, MW-4D.

	HI	BS	FS	ELEV.					(13)
BM	589.42	4.77		584.65	"X" ON SEAWALL	C	CARSEN		
TP			5.24	(584.18)					
BS	589.58	5.40							
TP			4.98	584.6					
BS	589.73	5.13							
TP			4.84	584.59					
BS	590.09	5.20							
P-101		<del>5.20</del>	5.1	(585.0) 584.99	GROUND				
P-101			1.89	588.20	TOR	=	TP		
BS	590.05	1.85							
TP			5.41	584.64					
BS	589.26	4.62							
TP			5.05	584.21					
BS	589.21	5.00							
BM			4.53	584.68					
Loop Error =			0.03						



(14)

	HI	BS	FS	ELEV	
BM	589.89	5.24		584.65	"X" ON SEAWALK - @ CAMDEN
MW-65			4.1	585.79	GROUND
MW-65			1.42	586.47	TOR
BS	590.13	1.66			SAA - Leg Kick
MW-60			4.4	585.73	Ground
MW-60			1.61	588.52	TOR
BM			5.49	594.64	"X" SAG
Loop Error =				0.01	
MW-65	589.97	1.50		588.47	TOR - TBm
MW-1			3.8	586.17	Ground
MW-1			2.31	587.66 ✓	TOR } South well
BS MW-1	590.46	2.80			<del>GROUND</del> } SAA
MW-1			4.5	585.96 ✓	GROUND } North well
MW-1			2.67	587.79 ✓	TOR }
BS	591.24	3.45			
P-104			5.2	586.04	Ground
P-104			2.13	589.11	TOR

(15)

HT	BS	FS	ELEV				
BS	590.21				P-104 TOR		
TP		5.24	584.97		RANDOM PT.		
BS	590.95				↓		
P-102		5.4	585.55		Ground		
P-102		2.39	588.56		TOR		
BS	591.50				↓		
MW-38		6.3			Ground		
MW-38		3.21	588.29		TOR		
BS	590.60				↓		
MW-31		5.3					
MW-31		2.39	588.27				
BS	590.60						
TP		5.29	585.31		© 53-6		
BS	590.21				↓		
TP		5.44	584.77		RANDOM PT.		
BS	589.50						
TP		5.04	584.46				
BS	590.09						
BS	590.09						

HI	BS	FS	ELEV	"X" ON SEA WALL @ CURVED	(16)
BM		5.47	584.62		584.65
(Loop Error .03)					
BM	589.50	4.85	584.65	SAA	
		4.98	584.52	H2O Measurement Point	
BM		4.85		(15' W of BM)	
				H2O @ 4.49	
				Below PT	
				3726142 230 PM	
				584.52	
				4.49	
				(580.03)	
				= H2O	
				in road	
				scrip.	

	HI	BS	FS	ELEV		(17)
TBM	591.93	4.14		587.79	MW-1 (NORTH)	
P+103			5.3		GROUND	
P-103			2.45	589.48	TOR	
BS	592.02	2.54			↓	
TBM			4.21	587.78	SAA	
<u>Loop Error = 0.01</u>						
TBM	589.40	2.32		587.48	TOR @ P-103	
MW-4S		5.12	5.5	-	GROUND	
MW-FS		2.	2.57	587.23	TOR	
BS	589.19	1.96			↓	
MW-AD			5.1		GROUND	
MW-AD			2.03	587.16	TOR	
TBM			1.72	587.47	SAA P-103 TORL	
<u>I Loop Error = 0.01</u>						

(18)

3/27/92

JMF / TWW

Level Loop ON  
wells & DIETOMENTS

Including:

MW-SS, MW-SD

P-Cloudy 30°

WINDY.

	HI	BS	FS	ELEV.	TOR	P-103
TBM	589.58	2.10		587.48		
TP			6.54	583.04	RANDOM PT	
BS	587.57	4.53				
<del>TP</del>						
<del>BS</del>						
MW-5D			3.9		GROUND	
MW-5D			1.04	586.53	RISE	
BS-	587.83	1.30			LEG KICK	
MW-5S			4.5		GROUND	
MW-5S			1.89	585.94	RISE	
BS	587.68	1.74			LEG KICK	
TP			4.65	583.03	RANDOM PT.	
BS	588.96	5.43				
TBM			1.36	587.50	TOR P-103	
Loop Error =	0.02					

# RENTAL EQUIPMENT:

INSTRUMENT : TOPCON GTS 3C

HIGHT PRISM: DOWN = 4.91

1 UP = 8.65

2 UP = 12.50

LEVEL = AT-F2

WALKEGAN HARBOR TRUST

4-14-92

J. Shabazz

Over count

D. Mitchell

40°

10-15 mph

1) RAW LEVEL LOOP ON-SITE:

MW-3S, MW-3D, MW-6S, MW-6D,

MW-5S, MW-5D, P-102, P-104

~~4-14-92~~

THIS WILL INSTALL MSL ELEVATION

at a later date.

(20)

+	HI	-	ELEV	LEVEL	LOOP	INTS ON SITE MW	(21)
						INTS ON SITE MW	4-14-72
						ELUATIONS ON MW-3D RISER IS ON PAGE 41	
						REVENTION = 588.23	
2.21	590.44		588.23		MW-3D	2" STEEL RISER	
		4.9	585.5		GRO.		
		2.21	588.23		CASING		
		5.2	585.2		GRO.	MW-3S	
		2.13	588.31		CASING	"	
		2.20	588.24		RISER	" (2" STEEL RISER)	
3.345	591.59						
		6.0	585.6		GRO.	P-102	
		3.02	588.57		CASING	"	
		3.07	588.52		RISER	" (PVC 1 1/4" RISER)	
2.411	590.96						
		5.545	585.41		SPK. 9	4700N SLOOE (P649)	
5.63	591.06						



(22)

4-14-92

	+	#1	-	ELEV	LEVEL	LAST	
		591.06					
			5'-	586.0	GRD	P-1011-	
			1'-	589.16	CASING	"	
			1'-	589.07	RISER	"	(1 1/4" PVC RISER)
TP4	193	591.00					
			5'-25	585.75	SPK	STR	4500N 5600E
TP5	623	591.98					
			5'-51	586.47	SPK	STR	3950N 5600E (RENT)
TP6	417	590.64					
			2'-15	588.19	NE COR. OF	4' X 4' CONC. SLAB	HOLDING
TP7	098	589.47			TENEE	4' X 4' CONC. SLAB	
			3'-2	585.7	GRD	HW-5D	
			1'-56	588.49	CASING	"	
			1'-	588.47	RISER	"	(2" STEEL)
TP8	070	589.17					



(24)

4-14-92

	+	HI	-	ELEV		LEVEL	LOOP	CONT.	
		591.14							
			5.3	585.8		GRO.		MW-1 D	
			3.40	587.74		CASING		MOST SOUTHERLY (EXISTING)	
TP13			3.52	587.62		RISER		"	(2" STEEL)
	3.36	590.98							
			5.0	586.0		GRO		MW-1 S	
			3.15	587.83		CASING		MOST NORTHERLY / OF 2	
TP14			3.22	587.76		RISER		"	(2" STEEL)
	4.01	591.83							
TP15			6.41	585.42	585.42	SPL 9	STA	4" DRAIN SADDON	(TP3)
	4.78	590.20							
TP16			1.965	588.23	588.23	RISER	MW-3 D	✓	

(25)

CORE PLANT R1 / FS  
42M cells CAN ~~42M cells CAN~~

4-15-92  
(Tax Day!!)

J. S. Hubbard  
D. Mitchell

	50°	containing	from surface
--	-----	------------	--------------

5-10 MPH

1) location of on site - T.1 trenching  
Boring, wells & Piezometer.

2) Location of off-sites  $\overline{P}_{\text{off-sites}}$  and wells. Also BMs.

TG 4500 SLOPE BS: NORTH T-R 4/15/92									
CONCRETE									
NO.	EST	ADJUSTING	CONCRETE	DESCRIPTION	LOCATION	VDIST	REMARKS	ELEV	
1	0	0	4500	ON-SITE	5.50	HI=591.25	(PG.22)	585.75	
2	200	0	4700	BS 4500 SLOPE	4.90	"	(PG.24)	585.42	
3	335.7	50.4	4836	BS 4700 SLOPE	-1.5	"	"	584.9	
4	301	5.0	4801	TT-00B	-1.5	"	"	584.9	
5	420	-1.0	4920.0	SS-1	-1.0	"	"	585.4	
6	461.8	-48.0	4961.8	MW-30	-0.7	"	"	85.7	
7	471.8	-46.7	4971.8	MW-35	2.8	8.65	"	85.4	
8	362.6	178.3	4863	TT-1	-0.9	4.70	"	85.5	
9	437.2	375	4937	TT-1	-0.9	"	"	85.5	
10	463.9	358.3	4963.9	P-102	-0.7	"	"	85.7	
11	269	179	4769	TT-00A	-1.3	"	"	85.1	
12	243	186	4743	TT-00A	-1.3	"	"	85.1	
13	274	160.3	4774	LATH WITH TIDE MARKED	-1.5	"	"	84.9	
14	289	154	4654	DANGER AREA	-1.3	"	"	85.1	
15	297	140	4797	"	-1.3	"	"	85.1	
16	276	141	4776	"	-1.2	"	"	85.2	

	NORTH	EAST	NORTHING	EASTING	DESCRIPTION	LOCATION	Y. DIST	4-15-72	(27) PREVIOUS ELEV.
17	226	189	4726	5789	TT-2		-1.6	4.90	84.8
18	88	317	4588	5917	TT-2		-1.8	"	84.6
19	-4.0	243	4496	5843	BARRELS (10)		-1.1	"	85.3
20	-18	244	4482	5844	"		-1.0	"	85.4
21	-20	238	4480	5838	"		-1.0	"	85.4
22	-3.0	233	4497	5833	"		-1.2	"	85.2
23	37	119	4537	5719	TT-3		-1.4	"	85.0
24	-153	118	4347	5718	TT-3		-1.0	"	85.4
25	-103	125	4397	5725	TT-03W		-1.1	"	85.3
26	-79	-97	4421	5503	TT-03W		0.1	"	86.5
27	-152	-95	43480	5505.0	SS-9		0.5	"	86.9
28	-0.1	-25.5	4499.9	5574.5	P-104		-0.2	"	86.2
29	7.4	-81	4507	5519	TT-4		0.3	"	86.7
30	43	-35	4513	5565	TT-4		-0.1	"	86.3
31	27	27.6	4527	5627.6	SS-B		-0.9	"	85.5
32	227.4	65.5	4727.4	5665.5	SS-7		-1.7	"	84.7

[illegible]

	NORTH	EAST	NORTHING	EASTING	DESCRIPTION	VDIST	PRISM	ELEV
					ON SITE LOCATIONS			
48	-478.0	-106.1	4022	5494	TT-13	0.2	4.90	86.6
49	-464.0	-176	4036	5424	TT-13	-0.0	"	86.4
50	-495.1	-132.7	4049	5467.3	P-103	0.4	"	86.8
51	-570	-50	3930	5550	TT-23	-0.7	"	85.7
52	-524	-37	3976	5563	TT-23	-0.6	"	85.8
53	-510	-62	3982	5538	TT-12	-0.3	"	86.1
54	-482	-16	4018	5584	TT-12	0.1	"	86.5
55	-584	-21	3916	1684	TT-14	-0.7	"	85.7
56	-628	-35	3872	5565	TT-15	-0.5	"	85.9
57	-548	-188	3952	5412	TT-16	-0.2	"	86.2
58	-595	-202	3905	5398	TT-16	-0.8	"	85.6
59	-591	-266	3909	5334	TT-17	-0.6	"	85.8
60	-537	-208	3963	5392	TT-17	0.0	"	86.4
61	-653	-255	3847	5345	TT-22	-1.1	"	85.3
62	-655	-323	4179	5277	TT-22	-1.1	"	85.3

(27)

4-15-92



NORTH	EAST	NORTHING	EASTING	DESCRIPTION	V. DIST.	P.O.S. IN	ELEV	4-15-92	(30)
13	-609	-301	3891	5299	TT-22N	0.0	4.90	86.4	
14	-662	-298	3838	5302	TT-22N	-0.8	"	85.6	
15	-711.9	-210.1	3788.1	5389.9	SS-14	-1.5	"	84.9	
16	-682	-179	3818	5421	TT-00D	-1.2	"	85.2	
17	-792	-188	3908	5412	TT-00D	-1.5	"	84.9	
18	-682	-179	3818	5421	TT-19W	-1.1	"	85.3	
19	-723	-28	3777	5572	TT-19W	-0.4	"	86.0	
20	-698	-19	3802	5581	TT-19	-0.2	"	86.2	
21	-767	-43	3733	5557	TT-19	-0.1	"	86.3	
22	-773	-62	3727	5538	TT-21	-0.9	"	85.5	
23	-782	-53	3718	5547	TT-21	0.1	"	86.5	
24	-810	-35	3680	5565	TT-24	-0.2	"	86.2	
25	-818	-29	3682	5571	TT-24	-1.1	"	85.3	
26	-817	-12	3683	5588	TT-20	0.1	"	86.5	
27	-808	-0.5	3700	5600	STK 3700N 5600E	0.2	"	86.6	
28	-761	5.0	3739	5605	TT-20	-0.1	"	86.3	

	WENT	EAST	NORTHING	EASTING	DESCRIPTION	V. DIST	PERIOD	ELEV
71	-292	71	4208	5671	TT-108A	-0.8	4901	85.6
80	-298	24	4202	5624	TT-8A	-0.1	"	86.3
81	6.0	-315	4500	5285	SAT CARTON AUG 9	-0.9	"	85.5
					STA. 4500N 5285E			

T9 500N 500E BS: NORTH				T-R		4/15-92		(32)
DESCRIPTION				Y-DIST		PEAK		REV
				Locating		HI = 591.58		
1	7	—	5600	T9 500N 500E (SPK)	5.2	—	586.36	(PG. 22)
2	700	0	4500	TBM / BS: 4500N 500E (SPK)	2.82	8.65	585.75	
3	403	-99	4203	TT-9	0.5	4.90	87.2	
4	334	-115	4134	TT-9	0.1	"	86.8	
5	214	48	4014	TT-11	-0.4	"	86.3	
6	163	43	3963	TT-11	-0.3	"	86.4	
7	101	92	3901	TT-15	0.0	"	86.7	
8	-31	26	3769	TT-18	-0.2	"	86.5	
9	-24	-29	3776	TT-18	-0.7	"	86.0	
10	163	34	3963	TT-14	-0.2	"	86.5	
11	40.3	-406.4	3846.3	SS-13	-1.6	"	85.1	
12	35.7	-598.8	3835.7	SS-12	1.0	8.65	83.9	
13	2.6	-788.4	3802.6	MW-55	2.7	8.65	85.6	
14	7.9	-788.9	3807.9	MW-50	2.5	8.65	85.4	
15	247.1	-364.5	4047.1	SS-11	-1.1	4.96	85.6	
16	150	0	3950.0	TBM / BS: 3950N 500E	-0.23	"	586.47	(PG. 22)

4-45-92 (33)		-Location Cont. P.		DESCRIPTION		OFF-SITE LOCATIONS		V. DIST.		PERIM. ELEV	
NORTH	EAST	NORTHING	EASTING								
17	463.4	228.9	4263.4	5828.9	SC-02 (BIT BRICKING LOT)	-0.9	4.90	85.8			
18	-200.6	0.9	3599.4	5600.9	SC-01	-2.3	"	84.4			
19	-153.0	-327.6	3447.0	5272.4	SS-15 (Gravel Lot)	-1.3	"	85.4			
20	-158.2	-524.6	3649.8	5075.4	SS-16 (BIT BRICKING LOT)	-1.5	"	85.2			
21	-146.9	-734.4	3853.1	4865.6	SS-17	6.0	up 2 12.50	85.1			

[illegible]

					X G 4500N 5285E BS: NORTH					(35)	
					T-R						
					DESCRIPTION					15-72	
0			4500.0	5285.0	LARSEN MARINE AREA						
1	198.8	-88.7	4698.8	5196.3	TBM MARK IS THE TOP OF SHEET PILE ELEV MARKED						
2	174.8	-346.4	4674.8	4938.6	TBM IN "SEAWALL" 585.52						
					BENCHMARK						
					X IN SEAWALL						
					NW CORNER SEAWALL ELEV MARKED						
					584.65						
					20' ± WEST OF "SHED"						
3	155.8	-317.1	4655.8	4967.9	NE COR "SHED"						
4	147.6	-318.4	4647.6	4966.6	SE " "						
5	216.1	-338.6	4716.1	4946.4	SE COR. STORAGE BLDING "LARSEN MARINE"						
6	234.3	-437.2	4734.3	4847.8	SW " " " "						
7	176.6	-345.9	4676.6	4939.1	NW COR. SLIP (SHEET PILE)						
8	103.4	-368.3	4603.4	4924.7	SW " " " "						
9	106.2	-316.2	4606.2	4968.8	SE " " " "						
10	161.3	-304.4	4661.3	4980.6	NE " " " "						







BENCH MARK INFO:

BM  
USED

"X" ON SEAWALL, NW CORNER OF SHIP.

at Larson Marine, 7' east of, &

41' south of; Larson Marine storage

building, at slip. EL. GIVEN = 584.65

CORR: 46.75N, 4939E

NOTE: THIS BM IS USED BY CANONIE

and Hi Tech. It was set by

Mid America Survey Co. 1-7-88.

Mid America Survey Co. came

off of a 45GS BM. to establish

elevation. (Fax sheet from Mid America Inc. 4/16/21)

BM  
"A" on sheet pile marking TEM

EL. GIVEN = 585.52

CORR: 46.99N, 5196

Waukegan Harbor

COKE PLANT RI/FS

4-16-92

S. Sabary

D. Mitchell

ORIENT

RAINING / BLOW

50°

5-10 mph

Now, 40

loop from

45GS BM. THIS IS THE BM USED

By Canonie.


(39)

	+	H1	-	ELEV	LEVEL	LOOP	INTO	P103, MW 4D, P. MW 4S	4-16-92
				586.47	TBM	SPK	3750N	5600E	(PG. 22)
	5.49	591.96							
			5.6	586.4		GRO	P. 103		
			2.49	589.47		CASING	"		
TP1			2.52	589.44		RISER	"	(1 1/2" PVC)	
	2.44	591.88							
TP2			6.04	585.84					
	5.57	591.41							
			5.2	586.2		GRO	MW 4-S		
			2.12	589.29		CASING	"		
TP3			2.24	589.17		RISER	"	(2" steel)	
	2.26	591.43							
			5.3	586.1		GRO	MW 4D		
			2.36	589.07		CASING	"		
TP4			2.37	589.06		RISER	"	(2" steel)	
	2.79	591.85							
			5.43	586.45	586.47	TBM	SPK		

	+	HI	-	ELEV		LEVEL LOOP P. 101, 55, 23, 4, 5, PP 50	(40) 4-16-92
				584.62		X ON SEAWALL GIVEN EL = 584.62	
	5.30	589.92					
TP1			5.43	584.49		Mark "BARR" ON SEAWALL (14' WEST OF X)	
	5.60	590.09					
			5.3	584.8		55-89'	
			5.5	584.6		55-85'	
			4.8	585.3		55-85' (2' WEST OF ORIGINAL)	
TP2			4.58 4.763	585.51		ON SEAWALL	585.52
	4.77	590.28					
TBM TP3			4.77	585.49	585.52	"A" MARK ON SEAWALL BN	GIVEN EL = 585.52
	4.63	590.12					
			5.505	584.62	584.62	X ON SEAWALL ✓	
TP4			5.05	585.07		BACK	
	5.27	590.34					
			4.8	585.5		55-83'	
TP5			4.925	585.42		SP. 4 4700N 5600E	
	4.86	590.28					

476-92

	+	HL	-	ELEV					
		590.28	4.4	585.9		PR-3D	4975.8N, 5528.3E		
TP6			2.045	588.23		DISK MW-3D			
	1.56	589.79							
TP7			5.13	584.66		SWP 5005N, 5036E			
	5.445	590.11							
			5.1	585.0		GRO P-101			
			1.90	588.21		CASING "			
TEB			1.965	588.14		RIFER "			
	1.95	590.09							
TP9			5.27	584.82					
	5.28	590.10							
TP11			5.48	584.61	584.62 ✓	X ON SP WALL ✓			



## ***Appendix C***

### ***Soil Boring Logs***

***Potential Source Area  
Investigation Shallow Borings***






# BORING LOG

PROJECT: WCP-RI/FS - Phase I  
 DATE STARTED: 3/7/92  
 DATE COMPLETED: 3/7/92  
 FIELD INSPECTOR: S. Marshik (BEC)  
 CREW CHIEF: P. Dickinson (WTD)

BORING NO.: SC-01

RISER PIPE ELEVATION: --

GROUND SURFACE ELEVATION: 584.4

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0	--	--	--	--	G		Blacktop
							Crushed rock base material 0.2'
							1.2'
	1.5	FS	N	N	SSB		SILTY SAND TO SAND WITH SILT (SP-SM)- Fine grained, dark gray. (10YR 4/1) moist (Fill) 2.0'
							POORLY GRADED SAND (SP)- Fine grained, pale brown (10YR 6/3) wet below 2.9' (Fill) 4.0'
5							E.O.B.
10							
15							
20							
25							
30							





COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe = Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 3 1/4" I.D. hollow stem auger. Borehole backfilled with cuttings.

SHEET 1 OF 1

# **BORING LOG**

PROJECT: WCP-R1/FS - Phase I  
 DATE STARTED: 3/7/92  
 DATE COMPLETED: 3/7/92  
 FIELD INSPECTOR: J. Fox (BEC)  
 CREW CHIEF: P. Dickinson (WTD)

BORING NO.: SC-02  
 RISER PIPE ELEVATION: --  
 GROUND SURFACE ELEVATION: 585.8

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0	--	--	--	--	G		Blacktop 0.2'
							Crushed rock base material 1.2'
	0	FS	N	N	SSB		SILTY SAND (SM)- With gravel, fine grained, black (5YR 5/1) moist (Fill). 2.0'
							SILTY SAND (SM)- With gravel, fine grained, very dark grayish-brown (10YR 3/2) moist wet below 3.4'. (Fill) 4.0'
5							E.O.B.
10							
15							
20							
25							
30							

COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L = Low, M = Moderate, S = Strong, V = Very Strong, P = Petroleum, D = Diesel  
 Sampling Method: G = Grab, SSB = Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P = PAHs, M = metals, Ph = Phenol, Pc = PCBs, Pe = Pesticides, A = Arsenic, C = Cyanide, T = TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 3 1/4" I.D. hollow stem auger. Borehole backfilled with cuttings.



***Background Soil Borings***

# BORING LOG

PROJECT: WCP-RI/FS - Phase I  
 DATE STARTED: 3/5/92  
 DATE COMPLETED: 3/5/92  
 FIELD INSPECTOR: J. Fox (BEC)  
 CREW CHIEF: P. Dickinson (WTD)

BORING NO.: BS-01  
 RISER PIPE ELEVATION: --  
 GROUND SURFACE ELEVATION: ~592

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0	--	--	--	--	G		POORLY GRADED SAND WITH SILT (SP-SM)- Fine grained, dark brown (1.5 YR 3/2) (Fill)
							0.5'
	0	FS	N	N	SSB		POORLY GRADED SAND (SP)- Fine grained, light brown (7.5 YR 6/4) (Fill)
							4.0' E.O.B.
5							
10							
15							
20							
25							
30							

COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe =  
 Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 3 1/4" I.D. hollow stem auger. Borehole backfilled with cuttings.

SHEET 1 OF 1

# BORING LOG

PROJECT: WCP-RI/FS - Phase I  
 DATE STARTED: 3/5/92  
 DATE COMPLETED: 3/5/92  
 FIELD INSPECTOR: J. Fox (BEC)  
 CREW CHIEF: P. Dickinson (WTD)

BORING NO.: BS-02

RISER PIPE ELEVATION: --

GROUND SURFACE ELEVATION: ~592

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0							
0.4'	-	-	-	-	G		SANDY ORGANIC SOIL (OL/SM)-Fine grained, black (2.5Y 2/0)
3.5'							LEAN CLAY (CL)- Fine grained, dark grayish brown (2.5Y 4/2) moist (Fill)
4.0'	2	FS	N	N	G		POORLY GRADED SAND (SP)- Fine grained, light brown (7.5 YR 6/1) moist (Fill)
E.O.B.							
5							
10							
15							
20							
25							
30							

COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe = Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 3 1/4" I.D. hollow stem auger. Borehole backfilled with cuttings.

SHEET 1 OF 1

# BORING LOG

PROJECT: WCP-RI/FS - Phase I

BORING NO.: BS-03

DATE STARTED: 3/5/92

DATE COMPLETED: 3/5/92

RISER PIPE ELEVATION: --

FIELD INSPECTOR: J. Fox (BEC)

CREW CHIEF: P. Dickinson (WTD)

GROUND SURFACE ELEVATION: ~589

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0	-	-	-	-	G		POORLY GRADED SAND WITH TRACE OF SILT (SP TO SP/SM)-Fine grained, dark gray (5Y5/1), moist. Pieces of glass (Fill)
2	FS	N	N	SSB			MIXED FILL: POORLY GRADED SAND WITH TRACE OF SILT (SP TO SP/SM)-Fine grained dark-gray (5Y 5/1), moist and ORGANIC SOIL (OL), Black (2.5Y 3/0), moist and LEAN CLAY WITH TRACE OF SILT (CL)-Pieces of glass and wood.
5							4.0' E.O.B.
10							
15							
20							
25							
30							

COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe =  
 Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 3 1/4" I.D. hollow stem auger. Borehole backfilled with cuttings.

SHEET 1 OF 1

# BORING LOG

PROJECT: WCP-RI/FS - Phase I  
 DATE STARTED: 3/5/92  
 DATE COMPLETED: 3/5/92  
 FIELD INSPECTOR: J. Fox (BEC)  
 CREW CHIEF: P. Dickinson (WTD)

BORING NO.: BS-04

RISER PIPE ELEVATION: --

GROUND SURFACE ELEVATION: ~588

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0	--	--	--	--	G		POORLY GRADED SAND (SP)- Fine to medium grained, pale brown (10YR 6/3) with a trace of gravel (~2%), moist (Fill)
							2.8'
							Furnace glass, medium to fine sand size, black, moist.
							3.0'
	0	FS	N	N	SSB		POORLY GRADED SAND (SP)- Fine grained very pale brown (10 YR 7/3), moist (Fill).
							4.0'
5							E.O.B.
10							
15							
20							
25							
30							




COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe = Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 3 1/4" I.D. hollow stem auger. Borehole backfilled with cuttings.

SHEET 1 OF 1

# BORING LOG

PROJECT: WCP-RI/FS - Phase I  
 DATE STARTED: 3/25/92  
 DATE COMPLETED: 3/25/92  
 FIELD INSPECTOR: J. Fox (BEC)  
 CREW CHIEF: P. Dickinson (WTD)

BORING NO.: BS-05  
 RISER PIPE ELEVATION: --  
 GROUND SURFACE ELEVATION: ~590

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0	--	--	--	--	G		SANDY SLAG- Black (5YR 2.5/1) moist (Fill)
1.4'	--	--	--	--	G		
1	FS	N	N	SSB			POORLY GRADED SAND (SP)- Fine grained, pale brown (10YR 6/3) moist, wet at 4.0' (Fill)
4.0'							E.O.B.
5							
10							
15							
20							
25							
30							

COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe = Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 3 1/4" I.D. hollow stem auger. Borehole backfilled with cuttings.

SHEET 1 OF 1

# BORING LOG

PROJECT: WCP-RI/FS - Phase I  
 DATE STARTED: 3/25/92  
 DATE COMPLETED: 3/25/92  
 FIELD INSPECTOR: J. Fox (BEC)  
 CREW CHIEF: P. Dickinson (WTD)

BORING NO.: BS-06  
 RISER PIPE ELEVATION: --  
 GROUND SURFACE ELEVATION: 586.3

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0	--	--	--	--	G		Sod
							0.2'
	O	FS	N	N	SSB		POORLY GRADED SAND (SP)- Fine to medium grained, pale brown.(10YR 6/3) moist (Fill)
5							4.0' E.O.B.
10							
15							
20							
25							
30							

COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe = Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 3 1/4" I.D. hollow stem auger. Borehole backfilled with cuttings.

SHEET 1 OF 1

# BORING LOG

PROJECT: WCP-RI/FS - Phase I  
 DATE STARTED: 3/25/92  
 DATE COMPLETED: 3/25/92  
 FIELD INSPECTOR: J. Fox (BEC)  
 CREW CHIEF: P. Dickinson (WTD)

BORING NO.: BS-07

RISER PIPE ELEVATION: --

GROUND SURFACE ELEVATION: 584.8

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0							
					G		SOD 0.1'
							POORLY GRADED SAND (SP)- Fine to medium grained, pale brown (10YR 6/3) moist wet below 2'± (Fill)
75	FS	N	N	SSB			
5							4.0' E.O.B.
10							
15							
20							
25							
30							

COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe = Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 3 1/4" I.D. hollow stem auger. Borehole backfilled with cuttings.

SHEET 1 OF 1



# BORING LOG

PROJECT: WCP-RI/FS - Phase I  
 DATE STARTED: 3/25/92  
 DATE COMPLETED: 3/25/92  
 FIELD INSPECTOR: J. Fox (BEC)  
 CREW CHIEF: P. Dickinson (WTD)

BORING NO.: BS-08  
 RISER PIPE ELEVATION: --  
 GROUND SURFACE ELEVATION: 585.6

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0	-	-	-	-	G		POORLY GRADED SAND (SP)- Fine to medium grained, pale brown.(10YR 6/3) moist wet below 3.5' (Alluvium)
3	FS	N	N	SSB			
5							4.0' E.O.B.
10							
15							
20							
25							
30							

COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe = Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 3 1/4" I.D. hollow stem auger. Borehole backfilled with cuttings.

***Surficial Soil Borings***

# BORING LOG

PROJECT: WCP-RI/FS - Phase I

BORING NO.: SS-01

DATE STARTED: 3/10/92



DATE COMPLETED: 3/10/92

RISER PIPE ELEVATION: --

FIELD INSPECTOR: K. French (BEC)

CREW CHIEF: P. Dickinson (WTD)

GROUND SURFACE ELEVATION: 585.4

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0							
	--	--	N	N	G		POORLY GRADED SAND TO POORLY GRADED SAND WITH SILT (SP TO SP-SM)- Fine to medium subrounded sand, less than 15% angular gravel, brown (10YR 5/3), to very dark grayish brown (10YR 3/2), moist, contains roots (Fill).
							1.5'
	4	FS	T	N	G & SSB		POORLY GRADED SAND WITH SILT (SP-SM)- Fine to medium sand, dark yellowish brown (10yr 4/6), moist to wet at approximately 3.0' (Fill).
							4.0'
5							E.O.B.
10							
15							
20							
25							
30							




COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe = Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 3 1/4" I.D. hollow stem auger. Borehole backfilled with cuttings.

SHEET 1 OF 1

# BORING LOG

PROJECT: WCP-RI/FS - Phase I  
 DATE STARTED: 3/6/92  
 DATE COMPLETED: 3/6/92  
 FIELD INSPECTOR: J. Fox (BEC)  
 CREW CHIEF: P. Dickinson (WTD)

BORING NO.: SS-02  
 RISER PIPE ELEVATION: --  
 GROUND SURFACE ELEVATION: 585.3

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0	--	--	--	--	G		Crushed Rock Base Material 0.4'
	--	--	--	--	G		SILTY SAND (SM)- Fine grained, black (10YR 2/1) moist with some foundry slag clinkers (Fill)
0.5	FS	N	N	SSB	SSB		POORLY GRADED SAND (SP)- Fine grained, pale brown (10YR 6/3), moist, wet below 3.0' (Fill) 2.5'
5							4.0' E.O.B.
10							
15							
20							
25							
30							

## COMMENT:




Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe = Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 3 1/4" I.D. hollow stem auger. Borehole backfilled with cuttings.

SHEET 1 OF 1

# BORING LOG

PROJECT: WCP-RI/FS - Phase I  
 DATE STARTED: 3/6/92  
 DATE COMPLETED: 3/6/92  
 FIELD INSPECTOR: J. Fox (BEC)  
 CREW CHIEF: P. Dickinson (WTD)

BORING NO.: SS-03  
 RISER PIPE ELEVATION: --  
 GROUND SURFACE ELEVATION: 585.5

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0							
					G		Crushed Rock Base Material 0.2'
							SILTY SAND (SM)- Fine grained, black (10YR 2/1) moist. (Fill)
	42	FS	N	N	SSB		2.5' POORLY GRADED SAND (SP)- Fine grained, pale brown (10YR 6/3), moist (Fill)
5							4.0' E.O.B.
10							
15							
20							
25							
30							




COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe =  
 Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 3 1/4" I.D. hollow stem auger. Borehole backfilled with cuttings.

SHEET 1 OF 1

# BORING LOG

PROJECT: WCP-RI/FS - Phase I  
 DATE STARTED: 3/6/92  
 DATE COMPLETED: 3/6/92  
 FIELD INSPECTOR: J. Fox (BEC)  
 CREW CHIEF: P. Dickinson (WTD)

BORING NO.: SS-04  
 RISER PIPE ELEVATION: --  
 GROUND SURFACE ELEVATION: 584.8

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0							
	--	--	--	--	G		Crushed Rock Base Material 0.2'
							SILTY SAND (SM)- Fine grained, black (10YR 2/1) moist, with some foundry slag clinkers (Fill)
	8	FS	N	N	SSB		POORLY GRADED SAND WITH SILT (SP-SM)- Fine grained, pale brown (10YR 6/3), moist, with some foundry slag clinkers (Fill) 2.5'
5							4.0' E.O.B.
10							
15							
20							
25							
30							

COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe = Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 3 1/4" I.D. hollow stem auger. Borehole backfilled with cuttings.

SHEET 1 OF 1

# BORING LOG

PROJECT: WCP-RI/FS - Phase I  
 DATE STARTED: 3/6/92  
 DATE COMPLETED: 3/6/92  
 FIELD INSPECTOR: John Fox (B.E.C.)  
 CREW CHIEF: P. Dickinson (WTD)

BORING NO.: SS-05  
 RISER PIPE ELEVATION: --  
 GROUND SURFACE ELEVATION: 584.6

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0							
					G		Crushed rock base material. 0.2'
							POORLY GRADED SAND (SP-SM)-With a trace of gravel, fine to medium grained, dark gray (5Y4/1), moist (Fill) 2.0'
150	FS	N	N	N	N		POORLY GRADED SAND (SP)- With trace of gravel, fine to medium grained, pale brown (10YR 6/3) moist (Fill) 4.0'
5							E.O.B.
10							
15							
20							
25							
30							

COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe = Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 3 1/4" I.D. hollow stem auger. Borehole backfilled with cuttings.

SHEET 1 OF 1



# BORING LOG

PROJECT: WCP-R/FS - Phase I  
 DATE STARTED: 3/11/92  
 DATE COMPLETED: 3/11/92  
 FIELD INSPECTOR: K. French (BEC)  
 CREW CHIEF: P. Dickinson (WTD)

BORING NO.: SS-06

RISER PIPE ELEVATION: --

GROUND SURFACE ELEVATION: 585.8

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0							
	-	-	-	N	G		SILTY SAND (SM)- Fine grained, black, oil present (Fill)
							2.5'
	11	FS	M	N	G,SSB		LEAN CLAY WITH SAND (CL-CS)-Dark brown (10YR 4/3) (Fill)
							4.0'
5							E.O.B.
10							
15							
20							
25							
30							

COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe = Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 3 1/4" I.D. hollow stem auger. Borehole backfilled with cuttings.

SHEET 1 OF 1



# BORING LOG

PROJECT: WCP-RI/FS - Phase I

BORING NO.: SS-07

DATE STARTED: 3/10/92

DATE COMPLETED: 3/10/92

RISER PIPE ELEVATION: --

FIELD INSPECTOR: K. French (BEC)

CREW CHIEF: P. Dickinson (WTD)

GROUND SURFACE ELEVATION: 584.7

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0							
	--	--	--	--	G		POORLY GRADED SAND WITH SILT (SP-SM)- Fine to medium subrounded sand with less than 15% subangular gravel, olive gray (5Y4/2), moist to wet at approximately 3.0', few roots to approximately 2.0' (Fill).
	O	FS	T	L	SSB		
5							4.0' E.O.B.
10							
15							
20							
25							
30							

COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe = Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 3 1/4" I.D. hollow stem auger. Borehole backfilled with cuttings.

SHEET 1 OF 1

# BORING LOG

PROJECT: WCP-RI/FS - Phase I  
 DATE STARTED: 3/11/92  
 DATE COMPLETED: 3/11/92  
 FIELD INSPECTOR: S. Marshik (BEC)  
 CREW CHIEF: P. Dickinson (WTD)

BORING NO.: SS-08

RISER PIPE ELEVATION: --

GROUND SURFACE ELEVATION: 585.5

Depth (feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0	--	--	--	--	G		POORLY GRADED SILTY SAND (SP-SM)-Fine to medium grained, black, wet at 3.5' (Fill).
2	FS	T	N	G,SSB			
5							4.0' E.O.B.
10							
15							
20							
25							
30							

COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe =  
 Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 3 1/4" I.D. hollow stem auger. Borehole backfilled with cuttings.

SHEET 1 OF 1

# BORING LOG

PROJECT: WCP-RI/FS - Phase I  
 DATE STARTED: 3/11/92  
 DATE COMPLETED: 3/11/92  
 FIELD INSPECTOR: S. Marshik (BEC)  
 CREW CHIEF: P. Dickinson (WTD)

BORING NO.: SS-09

RISER PIPE ELEVATION: --

GROUND SURFACE ELEVATION: 586.9

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0	--	--	--	--	G		SANDY LEAN CLAY (CL)- With trace of gravel, dark, yellowish, brown (10YR 4/4) (Fill)
3.9'	O	FS	N	N	G,SSB		POORLY GRADED SAND (SP)- Fine to medium grained, brown.(Fill)
4.0'							E.O.B.
5							
10							
15							
20							
25							
30							

COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe = Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 3 1/4" I.D. hollow stem auger. Borehole backfilled with cuttings.

SHEET 1 OF 1

# BORING LOG

PROJECT: WCP-RI/FS - Phase I

BORING NO.: SS-10

DATE STARTED: 3/11/92

DATE COMPLETED: 3/11/92

RISER PIPE ELEVATION: --

FIELD INSPECTOR: K. French (BEC)

CREW CHIEF: P. Dickinson (WTD)

GROUND SURFACE ELEVATION: 585.8

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0							
1	-	-	-	N	G		POORLY GRADED SAND TO SAND WITH SILT (SP/SP-SM)- Fine grained, black (Fill)
2	FS	T	N	G,SSB			3.0' SANDY LEAN CLAY (CL-CS)-With trace of gravel, dark yellowish brown (10YR 4/4) (Fill)
							3.25' POORLY GRADED SAND (SP)- Fine to medium grained brown (10YR 5/3) (Fill)
5							4.0' E.O.B.
10							
15							
20							
25							
30							

COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe = Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 3 1/4" I.D. hollow stem auger. Borehole backfilled with cuttings.

SHEET 1 OF 1

# BORING LOG

PROJECT: WCP-RI/FS - Phase I  
 DATE STARTED: 3/11/92  
 DATE COMPLETED: 3/11/92  
 FIELD INSPECTOR: S. Marshik (BEC)  
 CREW CHIEF: P. Dickinson (WTD)

BORING NO.: SS-11  
 RISER PIPE ELEVATION: --  
 GROUND SURFACE ELEVATION: 585.6

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0	--	--	--	--	G		POORLY GRADED SAND (SP)- Fine to medium grained, very dark grayish-brown (10YR 3/2) (Fill)
							2.5'
	0	FS	N	N	G,SSB		SANDY LEAN CLAY (CL-CS)-With trace of gravel, dark gray (10YR 4/1) (Fill)
							3.0'
							POORLY GRADED SAND (SP)- Fine grained, light yellowish-brown (10YR 6/4) (Fill)
							4.0'
5							E.O.B.
10							
15							
20							
25							
30							

COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe =  
 Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 3 1/4" I.D. hollow stem auger. Borehole backfilled with cuttings.

SHEET 1 OF 1

# BORING LOG

PROJECT: WCP-RI/FS - Phase I  
 DATE STARTED: 3/11/92  
 DATE COMPLETED: 3/11/92  
 FIELD INSPECTOR: S. Marshik (BEC)  
 CREW CHIEF: P. Dickinson (WTD)

BORING NO.: SS-12

RISER PIPE ELEVATION: --

GROUND SURFACE ELEVATION: 583.9

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0							
	-	-	-	-	G		POORLY GRADED SAND (SP)- Fine to medium grained, dark yellowish-brown (10YR 4/6). (Fill)
							2.5'
	O	FS	N	N	G,SSB		POORLY GRADED SAND (SP)- Fine to medium grained, light yellowish-brown (10YR 6/4). (Fill)
							4.0'
5							E.O.B.
10							
15							
20							
25							
30							

COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe =  
 Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 3 1/4" I.D. hollow stem auger. Borehole backfilled with cuttings.

SHEET 1 OF 1

# BORING LOG

PROJECT: WCP-RI/FS - Phase I  
 DATE STARTED: 3/12/92  
 DATE COMPLETED: 3/12/92  
 FIELD INSPECTOR: S. Marshik (BEC)  
 CREW CHIEF: P. Dickinson (WTD)

BORING NO.: SS-13

RISER PIPE ELEVATION: --

GROUND SURFACE ELEVATION: 585.1

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0							
	--	--	--	N	G		POORLY GRADED SAND TO SILTY SAND (SP-SM)-Fine to medium grained, black (Fill) 0.5'
							POORLY GRADED SAND (SP)- Fine grained, pale brown (10YR 6/3) (Fill) 2.5'
	6	FS	N	N	G,SSB		POORLY GRADED SAND (SP)- Fine grained, black, no odor.(Fill) 2.6'
							POORLY GRADED SAND (SP)- Fine grained, pale brown (10YR 6/3). (Fill) 4.0'
5							E.O.B.
10							
15							
20							
25							
30							

COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe =  
 Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 3 1/4" I.D. hollow stem auger. Borehole backfilled with cuttings.

SHEET 1 OF 1

# BORING LOG

PROJECT: WCP-RI/FS - Phase I  
 DATE STARTED: 3/12/92  
 DATE COMPLETED: 3/12/92  
 FIELD INSPECTOR: S. Marshik (BEC)  
 CREW CHIEF: P. Dickinson (WTD)

BORING NO.: SS-14

RISER PIPE ELEVATION: --

GROUND SURFACE ELEVATION: 585.2

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0							
					G		COAL FINES, BLACK.
	6	FS	T	N	G		
					SSB		3.5' POORLY GRADED SAND (SP)- Fine to medium grained, grayish-brown (10YR 5/2) (Fill)
5							4.0' E.O.B.
10							
15							
20							
25							
30							

COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe = Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 3 1/4" I.D. hollow stem auger. Borehole backfilled with cuttings.

SHEET 1 OF 1



# BORING LOG

PROJECT: WCP-RI/FS - Phase I

BORING NO.: SS-15

DATE STARTED: 3/7/92

DATE COMPLETED: 3/7/92

RISER PIPE ELEVATION: --

FIELD INSPECTOR: S. Marshik (BEC)

CREW CHIEF: P. Dickinson (WTD)

GROUND SURFACE ELEVATION: 585.4

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0							
	-	-	-	-	G		Gravel base material 0.1'
							SILTY SAND (SM)-With gravel, fine grained, black (5YR 5/1), moist (Fill) 1.0'
	O	FS	N	N	N		POORLY GRADED SAND (SP)- Trace gravel, fine grained, light yellowish brown (10YR 6/4) moist (Fill) 4.0'
5							E.O.B.
10							
15							
20							
25							
30							

COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe = Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 3 1/4" I.D. hollow stem auger. Borehole backfilled with cuttings.

SHEET 1 OF 1




# **BORING LOG**

PROJECT: WCP-R1/FS - Phase I  
 DATE STARTED: 3/7/92  
 DATE COMPLETED: 3/7/92  
 FIELD INSPECTOR: S. Marshik (B.E.C.)  
 CREW CHIEF: P. Dickinson (WTD)

BORING NO.: SS-16

RISER PIPE ELEVATION: --

GROUND SURFACE ELEVATION: 585.2

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0							
	-	-	T	N	G		Blacktop 0.2'
							Crushed rock base material 1.0'
0.5	FS	N	N	SSB			SILTY SAND (SP-SM)- With gravel, fine grained, black (5YR 5/1), moist, with foundry slag. (Fill)
5							4.0' E.O.B.
10							
15							
20							
25							
30							

COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe =  
 Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 3 1/4" I.D. hollow stem auger. Borehole backfilled with cuttings.

SHEET 1 OF 1

# BORING LOG

PROJECT: WCP-RI/FS - Phase I  
 DATE STARTED: 3/7/92  
 DATE COMPLETED: 3/7/92  
 FIELD INSPECTOR: S. Marshik (BEC)  
 CREW CHIEF: P. Dickinson (WTD)

BORING NO.: SS-17  
 RISER PIPE ELEVATION: --  
 GROUND SURFACE ELEVATION: 585.1

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0							
			T	N	G		Blacktop
							Crushed rock base material 0.1'
							1.0'
							SILTY SAND (SM)- With a trace of gravel, black (5YR 5/1), moist (Fill) 2.0'
1	FS	N	N	SSB			POORLY GRADED SAND (SP)- Fine grained light, brownish gray (10YR 6/2) moist (Fill)
							4.0'
5							E.O.B.
10							
15							
20							
25							
30							

COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe = Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 3 1/4" I.D. hollow stem auger. Borehole backfilled with cuttings.

SHEET 1 OF 1

***Pilot Borings***








# BORING LOG

PROJECT: WCP-RI/FS - Phase I  
 DATE STARTED: 3/16/92  
 DATE COMPLETED: 3/18/92  
 FIELD INSPECTOR: T. Wright-Wells (BEC)  
 CREW CHIEF: P. Dickinson(WTD)

BORING NO.: SB-03

RISER PIPE ELEVATION: --

GROUND SURFACE ELEVATION: 585.9

Depth (Feet)	OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0							
	0	--	N	N	SSB		SILTY SAND (SM)- Medium grained, brown to dark brown sand, with gravel from 0.5 to 1.0' (Fill). 1.5'
	2.4	--	N	N	SSB		Coal fines, fine to 1" pieces. 2.5'
5	6.2	--	N	N	SSB		POORLY GRADED SAND (SP)- Medium grained, brown, with a clayey sand lense from 5.0-5.3', moist to wet (Fill) 5.0'
	30	--	N	N	SSB		POORLY GRADED SAND (SP)- Medium grained, gray (10YR 6/1) with trace rounded pebbles, wet (Alluvium) 8.0'
10	90	--	N	N	SSB		SAND WITH SILT (SP-SM)- Fine grained, dark gray (10YR 4/1), with trace rounded pebbles, wet (Alluvium). 11.0'
	34	--	N	N	SSB		SILTY SAND (SM)- Fine to medium grained, dark gray (10YR 4/1) with black mottling throughout, wet (Alluvium)
	8	--	N	N	SSB		
15	6	--	N	N	SSB		
	160	--	N	L	SSB		
	760	--	N	M	SSB		
20							20.0'
	>1000	--	N	M	SSB		SAND WITH SILT (SP-SM)- Fine to medium grained, gray (10YR 5/1) with a trace black mottling throughout, wet (Alluvium).
	>1000	--	N	M	SSB		
25	>1000	--	N	M	SSB		
	>1000*	--	N	L	SSB		160 ppm nonmethane OVA reading (see Boring Log MW-3D) 28.5'
	>1000	--	N	M	SSB		SILT WITH CLAY (ML-CL)- Gray (10YR5/1), very dense, low to medium toughness, low to medium plasticity with angular gravel from 28.5-29' moist (Till).
30							

COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe = Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 6 1/4" I.D. hollow stem auger to 6 feet below grade. Boring was completed using mud rotary. Borehole backfilled with tremied neat cement grout.  
 \* See Boring Log MW-3D for nonmethane OVA reading for this interval

SHEET 1 OF 4

# BORING LOG

PROJECT: WCP-RI/FS - Phase I  
 DATE STARTED: 3/16/92  
 DATE COMPLETED: 3/18/92  
 FIELD INSPECTOR: T. Wright-Wells (BEC)  
 CREW CHIEF: P. Dickinson (WTD)

BORING NO.: SB-03

RISER PIPE ELEVATION: --

GROUND SURFACE ELEVATION: 585.9

Depth (Feet)	OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
30							
	28	--	N	N	SSB		SILT WITH CLAY (ML-CL)-Gray (10YR5/1), very dense, low to medium toughness, low to medium plasticity, moist (Till).
	62	--	N	N	SSB		
35	5.7	--	N	N	SSB		
40	0	--	N	N	SSB		
45	>1000	--	N	N	SSB		
50							Boulder, gray dolomite.
55	40	--	N	N	SSB		
60							

COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L = Low, M = Moderate, S = Strong, V = Very Strong, P = Petroleum, D = Diesel  
 Sampling Method: G = Grab, SSB = Split barrel with liner  
 Analytical Sample Type: V = VOC's, P = PAHs, M = metals, Ph = Phenol, Pc = PCBs, Pe =  
 Pesticides, A = Arsenic, C = Cyanide, T = TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 6 1/4" I.D. hollow stem auger to 6 feet below grade. Boring was  
 completed using mud rotary. Borehole backfilled with tremied neat cement grout.

SHEET 2 OF 4

# BORING LOG

PROJECT: WCP-RI/FS - Phase I  
 DATE STARTED: 3/16/92  
 DATE COMPLETED: 3/18/92  
 FIELD INSPECTOR: T. Wright-Wells (BEC)  
 CREW CHIEF: P. Dickinson (WTD)

BORING NO.: SB-03

RISER PIPE ELEVATION: --

GROUND SURFACE ELEVATION: 585.9

Depth (Feet)	OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
60							
65	90	--	N	N	SSB		CLAYEY SILT (CL-ML)- Gray (10YR 4/1), soft to firm, with cobbles at 81-83', 87-89', 92.5 - 93.5' and from 103' to E.O.B; thin sand lenses from 85-85.3' and from 94-94.5', moist. (Till)
70							
75	10	--	N	N	SSB		
80							
85	8	--	N	N	SSB		
90							

**COMMENT:** Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe =  
 Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 6 1/4" I.D. hollow stem auger to 6 feet below grade. Boring was  
 completed using mud rotary. Borehole backfilled with tremied neat cement grout.

SHEET 3 OF 4

## BORING LOG

PROJECT: WCP-RI/FS - Phase I

BORING NO.: SB-03

DATE STARTED: 3/16/92

RISER PIPE ELEVATION: --

DATE COMPLETED: 3/18/92

FIELD INSPECTOR: T. Wright-Wells (BEC)

GROUND SURFACE ELEVATION: 585.9

CREW CHIEF: P. Dickinson (WTD)

Depth (Feet)	OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
90							CLAYEY SILT (CL-ML)-Gray (10YR4/1), soft to firm, with cobbles at 92.5- 93.5' and from 103' to E.O.B.; thin sand lenses from 94-94.5', moist (Till).
95	54	--	N	N	SSB		
100							
105	6	--	N	N	SSB		Dolomite bedrock- gray. Logged from chips.
110							
115							108.0' _____ 109' _____ E.O.B.
120							

**COMMENT:** Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe =  
 Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 6 1/4" I.D. hollow stem auger to 6 feet below grade. Boring was  
 completed using mud rotary. Borehole backfilled with tremied neat cement grout.

SHEET 4 OF 4



# BORING LOG

PROJECT: WCP-RI/FS - Phase I  
 DATE STARTED: 3/18/92  
 DATE COMPLETED: 3/18/92  
 FIELD INSPECTOR: T. Wright-Wells (BEC)  
 CREW CHIEF: P. Dickinson (WTD)

BORING NO.: MW-3D

RISER PIPE ELEVATION: 588.23

GROUND SURFACE ELEVATION: 585.5

Depth (Feet)	OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0							
5							See Boring Log SB-03
10							
15							
20							
25							
28.0'	160	P, Ph,V	N	L	SSB		E.O.B.
30							

COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe =  
 Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 6 1/4" I.D. hollow stem auger. Monitoring well MW-3D installed in  
 borehole.

SHEET 1 OF 1

# BORING LOG

PROJECT: WCP-RI/FS - Phase I

BORING NO.: SB-04

DATE STARTED: 3/20/92

DATE COMPLETED: 3/20/92

RISER PIPE ELEVATION: 589.06

FIELD INSPECTOR: T. Wright - Wells (BEC)

CREW CHIEF: P. Dickinson (WTD)

GROUND SURFACE ELEVATION: 586.1

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0							
2	--	N	N	SSB			SILTY SAND (SM)- Fine to medium grained, brown (Fill). 0.5'
							Coal fines with limestone gravel. 1.0'
2	--	N	N	SSB			POORLY GRADED SAND (SP)- Fine to medium grained brown. (Fill) 5.0'
5							
10	10	--	N	N	SSB		POORLY GRADED SAND (SP)- Medium grained, gray w/black mottling (10YR 5/1). (Alluvium)
	0	--	N	N	SSB		
10	26	--	N	N	SSB		
	75	--	N	N	SSB		
15	21	--	N	N	SSB		
	24	--	N	N	SSB		
20	7	--	N	N	SSB		
	250	--	N	N	SSB		
25	1000	--	N	M	SSB		
	500	--	N	M	SSB		
30							


COMMENT: Oil Content In Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe =  
 Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 6 1/4" I.D. hollow stem auger. Monitoring well MW-4D installed in borehole.

SHEET 1 OF 2

# BORING LOG

PROJECT: WCP-RI/FS - Phase I  
 DATE STARTED: 3/20/92  
 DATE COMPLETED: 3/20/92  
 FIELD INSPECTOR: T. Wright-Wells (BEC)  
 CREW CHIEF: P. Dickinson (WTD)

BORING NO.: SB-04  
 RISER PIPE ELEVATION: 589.06  
 GROUND SURFACE ELEVATION: 586.1

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
30							
	1250	P,Ph,V	N	M	SSB		<div>31.0'</div> <div>POORLY GRADED GRAVEL (GP)- Medium to coarse grained, grey, wet (Alluvium)</div> <div>31.5'</div> <div>SILT TO SILT WITH CLAY (ML/ML-CL)-Light gray (10YR 7/1) trace coarse sand, moist (Till)</div> <div>32.0'</div> <div>E.O.B.</div>
35							
40							
45							
50							
55							
60							

COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy SHEET 2 OF 2  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe =  
 Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 6 1/4" I.D. hollow stem auger. Monitoring well MW-4D installed in borehole.












# BORING LOG

PROJECT: WCP-RI/FS - Phase I  
 DATE STARTED: 3/23/92  
 DATE COMPLETED: 3/23/92  
 FIELD INSPECTOR: J. Fox (BEC)  
 CREW CHIEF: B. Loveland (WTD)

BORING NO.: SB-05

RISER PIPE ELEVATION: 588.47

GROUND SURFACE ELEVATION: 585.7

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0							
0	0	-	N	N	G		POORLY GRADED SAND (SP)- Fine grained w/a trace of gravel, light brownish grey (10YR 6/2) (Fill)  5.0'
5	20	--	N	N	SSB		POORLY GRADED SAND (SP)-Fine grained, grey (10YR 6/1), wet (Alluvium)  7.0'
	5	--	N	N	SSB		POORLY GRADED SAND WITH GRAVEL (SP)-Fine to medium grained, grey (10yr 6/1), wet (Alluvium)  12.0'
10	15	--	N	N	SSB		
	9	--	N	N	SSB		POORLY GRADED SAND (SP/SP-SM) -W/a trace of silt, fine grained, grey (10yr 5/1) slightly stained or mottled dark grey (10YR 4/1), wet (Alluvium)  22.0'
15	30	--	N	N	SSB		
	12	--	N	N	SSB		
20	50	--	N	N	SSB		
	80	--	N	N	SSB		POORLY GRADED SAND (SP)- Fine to medium grained, dark grey (10YR 4/1), wet (Alluvium)  25.5'
25	75	P,Ph,V	N	N	SSB		POORLY GRADED GRAVEL (GP)- Medium to coarse grained, grey (10YR 6/1) wet (Alluvium)  25.7'
							SILT (ML/ML-CL)-With a trace of clay and a trace of coarse sand (<1%), light grey (10YR 7/1) moist (Till).  27.0'
30							E.O.B.

COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe =  
 Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 6 1/4" I.D. hollow stem auger. Monitoring Well MW-5D installed in borehole.

SHEET 1 OF 1

# BORING LOG

PROJECT: WCP-RI/FS - Phase I  
 DATE STARTED: 3/24/92  
 DATE COMPLETED: 3/24/92  
 FIELD INSPECTOR: T. Wright-Wells (BEC)  
 CREW CHIEF: B. Loveland (WTD)

BORING NO.: SB-06

RISER PIPE ELEVATION: 588.51

GROUND SURFACE ELEVATION: 585.7

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0							
	-	--	-	-	G		POORLY GRADED SAND (SP)- Fine to medium grained, brown (10YR 5/3), with 3' of dark gray sand at 2.5' (Fill)
	0	--	N	N	SSB		
5							
	3	--	N	N	SSB		
							7.5'
	4	--	N	N	SSB		POORLY GRADED SAND (SP)- Light gray (10YR 6/1) fine to medium grained. (Alluvium)
10							10.0'
	0	--	N	L	SSB		POORLY GRADED SAND (SP)- Dark gray (10YR 4/1) With black mottling. (Alluvium)
	50	--	N	L	SSB		
15							
	10	--	N	L	SSB		
	75	--	N	L	SSB		
20							
	250	--	N	L	SSB		
	150	P, Ph, V	N	M	SSB		
25							Unable to collect analyticals due to lack of sample.
	200	--	N	L	SSB		26.2'
							POORLY GRADED GRAVEL (GP) 26.5'
							SILT (ML)- Light gray (10YR 7/1) (Till) 27.5'
							E.O.B.
30							

COMMENT: Oil Content In Water: N = None, T = Trace, M = Moderate, H = Heavy SHEET 1 OF 1  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe =  
 Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 6 1/4" I.D. hollow stem auger. Monitoring well MW-6D installed in borehole.

# BORING LOG

PROJECT: WCP-RI/FS - Phase I  
 DATE STARTED: 3/9/92  
 DATE COMPLETED: 3/9/92  
 FIELD INSPECTOR: K. French (BEC)  
 CREW CHIEF: P. Dickinson (WTD)

BORING NO.: P-101

RISER PIPE ELEVATION: 588.14

GROUND SURFACE ELEVATION: 585.0

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0							
							Gravel-Crushed Rock 0.2'
							SILTY SAND (SM)- Fine to medium sand, black (Fill) 1.0'
							POORLY GRADED SAND (SP)- Fine to medium rounded sand, less than 10% silt, up to 10% fine gravel, very dark grayish brown (10YR 3/2) to dark grayish brown (10yr 4/2), moist to wet (Alluvium). 2.8'
5	--	--	N	N	G		
10	--	--	N	N	G		
							14.0' E.O.B.
15							
20							
25							
30							

COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L = Low, M = Moderate, S = Strong, V = Very Strong, P = Petroleum, D = Diesel  
 Sampling Method: G = Grab, SSB = Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P = PAHs, M = metals, Ph = Phenol, Pc = PCBs, Pe = Pesticides, A = Arsenic, C = Cyanide, T = TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 3 1/4" I.D. hollow stem auger. Piezometer P-101 installed in borehole.

SHEET 1 OF 1

# BORING LOG

PROJECT: WCP-RI/FS - Phase I

BORING NO.: P-102

DATE STARTED: 3/12/92



DATE COMPLETED: 3/12/92

RISER PIPE ELEVATION: 588.52

FIELD INSPECTOR: K. French (BEC)

CREW CHIEF: P. Dickinson (WTD)

GROUND SURFACE ELEVATION: 585.6

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0							
	--	--	N	N	G		POORLY GRADED SAND (SP)- Medium to coarse subrounded sand, less than 5% silt, very dark gray (7.5 YR3/0) discolored, moist, contains roots (Fill)
						2.0'	
							
						2.6'	
5	--	--	N	N	G		POORLY GRADED SAND (SP)- Fine to medium subrounded to rounded sand, less than 10% silt, black (7.5 YR 2/0), discolored, wet to saturated (Alluvium)
10							
	--	--	T	L	G		
14.0'							E.O.B.
15							
20							
25							
30							

COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe =  
 Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 3 1/4" I.D. hollow stem auger. Piezometer P-102 installed in borehole.

SHEET 1 OF 1





# BORING LOG

PROJECT: WCP-RI/FS - Phase I  
 DATE STARTED: 3/12/92  
 DATE COMPLETED: 3/13/92  
 FIELD INSPECTOR: K. French (BEC)  
 CREW CHIEF: P. Dickinson (WTD)

BORING NO.: P-103

RISER PIPE ELEVATION: 589.44

GROUND SURFACE ELEVATION: 586.4

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0	-	-	N	N	G		POORLY GRADED SAND WITH SILT (SP-SM)- Fine to medium subrounded sand, less than 15% gravel, very dark gray (10YR 3/1), moist, contains roots (Fill) 1.0'
5	-	-	N	N	G		POORLY GRADED SAND (SP)- Fine to medium rounded sand, less than 5% silt, dark grayish brown (2.5YR 4/2) to dark gray (10YR 4/1) at 6.0', moist to wet (Alluvium)
10	-	-	N	N	G		
15	-	-	N	N	G		
20							
25							
30							

5.4

14.5'  
E.O.B.

COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L = Low, M = Moderate, S = Strong, V = Very Strong, P = Petroleum, D = Diesel  
 Sampling Method: G = Grab, SSB = Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P = PAHs, M = metals, Ph = Phenol, Pc = PCBs, Pe = Pesticides, A = Arsenic, C = Cyanide, T = TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 3 1/4" I.D. hollow stem auger. Piezometer P-103 installed in borehole.

SHEET 1 OF 1



# BORING LOG

PROJECT: WCP-RI/FS - Phase I  
 DATE STARTED: 3/12/92  
 DATE COMPLETED: 3/12/92  
 FIELD INSPECTOR: K. French (BEC)  
 CREW CHIEF: P. Dickinson (WTD)

BORING NO.: P-104  
 RISER PIPE ELEVATION: 589.07  
 GROUND SURFACE ELEVATION: 586.0

Depth (Feet)	Nonmethane OVA Headspace (ppm)	Analytical Sample Type	Oil Content in Water	Product Odor	Sampling Method	Profile	DESCRIPTION OF MATERIALS AND REMARKS
0							
	--	--	T	N	G		POORLY GRADED SAND (SP)- Medium subrounded sand 5-10% silt, black (5Y2.5/1), moist (Fill)
							2.5'
	--	--	M	L	G		
5						3.6'	POORLY GRADED SAND (SP)- Fine to medium subrounded to rounded sand, less than 5% silt, black (5Y2.5/1) to very dark gray (7.5 YR 3/0), wet to saturated (Alluvium).
	--	--	T	L	G		
10							
	--	--	T	N	G		
							14.0'
15							E.O.B.
20							
25							
30							

COMMENT: Oil Content in Water: N = None, T = Trace, M = Moderate, H = Heavy  
 Odor: L= Low, M = Moderate, S = Strong, V = Very Strong, P= Petroleum, D= Diesel  
 Sampling Method: G= Grab, SSB= Split - barrel with liner  
 Analytical Sample Type: V = VOC's, P=PAHs, M= metals, Ph = Phenol, Pc = PCBs, Pe =  
 Pesticides, A = Arsenic, C= Cyanide, T=TCLP, FS = Full Scan Analyses (V,P,M,Ph,Pc,Pe,C).  
 Borehole drilled using 3 1/4" I.D. hollow stem auger. Piezometer P-104 installed in borehole.

SHEET 1 OF 1

***Appendix D***  
***left out intentionally***  
***because of size***


## ***Appendix E***

### ***Monitoring Well and Piezometer Construction Logs***

# WELL LOG

**BARR ENGINEERING CO.**  
Minneapolis, Minnesota

Project WCP RI/ES Phase I Well No. MW-3S  
 Date Started 3/13/92  
 Date Completed 3/14/92 Riser Pipe Elevation 588.24'  
 Field Inspector K. French (BEC)  
 Crew Chief P. Dickinson (WTD) Ground Surface Elevation 585.2

BOREHOLE CONSTRUCTION NOTES	LITHOLOGY	WELL CONSTRUCTION	WELL CONSTRUCTION NOTES
<p>Borehole advanced from 0' to 13.0' (585.2-572.2) using 6 1/4-inch I.D. hollow stem auger.</p> <p>Inside of auger flushed with potable water</p> <p>Well screen and riser pipe placed in the borehole.</p> <p>Sand pack and then bentonite pellets placed as auger retracted.</p> <p>Neat cement grout to surface.</p> <p>Water level was 2.5' below surface, on 3-13-92.</p>	<p>Fill 1.5'</p> <p>Coal Fines 2.5'</p> <p>Sand Fill 5.0'</p> <p>Medium Sand 8.0'</p> <p>Sand With Silt 11.0'</p> <p>Silty Sand 13.0'</p> <p>E.O.B.</p>		<p>Stickup: 3.04'</p> <p>2 -inch diameter, stainless steel riser pipe 0' to 1.5' (585.2-583.7).</p> <p>2-inch diameter, 10.5' long, #10 slot size stainless steel screen 1.5' - 12.0' (583.7-572.2).</p> <p>Sandpack 1.0 - 13.0' (584.2 - 572.2).</p> <p>Bentonite seal 0.5' - 1.0' (584.7 - 584.2).</p> <p>Cement grout 0 - 0.5'.</p> <p>4-foot long steel protective casing with locking cap.</p> <p>Three protective posts installed.</p>


Comments: <sup>1</sup> Elevation in feet MSL  
Vertical Scale : 1" = 5'

Sheet 1 of 1

# WELL LOG

BARR ENGINEERING CO.  
Minneapolis, Minnesota


Project WCP RI/ES Phase I Well No. MW-3D  
 Date Started 3/18/92  
 Date Completed 3/18/92 Riser Pipe Elevation 588.23'  
 Field Inspector T. Wright-Wells (BEC)  
 Crew Chief P. Dickinson (WTD) Ground Surface Elevation 585.5

BOREHOLE CONSTRUCTION NOTES	LITHOLOGY	WELL CONSTRUCTION	WELL CONSTRUCTION NOTES
<p>Borehole advanced from 0' to 28.0' (585.5 - 557.5) using 6 1/4-inch I.D. hollow stem auger.</p> <p>Inside of auger flushed with potable water.</p> <p>Well screen and riser pipe placed in borehole.</p> <p>Sand pack and then bentonite pellets placed as auger retracted.</p> <p>Neat cement grout to surface.</p>	<p>Silty Sand Fill — 1.5' — Coal Fines — 2.5' — Medium Sand Fill — 5.0' — Clayey Sand — 5.3' — Medium Sand — 8.0' — Fine Sand With Silt — 11.0' — Silty Sand</p> <p>20.0'</p> <p>Fine Sand With Silt</p> <p>28.0'</p> <p>E.O.B.</p>		<p>Stickup up: 2.73'</p> <p>2-inch diameter, stainless steel riser pipe 0' to 22.8' (585.5-562.7).</p> <p>2-inch diameter, 5' long, #10 slot size stainless steel screen 22.8'-27.8' (562.7-557.7')</p> <p>Sandpack 18'-27.8' (567.5-557.7).</p> <p>Bentonite seal 16.0-18.0' (569.5 - 567.5)</p> <p>Cement grout 0 - 16.0' (585.5 - 569.5)</p> <p>5-foot long protective casing with locking cap.</p> <p>Three protective posts installed.</p>

# WELL LOG

**BARR ENGINEERING CO.**  
Minneapolis, Minnesota

Project WCP RI/FS Phase I Well No. MW-4S  
 Date Started 3/19/92  
 Date Completed 3/19/92 Riser Pipe Elevation 589.17'  
 Field Inspector S. Marshik (BEC)  
 Crew Chief P. Dickinson (WTD) Ground Surface Elevation 586.2

BOREHOLE CONSTRUCTION NOTES	LITHOLOGY	WELL CONSTRUCTION	WELL CONSTRUCTION NOTES
<p>Borehole advanced from 0' to 14.0' (586.2 - 572.2) using 6 1/4-inch I.D. hollow stem auger.</p> <p>Inside of auger flushed with potable water.</p> <p>Well screen and riser pipe placed in borehole.</p> <p>Sand pack and then bentonite pellets placed as auger retracted.</p> <p>Neat cement grout to surface.</p>	<p>Topsoil Silty Sand Fill and Coal Fines 1.0'</p> <p>Fine to Medium Sand Fill 5.0'</p> <p>Medium Sand</p> <p>14.0' E.O.B.</p>		<p>Stickup up: 2.97'</p> <p>2-inch diameter, stainless steel riser pipe 0' to 1.7' (586.2 - 584.5).</p> <p>2-inch diameter 10.3' long, #10 slot size 1.7-12.0 (584.5-574.2)</p> <p>Sandpack 1.0- 14.0' (585.2 - 572.2)</p> <p>Bentonite seal 0.5-1.0' (585.7 - 585.2)</p> <p>Cement grout 0 - 0.5' (586.2 - 585.7')</p> <p>5-foot long protective casing with locking cap.</p> <p>Three protective posts installed.</p>

Comments:    <sup>1</sup> Elevation in feet MSL  
 Vertical Scale : 1" = 5'

Sheet 1 of 1

**BARR ENGINEERING CO.**  
Minneapolis, Minnesota

Well No. MW-4D

Date Completed 3/20/92

Riser Pipe Elevation 589.06<sup>1</sup>

Crew Chief P. Dickinson (WTD)

**Ground Surface Elevation 586.1**

BOREHOLE CONSTRUCTION NOTES	LITHOLOGY	WELL CONSTRUCTION	WELL CONSTRUCTION NOTES
<p>Borehole advanced from 0' to 32.0' (586.1-554.1) using 6 1/4-inch I.D. hollow stem auger.</p> <p>Inside of auger flushed potable water.</p> <p>Well screen and riser pipe placed in the borehole.</p> <p>Sand pack and then bentonite pellets placed as auger retracted.</p> <p>Neat cement grout to surface.</p>	<p>Silty Sand/Fill 0.5'</p> <p>Coal Fines 1.0'</p> <p>Fine to Medium Sand Fill 5.0'</p> <p>Medium Sand</p> <p>31.0' Gravel</p> <p>31.5' Silt</p> <p>32.0' E.O.B.</p>		<p>Stickup: 2.96'</p> <p>2 -inch diameter, stainless steel riser pipe 0' to 27.0' (586.1-559.1).</p> <p>2-inch diameter, 5' long, # 10 slot size stainless steel screen, 27.0-32.0' (559.1 - 554.1)</p> <p>Sandpack 22.0'-32.0' (564.1 - 554.1)</p> <p>Bentonite seal 20.0-22.0' (566.1- 564.1)</p> <p>Cement grout 0 - 20.0' (586.1 - 566.1)</p> <p>5-foot long steel protective casing with locking cap.</p> <p>Three protective posts installed.</p>


Comments: 1 Elevation in feet MSL  
Vertical Scale : 1" = 5'

Sheet 1 of 1

# WELL LOG

**BARR ENGINEERING CO.**  
Minneapolis, Minnesota

Project WCP RI/ES Phase I Well No. MW-5S  
Date Started 3/20/92  
Date Completed 3/20/92 Riser Pipe Elevation 587.89'  
Field Inspector S. Marshik (BEC)  
Crew Chief B. Loveland(WTD) Ground Surface Elevation 585.4

BOREHOLE CONSTRUCTION NOTES	LITHOLOGY	WELL CONSTRUCTION	WELL CONSTRUCTION NOTES
<p>Borehole advanced from 0' to 15.0' (585.4-570.4) using 6 1/4-inch I.D. hollow stem auger.</p> <p>Inside of auger flushed with potable water.</p> <p>Well screen and riser pipe placed in the borehole.</p> <p>Sand pack and then bentonite pellets placed as auger retracted.</p> <p>Neat cement grout to surface.</p> <p>Water level was 4.8' below surface on 3-20-92.</p>	<p>Fine Sand Fill</p> <p>5.0'</p> <p>Fine Sand 7.0'</p> <p>Fine to Medium Sand with Gravel 12.0'</p> <p>Fine Sand with Trace Silt 15.0'</p> <p>E.O.B.</p>		<p>Stickup: 2.49'</p> <p>2 -inch diameter, stainless steel riser pipe 0' to 2.8' (585.4-582.6).</p> <p>2-inch diameter, 10.4' long #10 slot size stainless steel screen 2.8' - 13.2' (582.6-572.2).</p> <p>Sandpack 1.8' to 15.0' (583.6 - 570.4).</p> <p>Bentonite seal 1.0' - 1.8' (584.4 - 583.6).</p> <p>Cement grout 0 - 1.0'.</p> <p>5-foot long steel protective casing with locking cap.</p> <p>Three protective posts installed.</p>



# WELL LOG

**BARR ENGINEERING CO.**  
Minneapolis, Minnesota


Project WCP RI/ES Phase I Well No. MW-5D  
Date Started 3/23/92  
Date Completed 3/23/92 Riser Pipe Elevation 588.47'  
Field Inspector J. Fox (BEC)  
Crew Chief B. Loveland(WTD) Ground Surface Elevation 585.7

BOREHOLE CONSTRUCTION NOTES	LITHOLOGY	WELL CONSTRUCTION	WELL CONSTRUCTION NOTES
<p>Borehole advanced from 0' to 26.0' (585.4-559.7) using 6 1/4-inch I.D. hollow stem auger.</p> <p>Inside of auger flushed with potable water.</p> <p>Well screen and riser pipe placed in borehole.</p> <p>Sand pack and then bentonite pellets placed as auger retracted.</p> <p>Neat cement grout to surface.</p>	<p>Fine Sand Fill</p> <p>5.0'</p> <p>Fine Sand</p> <p>7.0'</p> <p>Fine to Medium Sand with Gravel</p> <p>12.0'</p> <p>Fine Sand with a Trace of Silt</p> <p>22.0'</p> <p>Fine to Medium Sand</p> <p>25.5'</p> <p>Gravel</p> <p>25.7'</p> <p>Silt</p> <p>26.0'</p> <p>E.O.B.</p>		<p>Stickup: 2.77'</p> <p>2-inch diameter, stainless steel riser pipe 0' to 14.0' (585.7-571.7).</p> <p>2-inch diameter, 5' long, #10 slot size stainless steel screen, flush threaded 21.0'-26.0' (564.7 - 559.7)</p> <p>Sandpack 16.0' - 26.0' (569.7' - 559.7).</p> <p>Bentonite seal 14.0' - 16.0' (571.7' - 569.7')</p> <p>Cement grout 0 - 14.0' (585.7' - 571.7')</p> <p>5-foot long steel protective casing with locking cap.</p> <p>Three protective posts installed.</p>

# WELL LOG

**BARR ENGINEERING CO.**  
Minneapolis, Minnesota

Project WCP RI/ES Phase I Well No. MW-6S  
 Date Started 3/25/92  
 Date Completed 3/25/92 Riser Pipe Elevation 588.45'  
 Field Inspector T. Wright-Wells (BEC)  
 Crew Chief P. Dickinson (WTD) Ground Surface Elevation 585.7

BOREHOLE CONSTRUCTION NOTES	LITHOLOGY	WELL CONSTRUCTION	WELL CONSTRUCTION NOTES
<p>Borehole advanced from 0' to 13.5' (585.7 - 572.2) using 6 1/4-inch I.D. hollow stem auger.</p> <p>Inside of auger flushed potable water.</p> <p>Well screen and riser pipe placed in borehole.</p> <p>Sand pack and then bentonite pellets placed as auger retracted.</p> <p>Neat cement grout to surface.</p>	<p>Fine to Medium Sand Fill</p> <p style="text-align: center;">7.5'</p> <p>Fine to Medium Sand</p> <p style="text-align: center;">14.0' E.O.B.</p>		<p>Stickup: 2.75</p> <p>2 -inch diameter, stainless steel riser pipe 0' to 3.5' (585.7 - 582.2).</p> <p>2-inch diameter, 10' long, #10 slot size stainless steel screen 3.5-13.5' (582.2-572.2)</p> <p>Sandpack 2.5 - 13.5' (583.2 - 572.2)</p> <p>Bentonite seal 1.0-2.5' (584.7 - 583.2)</p> <p>Cement grout 0 - 1.0' (585.7 - 584.7)</p> <p>5- foot long protective casing with locking cap.</p> <p>Three protective posts installed.</p>


Comments:    <sup>1</sup> Elevation in feet MSL  
 Vertical Scale : 1" = 5'

Sheet 1 of 1

# WELL LOG

BARR ENGINEERING CO.  
Minneapolis, Minnesota

Project WCP RI/FS Phase I Well No. MW-6D  
 Date Started 3/24/92  
 Date Completed 3/24/92 Riser Pipe Elevation 588.51'  
 Field Inspector T. Wright-Wells (BEC)  
 Crew Chief B. Loveland (WTD) Ground Surface Elevation 585.7

BOREHOLE CONSTRUCTION NOTES	LITHOLOGY	WELL CONSTRUCTION	WELL CONSTRUCTION NOTES
<p>Borehole advanced from 0' to 27.5' (585.7 - 558.2) using 6 1/4-inch I.D. hollow stem auger.</p> <p>Inside of auger flushed with potable water.</p> <p>Well screen and riser pipe placed in borehole.</p> <p>Sand pack and then bentonite pellets placed as auger retracted.</p> <p>Neat cement grout to surface.</p>	<p>Fine to Medium Sand Fill</p> <p>7.5'</p> <p>Fine to Medium Sand</p> <p>26.2' Gravel</p> <p>26.5' Silt</p> <p>27.5' E.O.B.</p>		<p>Stickup: 2.81</p> <p>2-inch diameter, stainless steel riser pipe 0' to 21.5' (585.7 - 564.2).</p> <p>2-inch diameter, 5' long, #10 slot size stainless steel screen, 21.5 - 26.5' (564.2-559.2)</p> <p>Sandpack 16.5 - 26.5' (569.2- 559.2)</p> <p>Bentonite seal 14.5 - 16.5' (571.2-569.2)</p> <p>Cement grout 0 - 14.5' (585.7 - 571.2)</p> <p>5-foot long protective casing with locking cap.</p> <p>Three protective posts installed.</p>


Comments: <sup>1</sup> Elevation in feet MSL  
Vertical Scale : 1" = 5'

Sheet 1 of 1

# WELL LOG

**BARR ENGINEERING CO.**  
Minneapolis, Minnesota

Project WCP RI/FS Phase I Well No. P-101  
 Date Started 3/9/92  
 Date Completed 3/9/92 Riser Pipe Elevation 588.14'  
 Field Inspector K. French (BEC)  
 Crew Chief P. Dickinson (WTD) Ground Surface Elevation 585.0

BOREHOLE CONSTRUCTION NOTES	LITHOLOGY	WELL CONSTRUCTION	WELL CONSTRUCTION NOTES
<p>Hollow stem auger method.</p> <p>Borehole advanced from 0' to 14.0' (585.0-571.0) using 3 1/4-inch I.D. hollow stem auger.</p> <p>Inside of auger flushed with potable water.</p> <p>Well screen and riser pipe placed in the borehole.</p> <p>Sand pack and then bentonite pellets placed as auger retracted.</p> <p>Neat cement grout to surface.</p> <p>Water level was 5.94' below the top of the riser on 3/9/92 (582.2).</p>	<p>Silty Sand Fill 1.0'</p> <p>Fine to Medium Sand</p> <p>14.0' E.O.B.</p>		<p>Stickup: 3.14'</p> <p>1 1/4 -inch diameter, Schedule 40 PVC riser pipe 0' to 2.1' (585.0-582.9).</p> <p>10.0 foot long, 1 1/4-inch diameter #10 slot size, Schedule 40 PVC screen 2.1- 12.1' (582.9-572.9)</p> <p>Sandpack 1.5' to 14.0' (583.5 - 571.0)</p> <p>Bentonite seal 1.0' to 1.5' (584.0- 583.5)</p> <p>Cement grout 0' to 1.0' (585.0-584.0)</p> <p>5-foot long steel protective casing with locking cap.</p> <p>Three protective posts installed.</p>


Comments:    <sup>1</sup> Elevation in feet MSL  
 Vertical Scale : 1" = 5'

Sheet 1 of 1

# WELL LOG

**BARR ENGINEERING CO.**  
Minneapolis, Minnesota


Project WCP RI/ES Phase I Well No. P-102  
 Date Started 3/12/92  
 Date Completed 3/12/92 Riser Pipe Elevation 588.52'  
 Field Inspector K. French (BEG)  
 Crew Chief P. Dickinson (WTD) Ground Surface Elevation 585.6

BOREHOLE CONSTRUCTION NOTES	LITHOLOGY	WELL CONSTRUCTION	WELL CONSTRUCTION NOTES
<p>Hollow stem auger method.</p> <p>Borehole advanced from 0' to 14.0' (585.6-571.6) using 3 1/4-inch I.D. hollow stem auger.</p> <p>Inside of auger flushed with potable water.</p> <p>Well screen and riser pipe placed in the borehole.</p> <p>Sand pack and then bentonite pellets placed as auger retracted.</p> <p>Neat cement grout to surface.</p> <p>Water level was 5.52' below the top of the riser on 3/13/92 (583.0).</p>	<p>Medium to Coarse Sand Fill 2.0'</p> <p>Fine to Medium Sand</p> <p>14.0' E.O.B.</p>		<p>Stickup: 2.92'</p> <p>1 1/4 -inch diameter, Schedule 40 PVC riser pipe 0' to 2.2' (585.6-583.4).</p> <p>9.96 foot long, 1 1/4-inch diameter Schedule 40 PVC #10 slot size screen 2.2-12.2' (583.4-573.4)</p> <p>Sandpack 1.5' to 14.0' (584.1- 571.6)</p> <p>Bentonite seal 1.0' to 1.5' (584.6- 584.1)</p> <p>Cement grout 0' to 1.0' (585.6-584.6)</p> <p>5-foot long steel protective casing with locking cap.</p> <p>Three protective posts installed.</p>

# WELL LOG

**BARR ENGINEERING CO.**  
Minneapolis, Minnesota

Project WCP RI/FS Phase I Well No. P-103  
 Date Started 3/12/92  
 Date Completed 3/13/92 Riser Pipe Elevation 589.44'  
 Field Inspector K. French (BEC)  
 Crew Chief P. Dickinson (WTD) Ground Surface Elevation 586.4

BOREHOLE CONSTRUCTION NOTES	LITHOLOGY	WELL CONSTRUCTION	WELL CONSTRUCTION NOTES
<p>Hollow stem auger method.</p> <p>Borehole advanced from 0' to 14.5' (586.4-571.9) using 3 1/4-inch I.D. hollow stem auger.</p> <p>Inside of auger flushed with potable water.</p> <p>Well screen and riser pipe placed in the borehole.</p> <p>Sand pack and then bentonite pellets placed as auger retracted.</p> <p>Neat cement grout to surface.</p> <p>Water level was 5.39' below surface (581.01) on 3-13-92.</p>	<p>Fine to Medium Sand Fill 1.0'</p> <p>Fine to Medium Sand</p> <p>5.39'</p> <p>14.0' E.O.B.</p>		<p>Stickup: 3.04'</p> <p>1 1/4 -inch diameter, Schedule 40 PVC riser pipe 0' to 2.5' (586.4-583.9).</p> <p>9.95 foot long, 1 1/4-inch diameter Schedule 40 PVC #10 slot size screen 2.5 - 12.5 (583.9-573.9)</p> <p>Sandpack 1.5' to 14.5' (584.9 - 571.9)</p> <p>Bentonite seal 1.0' to 1.5' (585.4 - 584.9)</p> <p>Cement grout 0' to 1.0' (586.4-585.4)</p> <p>5-foot long steel protective casing with locking cap.</p> <p>Three protective posts installed.</p>


Comments:    <sup>1</sup> Elevation in feet MSL  
 Vertical Scale : 1" = 5'

Sheet 1 of 1

# WELL LOG

**BARR ENGINEERING CO.**  
Minneapolis, Minnesota

Project WCP RI/ES Phase I Well No. P-104  
 Date Started 3/12/92  
 Date Completed 3/12/92 Riser Pipe Elevation 589.07'  
 Field Inspector K. French (BEC)  
 Crew Chief P. Dickinson (WTD) Ground Surface Elevation 586.0

BOREHOLE CONSTRUCTION NOTES	LITHOLOGY	WELL CONSTRUCTION	WELL CONSTRUCTION NOTES
<p>Hollow stem auger method.</p> <p>Borehole advanced from 0' to 14.0' (586.0-572.0) using 3 1/4-inch I.D. hollow stem auger.</p> <p>Inside of auger flushed with potable water.</p> <p>Well screen and riser pipe placed in the borehole.</p> <p>Sand pack and then bentonite pellets placed as auger retracted.</p> <p>Neat cement grout to surface.</p> <p>Water level was 3.5' below surface (582.5) on 3-13-92.</p>	<p>Poorly Graded Sand Fill 2.5'</p> <p>Fine to Medium Sand</p> <p>14.0' E.O.B.</p>		<p>Stickup: 3.07'</p> <p>1 1/4 -inch diameter, Schedule 40 PVC riser pipe 0' to 2.5' (586.0-583.5).</p> <p>9.95 foot long, 1 1/4-inch diameter Schedule 40 PVC #10 slot size screen 2.1-12.0' (583.9-574.0)</p> <p>Sandpack 1.5' to 14.5' (584.5- 571.5)</p> <p>Bentonite seal 1.0' to 1.5' (585.0-584.5)</p> <p>Cement grout 0' to 1.0' (586.0-585.0)</p> <p>5-foot long steel protective casing with locking cap.</p> <p>Three protective posts installed.</p>

***Appendix F***

***Field Log Data Sheets - Well Development  
and Water Level Data Sheets***



***Field Log Data Sheets -  
Well Development***

# Barr

Engineering Company

## FIELD LOG DATA SHEET

Station: MW-35

Client: NSG/WCP

Project No. 131-491-10103JSLB11

Location: Waukegan, IL Date: 3/25/92 Sample Time: \_\_\_\_\_

General		Stabilization Test					
		TIME/ VOLUME	TEMP CENT.	COND. umhos	COND. @ 25	pH	Eh
Barr Lock: Y N	Y	1. 2:35/750	9.3	490		7.30	
Casing Dia: (in.)	2	2. 2:40/825	9.0	490		7.09	
Total Depth (ft.)	12	3. 2:45/900	9.0	490		7.02	
Static Depth (ft.)	--	4. 2:50/975	8.9	490		7.07	
Water Depth:	5'(TOL)	5.					
Well Vol. (gal.)	1.5	6.					
Purge Method:	pump + surge	7.					
Samp. Method:	—	Appearance: slight oil sheen					
Start Time:	1:45	Odor: none					
Stop Time:	2:50	Comments:					
Duration: (min.)	65						
Rate, gpm:	15						
Volume Purged:	975						
Samplers: TWW, JMF		Others Present:					
gen _____ VOC _____ COD _____ TOC _____ semi-volatile _____ f. metal _____ t. metal _____							
nitro _____ cyanide _____ oil & grease _____ 200 ml filter _____ 500 ml filter _____							
others _____							

# Barr

Engineering Company

## FIELD LOG DATA SHEET

Station: MW-4S

Client: NSG/WCP

Project No. 113-491-10103JS-4311

Location: Waukegan, IL Date: 3/25/92 Sample Time: \_\_\_\_\_

General		Stabilization Test					
		TIME/ VOLUME	TEMP CENT.	COND. umhos	COND. @ 25	pH	Eh
Barr Lock: Y N	Y	1. 6:15/675	8.5	SSD		7.40	
Casing Dia: (in.)	2	2. 6:20/750	8.4	SSD		7.21	
Total Depth (ft.)	12.0	3. 6:25/825	8.3	SSD		7.30	
Static Depth (ft.)	--	4. 6:40/900	8.3	SSD		7.36	
Water Depth:	6.8 (TOL)	5. 6:45/975	8.3	SSD		7.39	
Well Vol. (gal.)	1.2	6.					
Purge Method:	Pump + Surge	7.					
Samp. Method:	—	Appearance: clear, after a few minutes					
Start Time:	5:30	Odor: yes-					
Stop Time:	6:46	Comments: - pump stopped fr 6:26-6:35 + restarted.					
Duration: (min.)	76						
Rate, gpm:	±15						
Volume Purged:	975						
Samplers: JMF, TWW		Others Present:					
gen _____ VOC _____ COD _____ TOC _____ semi-volatile _____ f. metal _____ t. metal _____							
nitro _____ cyanide _____ oil & grease _____ 200 ml filter _____ 500 ml filter _____							
others _____							

# Barr

Engineering Company

## FIELD LOG DATA SHEET

Station: MW-SS

Client: NSG/WCP

Project No. 13149-1003JS4311

Location: Waukegan II

Date: 3/25/92

Sample Time: \_\_\_\_\_

General		Stabilization Test					
		TIME/ VOLUME	TEMP CENT.	COND. umhos	COND. @ 25	pH	Eh
Barr Lock: Y N	✓	1.4:20/75	8.3	320		7.57	
Casing Dia: (in.)	2	2.4:25/100	8.2	320		7.59	
Total Depth (ft.)	13.2	3.4:30/125	8.3	320		7.51	
Static Depth (ft.)	—	4.4:35/175	8.1	312		7.60	
Water Depth:	5.8' (tol)	5.4:40/225	8.1	310		7.69	
Well Vol. (gal.)	1.6	6.4:45/275	7.9	309		7.70	
Purge Method:	Pump + Surge	7.					
Samp. Method:	—	Appearance: clear, after 50 gals					
Start Time:	4:05	Odor: none					
Stop Time:	4:50	Comments: - increased pumping rate fr. 5 to 10 gpm at 4:31 - pump shut off for 1 minute + restarted					
Duration: (min.)	45						
Rate, gpm:	5-10						
Volume Purged:	325						
Samplers: JMF, TWW		Others Present:					
gen _____		VOC _____ COD _____ TOC _____ semi-volatile _____ f. metal _____ t. metal _____					
nitro _____		cyanide _____ oil & grease _____ 200 ml filter _____ 500 ml filter _____					
others _____							

# Barr

Engineering Company

## FIELD LOG DATA SHEET

Station: MW-65

Client: NSG/WCP

Project No. 11B1-1491-1003JS14311

Location: Waukegan IL Date: 3/27/92 Sample Time: \_\_\_\_\_

General		Stabilization Test					
		TIME/ VOLUME	TEMP CENT.	COND. umhos	COND. @ 25	pH	Eh
Barr Lock: Y N	Y	1. <sup>12:25</sup> /	9.6	1000		7.66	
Casing Dia: (in.)	2	2. <sup>12:30</sup> /	9.5	1000		7.76	
Total Depth (ft.)	13.5	3. <sup>12:35</sup> /	9.9	1000		7.75	
Static Depth (ft.)	—	4.					
Water Depth:	8.0(TOC)	5.					
Well Vol. (gal.)	1.3	6.					
Purge Method:	pump surge	7.					
Samp. Method:	—	Appearance: <u>clear</u>					
Start Time:	10:30	Odor: <u>yes</u>					
Stop Time:	12:35	Comments:					
Duration: (min.)	125						
Rate, gpm:	69gpm						
Volume Purged:	750						
Samplers: <u>TWW, JMF</u>		Others Present: <u>WTD</u>					
gen _____ VOC _____ COD _____ TOC _____ semi-volatile _____ f. metal _____ t. metal _____							
nitro _____ cyanide _____ oil & grease _____ 200 ml filter _____ 500 ml filter _____							
others _____							

# Barr

Engineering Company

## FIELD LOG DATA SHEET

Station: 111-23

Client: NSG/WCP

Project No. 134142-1342111111

Location: Waukegan Date: 2/14/97 Sample Time: \_\_\_\_\_

General		Stabilization Test					
		TIME/ VOLUME	TEMP CENT.	COND. umhos	COND. @ 25	pH	Eh
Barr Lock: Y N	<u>Y</u>	1. <u>6:19</u> / <u>448</u>	<u>27</u>	<u>750</u>		<u>8.76</u>	
Casing Dia: (in.)	<u>2</u>	2. <u>6:50</u> / <u>455</u>	<u>27</u>	<u>750</u>		<u>8.75</u>	
Total Depth (ft.)	<u>27.8</u>	3. <u>7:19</u> / <u>462</u>	<u>27</u>	<u>750</u>		<u>8.75</u>	
Static Depth (ft.)	<u>—</u>	4.					
Water Depth:	<u>5.9 (200)</u>	5.					
Well Vol. (gal.)	<u>3.3</u>	6.					
Purge Method:	<u>pump surge</u>	7.					
Samp. Method:	<u>—</u>	Appearance: <u>colorless, no silt</u>					
Start Time:	<u>5:15</u>	Odor: <u>—</u>					
Stop Time:	<u>6:31</u>	Comments: <u>Proton</u>					
Duration: (min.)	<u>76</u>						
Rate, gpm:	<u>7</u>						
Volume Purged:	<u>550</u>						
Samplers: <u>TWW, JMF</u>		Others Present:					
gen _____ VOC _____ COD _____ TOC _____ semi-volatile _____ f. metal _____ t. metal _____							
nitro _____ cyanide _____ oil & grease _____ 200 ml filter _____ 500 ml filter _____							
others _____							

## MONITORING WELL DEVELOPMENT

WELL NUMBER MW-DA D

WELL DIAMETER ~~2.0~~ 2" SS

TOTAL DEPTH 32.0

DEPTH TO WATER BEFORE DEVELOPMENT 6.8 TOC

DEPTH TO WATER AFTER DEVELOPMENT 6.8 TOC

PROJECT NO. 3568

DATE March 23, 92

DEVELOPED BY PD

### DESCRIPTION OF DEVELOPMENT METHOD

1.7 BK hand pump 75 gal. March 23, 92

Trash Pump 5 gal/min  
surge w/Bailer

3-26-92

Trash pump

150 gal

3-27-92

VOLUME OF WATER REMOVED FROM WELL

~~7500~~

1,950

CLARITY OF WATER IN WELL BEFORE DEVELOPMENT

Silty dark Bm / gray

CLARITY OF WATER IN WELL AFTER DEVELOPMENT

Silty Lt. Bm

VOLUME OF WATER ADDED TO WELL

none.

SOURCE OF WATER ADDED TO WELL

none

TIME SPENT FOR DEVELOPMENT

9 hours

COMMENTS:



ENVIRONMENTAL DRILLING  
**WTD**  
A DIVISION OF LONGYEAR COMPANY

# Barr

Engineering Company

## FIELD LOG DATA SHEET

Station: MW-4D

Client: NSG/WCP

Project No. 1131-1491-10103JISL4311

Location: Waukegan, IL Date: 3/26/92 Sample Time: \_\_\_\_\_

General		Stabilization Test					
		TIME/ VOLUME	TEMP CENT.	COND. umhos	COND. @ 25	pH	Eh
Barr Lock: Y N	<u>Y</u>	1. <u>3:45</u> <u>1400</u>	<u>11.4</u>	<u>7000</u>		<u>8.55</u>	
Casing Dia: (in.)	<u>2</u>	2. <u>3:50</u> <u>1425</u>	<u>11.1</u>	<u>7000</u>		<u>8.49</u>	
Total Depth (ft.)	<u>32'</u>	3. <u>3:55</u> <u>1450</u>	<u>11.7</u>	<u>7000</u>		<u>8.45</u>	
Static Depth (ft.)	<u>-</u>	4. <u>4:00</u> <u>1475</u>	<u>11.5</u>	<u>7000</u>		<u>8.44</u>	
Water Depth:	<u>6.8</u> <u>1500</u>	5. <u>4:05</u> <u>1500</u>	<u>11.5</u>	<u>7000</u>		<u>8.44</u>	
Well Vol. (gal.)	<u>3.8</u>	6.					
Purge Method:	<u>Pump &amp; Surge</u>	7.					
Samp. Method:	<u>-</u>	Appearance: <u>cloudy, yellowish, green tint</u>					
Start Time:	<u>11:30</u>	Odor: <u>VEG -</u>					
Stop Time:	<u>4:06</u>	Comments: <u>1. 2. 3. 4. 5. 6. 7. 8. 9. 10. 11. 12. 13. 14. 15. 16. 17. 18. 19. 20. 21. 22. 23. 24. 25. 26. 27. 28. 29. 30. 31. 32. 33. 34. 35. 36. 37. 38. 39. 40. 41. 42. 43. 44. 45. 46. 47. 48. 49. 50. 51. 52. 53. 54. 55. 56. 57. 58. 59. 60. 61. 62. 63. 64. 65. 66. 67. 68. 69. 70. 71. 72. 73. 74. 75. 76. 77. 78. 79. 80. 81. 82. 83. 84. 85. 86. 87. 88. 89. 90. 91. 92. 93. 94. 95. 96. 97. 98. 99. 100. 101. 102. 103. 104. 105. 106. 107. 108. 109. 110. 111. 112. 113. 114. 115. 116. 117. 118. 119. 120. 121. 122. 123. 124. 125. 126. 127. 128. 129. 130. 131. 132. 133. 134. 135. 136. 137. 138. 139. 140. 141. 142. 143. 144. 145. 146. 147. 148. 149. 150. 151. 152. 153. 154. 155. 156. 157. 158. 159. 160. 161. 162. 163. 164. 165. 166. 167. 168. 169. 170. 171. 172. 173. 174. 175. 176. 177. 178. 179. 180. 181. 182. 183. 184. 185. 186. 187. 188. 189. 190. 191. 192. 193. 194. 195. 196. 197. 198. 199. 200. 201. 202. 203. 204. 205. 206. 207. 208. 209. 210. 211. 212. 213. 214. 215. 216. 217. 218. 219. 220. 221. 222. 223. 224. 225. 226. 227. 228. 229. 230. 231. 232. 233. 234. 235. 236. 237. 238. 239. 240. 241. 242. 243. 244. 245. 246. 247. 248. 249. 250. 251. 252. 253. 254. 255. 256. 257. 258. 259. 260. 261. 262. 263. 264. 265. 266. 267. 268. 269. 270. 271. 272. 273. 274. 275. 276. 277. 278. 279. 280. 281. 282. 283. 284. 285. 286. 287. 288. 289. 290. 291. 292. 293. 294. 295. 296. 297. 298. 299. 300. 301. 302. 303. 304. 305. 306. 307. 308. 309. 310. 311. 312. 313. 314. 315. 316. 317. 318. 319. 320. 321. 322. 323. 324. 325. 326. 327. 328. 329. 330. 331. 332. 333. 334. 335. 336. 337. 338. 339. 340. 341. 342. 343. 344. 345. 346. 347. 348. 349. 350. 351. 352. 353. 354. 355. 356. 357. 358. 359. 360. 361. 362. 363. 364. 365. 366. 367. 368. 369. 370. 371. 372. 373. 374. 375. 376. 377. 378. 379. 380. 381. 382. 383. 384. 385. 386. 387. 388. 389. 390. 391. 392. 393. 394. 395. 396. 397. 398. 399. 400. 401. 402. 403. 404. 405. 406. 407. 408. 409. 410. 411. 412. 413. 414. 415. 416. 417. 418. 419. 420. 421. 422. 423. 424. 425. 426. 427. 428. 429. 430. 431. 432. 433. 434. 435. 436. 437. 438. 439. 440. 441. 442. 443. 444. 445. 446. 447. 448. 449. 450. 451. 452. 453. 454. 455. 456. 457. 458. 459. 460. 461. 462. 463. 464. 465. 466. 467. 468. 469. 470. 471. 472. 473. 474. 475. 476. 477. 478. 479. 480. 481. 482. 483. 484. 485. 486. 487. 488. 489. 490. 491. 492. 493. 494. 495. 496. 497. 498. 499. 500. 501. 502. 503. 504. 505. 506. 507. 508. 509. 510. 511. 512. 513. 514. 515. 516. 517. 518. 519. 520. 521. 522. 523. 524. 525. 526. 527. 528. 529. 530. 531. 532. 533. 534. 535. 536. 537. 538. 539. 540. 541. 542. 543. 544. 545. 546. 547. 548. 549. 550. 551. 552. 553. 554. 555. 556. 557. 558. 559. 560. 561. 562. 563. 564. 565. 566. 567. 568. 569. 570. 571. 572. 573. 574. 575. 576. 577. 578. 579. 580. 581. 582. 583. 584. 585. 586. 587. 588. 589. 590. 591. 592. 593. 594. 595. 596. 597. 598. 599. 600. 601. 602. 603. 604. 605. 606. 607. 608. 609. 610. 611. 612. 613. 614. 615. 616. 617. 618. 619. 620. 621. 622. 623. 624. 625. 626. 627. 628. 629. 630. 631. 632. 633. 634. 635. 636. 637. 638. 639. 640. 641. 642. 643. 644. 645. 646. 647. 648. 649. 650. 651. 652. 653. 654. 655. 656. 657. 658. 659. 660. 661. 662. 663. 664. 665. 666. 667. 668. 669. 670. 671. 672. 673. 674. 675. 676. 677. 678. 679. 680. 681. 682. 683. 684. 685. 686. 687. 688. 689. 690. 691. 692. 693. 694. 695. 696. 697. 698. 699. 700. 701. 702. 703. 704. 705. 706. 707. 708. 709. 710. 711. 712. 713. 714. 715. 716. 717. 718. 719. 720. 721. 722. 723. 724. 725. 726. 727. 728. 729. 730. 731. 732. 733. 734. 735. 736. 737. 738. 739. 740. 741. 742. 743. 744. 745. 746. 747. 748. 749. 750. 751. 752. 753. 754. 755. 756. 757. 758. 759. 760. 761. 762. 763. 764. 765. 766. 767. 768. 769. 770. 771. 772. 773. 774. 775. 776. 777. 778. 779. 780. 781. 782. 783. 784. 785. 786. 787. 788. 789. 790. 791. 792. 793. 794. 795. 796. 797. 798. 799. 800. 801. 802. 803. 804. 805. 806. 807. 808. 809. 810. 811. 812. 813. 814. 815. 816. 817. 818. 819. 820. 821. 822. 823. 824. 825. 826. 827. 828. 829. 830. 831. 832. 833. 834. 835. 836. 837. 838. 839. 840. 841. 842. 843. 844. 845. 846. 847. 848. 849. 850. 851. 852. 853. 854. 855. 856. 857. 858. 859. 860. 861. 862. 863. 864. 865. 866. 867. 868. 869. 870. 871. 872. 873. 874. 875. 876. 877. 878. 879. 880. 881. 882. 883. 884. 885. 886. 887. 888. 889. 890. 891. 892. 893. 894. 895. 896. 897. 898. 899. 900. 901. 902. 903. 904. 905. 906. 907. 908. 909. 910. 911. 912. 913. 914. 915. 916. 917. 918. 919. 920. 921. 922. 923. 924. 925. 926. 927. 928. 929. 930. 931. 932. 933. 934. 935. 936. 937. 938. 939. 940. 941. 942. 943. 944. 945. 946. 947. 948. 949. 950. 951. 952. 953. 954. 955. 956. 957. 958. 959. 960. 961. 962. 963. 964. 965. 966. 967. 968. 969. 970. 971. 972. 973. 974. 975. 976. 977. 978. 979. 980. 981. 982. 983. 984. 985. 986. 987. 988. 989. 990. 991. 992. 993. 994. 995. 996. 997. 998. 999. 1000. 1001. 1002. 1003. 1004. 1005. 1006. 1007. 1008. 1009. 1010. 1011. 1012. 1013. 1014. 1015. 1016. 1017. 1018. 1019. 1020. 1021. 1022. 1023. 1024. 1025. 1026. 1027. 1028. 1029. 1030. 1031. 1032. 1033. 1034. 1035. 1036. 1037. 1038. 1039. 1040. 1041. 1042. 1043. 1044. 1045. 1046. 1047. 1048. 1049. 1050. 1051. 1052. 1053. 1054. 1055. 1056. 1057. 1058. 1059. 1060. 1061. 1062. 1063. 1064. 1065. 1066. 1067. 1068. 1069. 1070. 1071. 1072. 1073. 1074. 1075. 1076. 1077. 1078. 1079. 1080. 1081. 1082. 1083. 1084. 1085. 1086. 1087. 1088. 1089. 1090. 1091. 1092. 1093. 1094. 1095. 1096. 1097. 1098. 1099. 1100. 1101. 1102. 1103. 1104. 1105. 1106. 1107. 1108. 1109. 1110. 1111. 1112. 1113. 1114. 1115. 1116. 1117. 1118. 1119. 1120. 1121. 1122. 1123. 1124. 1125. 1126. 1127. 1128. 1129. 1130. 1131. 1132. 1133. 1134. 1135. 1136. 1137. 1138. 1139. 1140. 1141. 1142. 1143. 1144. 1145. 1146. 1147. 1148. 1149. 1150. 1151. 1152. 1153. 1154. 1155. 1156. 1157. 1158. 1159. 1160. 1161. 1162. 1163. 1164. 1165. 1166. 1167. 1168. 1169. 1170. 1171. 1172. 1173. 1174. 1175. 1176. 1177. 1178. 1179. 1180. 1181. 1182. 1183. 1184. 1185. 1186. 1187. 1188. 1189. 1190. 1191. 1192. 1193. 1194. 1195. 1196. 1197. 1198. 1199. 1200. 1201. 1202. 1203. 1204. 1205. 1206. 1207. 1208. 1209. 1210. 1211. 1212. 1213. 1214. 1215. 1216. 1217. 1218. 1219. 1220. 1221. 1222. 1223. 1224. 1225. 1226. 1227. 1228. 1229. 1230. 1231. 1232. 1233. 1234. 1235. 1236. 1237. 1238. 1239. 1240. 1241. 1242. 1243. 1244. 1245. 1246. 1247. 1248. 1249. 1250. 1251. 1252. 1253. 1254. 1255. 1256. 1257. 1258. 1259. 1260. 1261. 1262. 1263. 1264. 1265. 1266. 1267. 1268. 1269. 1270. 1271. 1272. 1273. 1274. 1275. 1276. 1277. 1278. 1279. 1280. 1281. 1282. 1283. 1284. 1285. 1286. 1287. 1288. 1289. 1290. 1291. 1292. 1293. 1294. 1295. 1296. 1297. 1298. 1299. 1300. 1301. 1302. 1303. 1304. 1305. 1306. 1307. 1308. 1309. 1310. 1311. 1312. 1313. 1314. 1315. 1316. 1317. 1318. 1319. 1320. 1321. 1322. 1323. 1324. 1325. 1326. 1327. 1328. 1329. 1330. 1331. 1332. 1333. 1334. 1335. 1336. 1337. 1338. 1339. 1340. 1341. 1342. 1343. 1344. 1345. 1346. 1347. 1348. 1349. 1350. 1351. 1352. 1353. 1354. 1355. 1356. 1357. 1358. 1359. 1360. 1361. 1362. 1363. 1364. 1365. 1366. 1367. 1368. 1369. 1370. 1371. 1372. 1373. 1374. 1375. 1376. 1377. 1378. 1379. 1380. 1381. 1382. 1383. 1384. 1385. 1386. 1387. 1388. 1389. 1390. 1391. 1392. 1393. 1394. 1395. 1396. 1397. 1398. 1399. 1400. 1401. 1402. 1403. 1404. 1405. 1406. 1407. 1408. 1409. 1410. 1411. 1412. 1413. 1414. 1415. 1416. 1417. 1418. 1419. 1420. 1421. 1422. 1423. 1424. 1425. 1426. 1427. 1428. 1429. 1430. 1431. 1432. 1433. 1434. 1435. 1436. 1437. 1438. 1439. 1440. 1441. 1442. 1443. 1444. 1445. 1446. 1447. 1448. 1449. 1450. 1451. 1452. 1453. 1454. 1455. 1456. 1457. 1458. 1459. 1460. 1461. 1462. 1463. 1464. 1465. 1466. 1467. 1468. 1469. 1470. 1471. 1472. 1473. 1474. 1475. 1476. 1477. 1478. 1479. 1480. 1481. 1482. 1483. 1484. 1485. 1486. 1487. 1488. 1489. 1490. 1491. 1492. 1493. 1494. 1495. 1496. 1497. 1498. 1499. 1500. 1501. 1502. 1503. 1504. 1505. 1506. 1507. 1508. 1509. 1510. 1511. 1512. 1513. 1514. 1515. 1516. 1517. 1518. 1519. 1520. 1521. 1522. 1523. 1524. 1525. 1526. 1527. 1528. 1529. 1530. 1531. 1532. 1533. 1534. 1535. 1536. 1537. 1538. 1539. 1540. 1541. 1542. 1543. 1544. 1545. 1546. 1547. 1548. 1549. 1550. 1551. 1552. 1553. 1554. 1555. 1556. 1557. 1558. 1559. 1560. 1561. 1562. 1563. 1564. 1565. 1566. 1567. 1568. 1569. 1570. 1571. 1572. 1573. 1574. 1575. 1576. 1577. 1578. 1579. 1580. 1581. 1582. 1583. 1584. 1585. 1586. 1587. 1588. 1589. 1590. 1591. 1592. 1593. 1594. 1595. 1596. 1597. 1598. 1599. 1600. 1601. 1602. 1603. 1604. 1605. 1606. 1607. 1608. 1609. 1610. 1611. 1612. 1613. 1614. 1615. 1616. 1617. 1618. 1619. 1620. 1621. 1622. 1623. 1624. 1625. 1626. 1627. 1628. 1629. 1630. 1631. 1632. 1633. 1634. 1635. 1636. 1637. 1638. 1639. 1640. 1641. 1642. 1643. 1644. 1645. 1646. 1647. 1648. 1649. 1650. 1651. 1652. 1653. 1654. 1655. 1656. 1657. 1658. 1659. 1660. 1661. 1662. 1663. 1664. 1665. 1666. 1667. 1668. 1669. 1670. 1671. 1672. 1673. 1674. 1675. 1676. 1677. 1678. 1679. 1680. 1681. 1682. 1683. 1684. 1685. 1686. 1687. 1688. 1689. 1690. 1691. 1692. 1693. 1694. 1695. 1696. 1697. 1698. 1699. 1700. 1701. 1702. 1703. 1704. 1705. 1706. 1707. 1708. 1709. 1710. 1711. 1712. 1713. 1714. 1715. 1716. 1717. 1718. 1719. 1720. 1721. 1722. 1723. 1724. 1725. 1726. 1727. 1728. 1729. 1730. 1731. 1732. 1733. 1734. 1735. 1736. 1737. 1738. 1739. 1740. 1741. 1742. 1743. 1744. 1745. 1746. 1747. 1748. 1749. 1750. 1751. 1752. 1753. 1754. 1755. 1756. 1757. 1758. 1759. 1760. 1761. 1762. 1763. 1764. 1765. 1766. 1767. 1768. 1769. 1770. 1771. 1772. 1773. 1774. 1775. 1776. 1777. 1778. 1779. 1780. 1781. 1782. 1783. 1784. 1785. 1786. 1787. 1788. 1789. 1790. 1791. 1792. 1793. 1794. 1795. 1796. 1797. 1798. 1799. 1800. 1801. 1802. 1803. 1804. 1805. 1806. 1807. 1808. 1809. 1810. 1811. 1812. 1813. 1814. 1815. 1816. 1817. 1818. 1819. 1820. 1821. 1822. 1823. 1824. 1825. 1826. 1827. 1828. 1829. 1830. 1831. 1832. 1833. 1834. 1835. 1836. 1837. 1838. 1839. 1840. 1841. 1842. 1843. 1844. 1845. 1846. 1847. 1848. 1849. 1850. 1851. 1852. 1853. 1854. 1855. 1856. 1857. 1858. 1859. 1860. 1861. 1862. 1863. 1864. 1865. 1866. 1867. 1868. 1869. 1870. 1871. 1872. 1873. 1874. 1875. 1876. 1877. 1878. 1879. 1880. 1881. 1882. 1883. 1884. 1885. 1886. 1887. 1888. 1889. 1890. 1891. 1892. 1893. 1894. 1895. 1896. 1897. 1898. 1899. 1900. 1901. 1902. 1903. 1904. 1905. 1906. 1907. 1908. 1909. 1910. 1911. 1912. 1913. 1914. 1915. 1916. 1917. 1918. 1919. 1920. 1921. 1922. 1923. 1924. 1925. 1926. 1927. 1928. 1929. 1930. 1931. 1932. 1933. 1934. 1935. 1936. 1937. 1938. 1939. 1940. 1941. 1942. 1943. 1944. 1945. 1946. 1947. 1948. 1949. 1950. 1951. 1952. 1953. 1954. 1955. 1956. 1957. 1958. 1959. 1960. 1961. 1962. 1963. 1964. 1965. 1966. 1967. 1968. 1969. 1970. 1971. 1972. 1973. 1974. 1975. 1976. 1977. 1978. 1979. 1980. 1981. 1982. 1983. 1984. 1985. 1986. 1987. 1988. 1989. 1990. 1991. 1992. 1993. 1994. 1995. 1996. 1997. 1998. 1999. 2000. 2001. 2002. 2003. 2004. 2005. 2006. 2007. 2008. 2009. 2010. 2011. 2012. 2013. 2014. 2015. 2016. 2017. 2018. 2019. 2020. 2021.</u>					



# Barr

Engineering Company

## FIELD LOG DATA SHEET

Station: MW-4P

Client: NSG

Project No. 11311419170103JSL311

Location: Waukegan, IL

Date: 3/27/92

Sample Time: \_\_\_\_\_

General		Stabilization Test					
		TIME/ VOLUME	TEMP CENT.	COND. umhos	COND. @ 25	pH	Eh
Barr Lock: Y N	<u>Y</u>	1. <u>2:22/335</u>	<u>12.3</u>	<u>6500</u>		<u>8.50</u>	
Casing Dia: (in.)	<u>2</u>	2. <u>2:27/360</u>	<u>12.2</u>	<u>7000</u>		<u>8.50</u>	
Total Depth (ft.)	<u>32</u>	3. <u>2:32/390</u>	<u>11.9</u>	<u>7000</u>		<u>8.48</u>	
Static Depth (ft.)	<u>-</u>	4. <u>2:37/425</u>	<u>12.1</u>	<u>7000</u>		<u>8.48</u>	
Water Depth:	<u>6.8 (TOL)</u>	5.					
Well Vol. (gal.)	<u>3.8</u>	6.					
Purge Method:	<u>PUMP &amp; SURGE</u>	7.					
Samp. Method:	<u>-</u>	Appearance: <u>GOLDEN BROWN - LITE FOAM</u>					
Start Time:	<u>12:30</u>	Odor: <u>YES</u>					
Stop Time:	<u>2:40</u>	Comments: <u>SEDIMENT cleaned up @</u> <u>Between 1955 pumping and ~200 gal</u> <u>this pumping.</u>  <u>VOLUMES were measured directly.</u>					
Duration: (min.)	<u>130</u>						
Rate, gpm:	<u>±3</u>						
Volume Purged:	<u>425</u>						
Samplers: <u>JMF / TWW</u>		Others Present: <u>WTD</u>					
gen _____ VOC _____ COD _____ TOC _____ semi-volatile _____ f. metal _____ t. metal _____ nitro _____ cyanide _____ oil & grease _____ 200 ml filter _____ 500 ml filter _____ others _____							

# Barr

Engineering Company

## FIELD LOG DATA SHEET

Station: MW-5D

Client: NSG - WCP

Project No. 11314910103J54311

Location: Waukegan, IL

Date: 3/27/92

Sample Time: \_\_\_\_\_

General		Stabilization Test					
		TIME/ VOLUME	TEMP CENT.	COND. umhos	COND. @ 25	pH	Eh
Barr Lock: <input checked="" type="checkbox"/> N	Y	1. 820/300	8.6	2600 <del>2580</del>		8.40	
Casing Dia: (in.)	2	2. 825/325	9.3	2600 <del>2580</del>		8.39	
Total Depth (ft.)	26.0	3. 830/350	8.9	2600 <del>2580</del>		8.42	
Static Depth (ft.)	—	4. 835/375	8.8	2600 <del>2580</del>		8.45	
Water Depth:	7.8(TOC)	5.					
Well Vol. (gal.)	3.2	6.					
Purge Method:	PUMP & SURGE	7.					
Samp. Method:	—	Appearance: golden					
Start Time:	7:10 AM	Odor: yes					
Stop Time:	8:40	Comments: 70 min / 300 GAL = ~ 5 GPM  clear - slightly golden after several well volumes.					
Duration: (min.)	90						
Rate, gpm:	5±						
Volume Purged:	415 GAL						
Samplers: JMF / TWL		Others Present: WTD					
gen _____		VOC _____	COD _____	TOC _____	semi-volatile _____	f. metal _____	t. metal _____
nitro _____		cyanide _____	oil & grease _____	200 ml filter _____	500 ml filter _____		
others _____							

# Barr

Engineering Company

## FIELD LOG DATA SHEET

Station: MW-6D

Client: NSG/WCP

Project No. 131-491-1903JISL4311

Location: Waukegan, IL Date: 3/27/92 Sample Time: \_\_\_\_\_

General		Stabilization Test					
		TIME/ VOLUME	TEMP CENT.	COND. umhos	COND. @ 25	pH	Eh
Barr Lock: Y N	<u>V</u>	1. <sup>10:08</sup> / <u>215</u>	<u>10.8</u>	<u>8500</u>		<u>8.33</u>	
Casing Dia: (in.)	<u>2</u>	2. <sup>10:13</sup> / <u>215</u>	<u>10.8</u>	<u>8500</u>		<u>8.30</u>	
Total Depth (ft.)	<u>26.5</u>	3. <sup>10:18</sup> / <u>250</u>	<u>10.7</u>	<u>8500</u>		<u>8.28</u>	
Static Depth (ft.)	<u>—</u>	4.					
Water Depth:	<u>8.0 (rad)</u>	5.					
Well Vol. (gal.)	<u>3.2</u>	6.					
Purge Method:	<u>Pump + surge</u>	7.					
Samp. Method:	<u>—</u>	Appearance: <u>golden brown, slightly cloudy</u>					
Start Time:	<u>9am</u>	Odor: <u>yes</u>					
Stop Time:	<u>10:20</u>	Comments:					
Duration: (min.)	<u>80</u>						
Rate, gpm:	<u>3</u>						
Volume Purged:	<u>250</u>						
Samplers: <u>TWW/JMF</u>		Others Present: <u>WTD</u>					
gen _____ VOC _____ COD _____ TOC _____ semi-volatile _____ f. metal _____ t. metal _____							
nitro _____ cyanide _____ oil & grease _____ 200 ml filter _____ 500 ml filter _____							
others _____							

# Barr

Engineering Company

## FIELD LOG DATA SHEET

Station: P-101

Client: NSG WLP

Project No. 131-1491-1013JSK1311

Location: Waukegan, IL Date: 5/24/92 Sample Time: \_\_\_\_\_

General		Stabilization Test					
		TIME/ VOLUME	TEMP CENT.	COND. umhos	COND. @ 25	pH	Eh
Barr Lock: Y N	Y	1. 5:32 / 20 GAL	7.2	1050		8.02	
Casing Dia: (in.)	1 1/4	2. 5:42 / 30 GAL	6.7	1050		7.79	
Total Depth (ft.)		3. 5:52 / 40 GAL	6.6	1050		7.76	
Static Depth (ft.)		4. 6:02 / 50 GAL	6.6	1050		7.76	
Water Depth:		5.					
Well Vol. (gal.)		6.					
Purge Method:		7.					
Samp. Method:		Appearance:					
Start Time:	5:12	Odor:					
Stop Time:	6:12	Comments: 5 GAL/4 MIN — 5 GAL/5 MIN cloudy — 5 GAL then clear					
Duration: (min.)	60						
Rate, gpm:	~16 gpm						
Volume Purged:	60						
Samplers: JMF		Others Present: W T					
gen _____ VOC _____ COD _____ TOC _____ semi-volatile _____ f. metal _____ t. metal _____							
nitro _____ cyanide _____ oil & grease _____ 200 ml filter _____ 500 ml filter _____							
others _____							

# Barr

Engineering Company

## FIELD LOG DATA SHEET

Station: P-102

Client: NSG-WCP

Project No. 13149-904JSEF1

Location: Dauligan, IL.

Date: 3/24/92

Sample Time: \_\_\_\_\_

General		Stabilization Test					
		TIME/ VOLUME	TEMP CENT.	COND. umhos	COND. @ 25	pH	Eh
Barr Lock: Y N	Y	1. 3:15 / 25 GAL	10.6	680		7.30	
Casing Dia: (in.)	1 1/4	2. 3:25 / 35 GAL	10.7	680		7.39	
Total Depth (ft.)		3. 3:35 / 45 GAL	10.4	680		7.46	
Static Depth (ft.)	15.0'	4. 3:45 / 55 GAL	10.5	680		7.50	
Water Depth:	6.3	5. 3:55 / 65 GAL	10.2	680 710			7.49
Well Vol. (gal.)		6.					
Purge Method:		7.					
Samp. Method:		Appearance: <u>cloudy - 10 GAL then clear</u>					
Start Time:	2:50	Odor: <u>NONE - ABOVE BACKGROUND</u>					
Stop Time:	4:00	Comments:					
Duration: (min.)	70						
Rate, gpm:	~1 GPM						
Volume Purged:	70						
Samplers: <u>JMF</u>		Others Present: <u>WTD</u>					
gen _____ VOC _____ COD _____ TOC _____ semi-volatile _____ f. metal _____ t. metal _____							
nitro _____ cyanide _____ oil & grease _____ 200 ml filter _____ 500 ml filter _____							
others _____							

# Barr

Engineering Company

## FIELD LOG DATA SHEET

Station: P-103

Client NSG-WCP

Project No. 113149-003JSL311

Location: Waukegan, IL

Date: 3/24/92

Sample Time: \_\_\_\_\_

General		Stabilization Test					
		TIME/ VOLUME	TEMP CENT.	COND. umhos	COND. @ 25	pH	Eh
Barr Lock: <u>(Y) N</u>	<u>Y</u>	1. <u>11:11 / 306 GAL</u>	<u>10.6</u>	<u>1020</u>		<u>7.66</u>	
Casing Dia: (in.)	<u>1 1/4</u>	2. <u>11:25 / 406 GAL</u>	<u>10.7</u>	<u>990</u>		<u>7.67</u>	
Total Depth (ft.)		3. <u>11:40 / 556 GAL</u>	<u>9.3</u>	<u>980</u>		<u>7.84</u>	
Static Depth (ft.)	<u>15.4'</u>	4. <u>11:52 / 676 GAL</u>	<u>8.8</u>	<u>900</u> ✓		<u>7.80</u> ✓	
Water Depth:	<u>7.6</u>	5. <u>12:02 / 77 GAL</u>	<u>8.8</u> ✓	<u>900</u> ✓		<u>7.89</u> ✓	
Well Vol. (gal.)		6. <u>12:12 / 87 GAL</u>	<u>8.9</u> ✓	<u>900</u> ✓		<u>7.80</u> ✓	
Purge Method:	<u>AIR LIFT</u>	7.					
Samp. Method:		Appearance: <u>cloudy 0-10 GAL - Then clear.</u>					
Start Time:	<u>10:35</u>	Odor: <u>NONE</u>					
Stop Time:	<u>12:25</u>	Comments: <u>CI @ 15.4' @ START</u> <u>H2O 7.6' " "</u> } <u>Below TOR</u> <u>START AIR LIFT 10:35 AM</u> <u>@ 1 GPM (56 GAL / 6 min)</u> (1) slightly cloudy (2) clear (3) clear (4) clear					
Duration: (min.)	<u>110</u>						
Rate, gpm:	<u>1 GPM</u>						
Volume Purged:	<u>110 ±</u>						
Samplers: <u>JMF</u>		Others Present: <u>WTD</u>					
gen _____		VOC _____					
COD _____		TOC _____					
semi-volatile _____		f. metal _____					
t. metal _____		nitro _____					
cyanide _____		oil & grease _____					
200 ml filter _____		500 ml filter _____					
others _____							

# Barr

Engineering Company

## FIELD LOG DATA SHEET

Station: P-104

Client: NSG - WCP

Project No. 1131-4A-10103 JB K 31

Location: Wan Keng, EC.

Date: 2/24/92 Sample Time: \_\_\_\_\_

General		Stabilization Test					
		TIME/ VOLUME	TEMP CENT.	COND. umhos	COND. @ 25	pH	Eh
Barr Lock: <u>Ø N</u>	<u>Y</u>	1. <u>1:47/42 GAL</u>	<u>11.1</u>	<u>720</u>		<u>7.51</u>	
Casing Dia: (in.)	<u>1 1/4</u>	2. <u>1:57/52 GAL</u>	<u>9.3</u>	<u>700</u>		<u>7.26</u>	
Total Depth (ft.)		3. <u>2:07/62 GAL</u>	<u>9.8</u>	<u>700</u>		<u>7.03</u>	
Static Depth (ft.)	<u>15.4</u>	4. <u>2:17/72 GAL</u>	<u>9.4</u>	<u>700</u>		<u>7.06</u>	
Water Depth:	<u>6.6</u>	5. <u>2:27/82 GAL</u>	<u>9.4</u>	<u>700</u>		<u>7.07</u>	
Well Vol. (gal.)		6.					
Purge Method:	<u>AIR LIFT</u>	7.					
Samp. Method:		Appearance: <u>cloudy 10 GAL - then clear</u>					
Start Time:	<u>1:05</u>	Odor: <u>NONE - ABOVE BASIC GROUND.</u>					
Stop Time:	<u>2:30</u>	Comments: <u>SLIGHT oily film and</u> <u>SLIGHT yellow color to</u> <u>H2O - BUT clear OF sediment.</u>					
Duration: (min.)	<u>85</u>						
Rate, gpm:	<u>1 GPM</u>						
Volume Purged:	<u>85</u>						
Samplers: <u>JMF</u>		Others Present: <u>WTD</u>					
gen _____		VOC _____					
COD _____		TOC _____					
semi-volatile _____		f. metal _____					
t. metal _____							
nitro _____		cyanide _____					
oil & grease _____		200 ml filter _____					
500 ml filter _____							
others _____							

***Water Level Data Sheets***





## WATER LEVEL DATA SHEET

PROJECT NAME WAKKAN/WCP RT/ES

SAMPLERS, IEG

DATE 4/9/92

PAGE \_\_\_\_\_ OF \_\_\_\_\_

[illegible]

## WATER LEVEL DATA SHEET

PROJECT NAME WAKGON/WCP RT/FS

SAMPLERS KAF/TWW

DATE 4-15-92

PAGE 1 OF 1

[illegible]

## WATER LEVEL DATA SHEET

PROJECT NAME WAKGGM/WCP RT/FS

SAMPLERS MES/LCK

DATE 4.21.92

PAGE 1 OF 1

[illegible]

## - WATER LEVEL DATA SHEET

PROJECT NAME WAKEGAN / WCP RI / FS

SAMPLERS LCR

DATE 5-7-92

PAGE 1 OF 1

[illegible]

\* Dry lid

~~\*\*~~ ~~\*\*~~ wave action  $\pm \frac{1}{2}$  inch.

## WATER LEVEL DATA SHEET

PROJECT NAME

WAKEGAN / WCP / R<sup>2</sup> / FB

SAMPLERS LCK

DATE 5-27-92

PAGE 1 OF 1

[illegible]

## ***Appendix G***

### ***Slug Test Data and Evaluation***

TABLE G-1

SLUG TEST PARAMETERS  
BOUWER AND RICE METHOD

Well	Depth to Static Water Level (Below Top of Casing) (ft) 4/15/92	Average Initial Drawdown ( $y_0$ ) (ft)	Static Height of Water in Well ( $L_w$ ) (ft)	Saturated Screen Length ( $L_s$ ) (ft)	Radius of Casing ( $r_c$ ) (ft)	Radius of Filter Pack ( $r_w$ ) (ft)	Saturated Thickness of Aquifer (H) (ft)
MW-1S	6.03	2.1	13.72	5.0	0.083	0.25	24.0
MW-1D	5.91	1.8	23.84	5.0	0.083	0.25	24.0
MW-3S	5.49	0.18	9.55	9.55	0.083	0.427	26.1
MW-3D	5.53	1.6	25.31	5.0	0.083	0.427	25.7
MW-4S	6.75	0.19	8.70	8.70	0.083	0.427	27.7
MW-4D	6.72	1.5	27.62	4.5	0.083	0.427	27.7
MW-5S	7.14	0.17	9.14	9.14	0.083	0.427	21.1
MW-5D	7.74	1.6	20.88	4.7	0.083	0.427	20.9
MW-6S	7.61	0.19	9.14	9.14	0.083	0.427	21.6
MW-6D	7.74	2.0	21.79	5.0	0.083	0.427	21.8



BARR ENGINEERING COMPANY

MEMORANDUM

TO: WCP RI/FS File (13/49-003JSL33)  
FROM: KAF  
DATE: May 22, 1992  
RE: Slug Test Evaluation  
L<sub>e</sub> and r<sub>c</sub> Parameters for Bouwer and Rice Method

Parameter L<sub>e</sub>

Because the filter pack and aquifer were both poorly graded sand, it was assumed that the filter pack and aquifer had similar hydraulic conductivities. For this reason, the length of the intake zone (L<sub>e</sub>) was assumed to be the length of the screen and not the length of the sand pack.

Parameter r<sub>c</sub>

According to the Bouwer and Rice method, an equivalent value of r<sub>c</sub> must be substituted for r<sub>c</sub> when the water is rising or falling within the gravel pack as well as the well casing. The formula for the equivalent r<sub>c</sub> is:

$$\text{equiv } r_c = \sqrt{(1-n)r_c^2 + nr_v^2}$$

n = porosity of gravel pack

r<sub>v</sub> = radius of gravel pack

r<sub>c</sub> = radius of casing

This formula assumes that the entire porosity of a gravel pack drains into the well casing during the slug test. An equivalent radius was calculated for wells screened across the water table (MW-3S, -45, -5S, and -65). The hydraulic conductivities estimated using this radius were several times higher than the hydraulic conductivities estimated for the deeper wells (sand pack fully saturated), although there was no geologic explanation for the difference. When

the actual  $r_c$  value instead of the equivalent  $r_c$  value was used, the hydraulic conductivity estimates for the water table wells were similar to those for the deeper wells. The conclusion was that the equivalent  $r_c$  was too large and that the entire porosity of the gravel pack cannot have drained into the well casing. The following calculation shows that only 3 percent of the total volume of the exposed filter pack drained into the well casing:

Volume of water drained from filter pack into screen:

$$\Pi r_c^2 (0.8 \text{ ft}) 1$$

where 1 = porosity of the well casing, and

where  $y_0 = 1$  foot (initial drawdown)

$y_t = 0.2$  foot (beginning of aquifer response on graph)

$y_0 - y_t = 0.8$  foot (recovery due to draining of filter pack)

Volume of filter pack that can drain into well:

$$\Pi (r_w^2 - r_c^2) y_0$$


Drained porosity of filter pack (x):

$$x = \frac{\Pi r_c^2 (0.8)}{\Pi (r_w^2 - r_c^2) y_0} = 0.03$$

where:  $r_c = 0.083$  foot,  $r_w = 0.427$  foot, and  $y_0 = 1.0$  foot

Because only 3 percent of the total filter pack volume drained into the well during the slug test, the filter pack can be assumed to have been essentially saturated throughout the test and the actual casing radius ( $r_c$ ) can be used instead of the equivalent radius.


# WCP RI/FS MW-1S SLUG OUT TEST 1



AQTESOLV

 GERAGHTY  
& MILLER, INC.  
 Modeling Group

WCP RI/FS MW-1S SLUG OUT TEST 2




AQTESOLV

 GERAGHTY  
& MILLER, INC.  
 Modeling Group

Drawdown (ft)


### WCP RI/FS MW-1D SLUG IN TEST 1



AQTESOLV

 GERAGHTY  
& MILLER, INC.  
Modeling Group


# WCP RI/FS MW-1D SLUG IN TEST 2



AQTESOLV

 GERAGHTY  
& MILLER, INC.  
Modeling Group

# WCP RI/FS MW-1D SLUG OUT TEST 1




AQTESOLV

 GERAGHTY  
& MILLER, INC.  
Modeling Group

# WCP RI/FS MW-1D SLUG OUT TEST 2

Drawdown (ft)




AQTESOLV

 GERAGHTY  
& MILLER, INC.  
Modeling Group




# WCP RI/FS MW-3S SLUG OUT TEST 1




AQTESOLV


 GERAGHTY  
& MILLER, INC.  
 Modeling Group

# WCP RI/FS MW-3S SLUG OUT TEST 2




AQTESOLV

 GERAGHTY  
& MILLER, INC.

 Modeling Group

# WCP RI/FS MW-3D SLUG IN TEST 2




AQTESOLV

 GERAGHTY  
& MILLER, INC.  
 Modeling Group

# WCP RI/FS MW-3D SLUG OUT TEST 1


Drawdown (ft)



AQTESOLV

 GERAGHTY  
& MILLER, INC.  
 Modeling Group

# WCP RI/FS MW-3D SLUG OUT TEST 2




AQTESOLV

 GERAGHTY  
& MILLER, INC.  
 Modeling Group

Drawdown (ft)

### WCP RI/FS MW-4S SLUG OUT TEST 1




AQTESOLV

 GERAGHTY  
& MILLER, INC.  
Modeling Group

# WCP RI/FS MW-4S SLUG OUT TEST 2

Drawdown (ft)




AQTESOLV

 GERAGHTY  
& MILLER, INC.  
 Modeling Group

# WCP RI/FS MW-4D SLUG IN TEST 1

Drawdown (ft)




AQTESOLV

 GERAGHTY  
& MILLER, INC.  
 Modeling Group




# WCP RI/FS MW-4D SLUG IN TEST 2



AQTESOLV

GERAGHTY  
& MILLER, INC.  
Modeling Group


Drawdown (ft)



AQTESOLV

 GERAGHTY  
& MILLER, INC.  
 Modeling Group

# WCP RI/FS MW-4D SLUG OUT TEST 2




AQTESOLV

 GERAGHTY  
& MILLER, INC.  
Modeling Group

Drawdown (ft)


### WCP RI/FS MW-5S SLUG OUT TEST 1



AQTESOLV

 GERAGHTY  
& MILLER, INC.  
Modeling Group

# WCP RI/FS MW-5S SLUG OUT TEST 2




AQTESOLV

 GERAGHTY  
& MILLER, INC.  
Modeling Group

# WCP RI/FS MW-5D SLUG IN TEST 1


Drawdown (ft)



AQTESOLV

 GERAGHTY  
& MILLER, INC.  
Modeling Group


# WCP RI/FS MW-5D SLUG IN TEST 2



AQTESOLV

 GERAGHTY  
& MILLER, INC.  
Modeling Group

# WCP RI/FS MW-5D SLUG OUT TEST 1




AQTESOLV

GERAGHTY  
& MILLER, INC.  
Modeling Group



# WCP RI/FS MW-6D SLUG IN TEST 1




AQTESOLV

 GERAGHTY  
& MILLER, INC.  
Modeling Group

Drawdown (ft)


# WCP RI/FS MW-6S SLUG OUT TEST 1



AQTESOLV

 GERAGHTY  
& MILLER, INC.  
 Modeling Group


# WCP RI/FS MW-6S SLUG OUT TEST 2



AQTESOLV

 GERAGHTY  
& MILLER, INC.  
Modeling Group


# WCP RI/FS MW-6D SLUG IN TEST 2



AQTESOLV

 GERAGHTY  
& MILLER, INC.  
Modeling Group


# WCP RI/FS MW-6D SLUG OUT TEST 1



AQTESOLV

 GERAGHTY  
& MILLER, INC.  
Modeling Group

# WCP RI/FS MW-6D SLUG OUT TEST 2



AQTESOLV



GERAGHTY  
& MILLER, INC.

Modeling Group

## ***Appendix H***

### ***Phase I Groundwater Sampling Field Log Data Sheets***

## WATER LEVEL DATA SHEET

PROJECT NAME WAKEGAN / WCP RI/FS

SAMPLERS IEG

DATE 4/9/92

PAGE \_\_\_\_\_ OF \_\_\_\_\_

[illegible]



## WATER LEVEL DATA SHEET

PROJECT NAME WAKEGAN / WCP RI/FS

SAMPLERS E. Gabrielson -

DATE 4/7/92

PAGE \_\_\_\_\_ OF \_\_\_\_\_

[illegible]

## FIELD LOG COVER SHEET

Page 1 of \_\_\_\_

## WATER SAMPLING

Client: WAKEGAN / WCP RIFES Project Number 13 / 49 - 003 JSL 31Samplers: JEG KSJSampling Period: 4 / 7 / 92  
4 / 8 / 92  
4 / 9 / 92  
1 / 1

Weather:

Date	Temperature	Wind Speed	Wind Direction	Cloud Cover
4 / 7 / 92	45 oF	5-10 mph	<u>W</u>	40 %
4 / 8 / 92	50 oF	10-15 mph	<u>SE</u>	10 %
4 / 9 / 92	oF	mph		
1 / 1	oF	mph		

Containers received from: Pace Braun Enseco CH2M Hill EDISamples shipped for analysis to: Pace Braun Enseco CH2M Hill EDI

Samples dropped off at: Pace Braun

Water blank received from: Pace Braun Enseco CH2M Hill EDIType of blank: Trip / Field Field blank is: air / waterMask # 1 collected at station # MW4D-1 Mask # 2 collected at station # MW6S-1  
MS/MSD - MW5S-1Name and affiliation of others present: pete Lynch PRC

Comments:

Water Levels were taken 4/7/92 and 4/9/92.

PROJECT NAME WAKEGAN WCP RI/FS  
PROJECT NUMBER 1131149-1003 75W311  
SAMPLER E. Gabrielson KSJ

PROJECT NUMBER 113/49-00375431

SAMPLER E. Gabrielson KSJ

[illegible]

# Barr

Engineering Company

## FIELD LOG DATA SHEET

Station: MW35-1

Client: WCP RIFS

Project No. 131-149-10103JIS14311

Location: \_\_\_\_\_ Date: 4/7/92 Sample Time: 1520

General		Stabilization Test					
		TIME/ VOLUME	TEMP CENT.	COND. umhos	COND. @ 25	pH	Eh
Barr Lock: <u>(Y)</u> N		1. 150L	12.0	450		7.3	
Casing Dia: (in.)	2"	2. 1503 <sup>30</sup>	11.0	445		7.4	
Total Depth (ft.)	15	3. 1504 <sup>30</sup>	11.0	440		7.4	
Static Depth (ft.)	5.54	4. 1505	11.0	440	585	7.4	
Water Depth:	10	5.					
Well Vol. (gal.)	1.5	6.					
Purge Method:	(cont)	7.					
Samp. Method:	Butter	Appearance: <u>Brown</u>					
Start Time:	1458	Odor: <u>yo</u>					
Stop Time:	1505	Comments: <u>FB-1 poured</u>					
Duration: (min.)	7						
Rate, gpm:	1.5						
Volume Purged:	10.5						
Samplers: <u>JEG K SJ</u>		Others Present: _____					
gen <u>3</u> VOC _____ COD _____ TOC _____		semi-volatile <u>2</u> f. metal <u>1</u> t. metal _____					
nitro _____ cyanide <u>1</u> _____		oil & grease _____ 200 ml filter _____ 500 ml filter _____					
others _____							

# Barr

Engineering Company

## FIELD LOG DATA SHEET

Station: MW30-1

Client: WCP RI/FS

Project No. 1131-1491-1010301514311

Location: \_\_\_\_\_

Date: 4/7/92

Sample Time: 1536

General		Stabilization Test					
		TIME/ VOLUME	TEMP CENT.	COND. umhos	COND. @ 25	pH	Eh
Barr Lock <input checked="" type="checkbox"/> N		1. 1510	13.0	8000		9.4	
Casing Dia: (in.)	2	2. 1512	13.0	8000		9.4	
Total Depth (ft.)	31	3. 1513	13.0	8000	10200	9.4	
Static Depth (ft.)	5.59	4.					
Water Depth:	25.5	5.					
Well Vol. (gal.)	4	6.					
Purge Method:	Cent	7.					
Samp. Method:	Balter	Appearance: light brown, milky white residue					
Start Time:	1507	Odor: yes					
Stop Time:	1514	Comments:					
Duration: (min.)	7						
Rate, gpm:	3						
Volume Purged:	21						
Samplers:		Others Present:					
gen _____		VOC <u>3</u> COD _____ TOC _____ semi-volatile <u>2</u> f. metal _____ t. metal _____					
nitro _____		cyanide <u>1</u> oil & grease _____ 200 ml filter _____ 500 ml filter _____					
others _____							

# Barr

Engineering Company

## FIELD LOG DATA SHEET

Station: MW45-1

Client: WCP RI/FS

Project No. 1131419-0103151311

Location: \_\_\_\_\_ Date: 4/7/92 Sample Time: \_\_\_\_\_

General		Stabilization Test					
		TIME/ VOLUME	TEMP CENT.	COND. umhos	COND. @ 25	pH	Eh
Barr Lock: <input checked="" type="radio"/> N		1. 4.5/GAL	10	600		8.0	
Casing Dia: (in.)	2"	2. 6.0/GAL	10	600		8.0	
Total Depth (ft.)	15.5	3. 7.5/GAL	10	600	800	8.0	
Static Depth (ft.)	6.62	4.					
Water Depth:	9	5.					
Well Vol. (gal.)	1.5	6.					
Purge Method:	cont	7.					
Samp. Method:	Bailer	Appearance: clear					
Start Time:	1639	Odor: NO					
Stop Time:	1643	Comments:					
Duration: (min.)	4						
Rate, gpm:	2						
Volume Purged:	8						
Samplers: JEG KSS		Others Present:					
gen _____		VOC <u>3</u> COD _____ TOC _____ semi-volatile <u>2</u> f. metal <u>1</u> t. metal _____					
nitro _____		cyanide <u>1</u> oil & grease _____ 200 ml filter _____ 500 ml filter _____					
others _____							

# Barr

Engineering Company

## FIELD LOG DATA SHEET

Station: MW40-1

Client: WCP RI/FS

Project No. 1131-14191-1003JTS14311

Location: \_\_\_\_\_

Date: 4/7/92

Sample Time: 1720

General		Stabilization Test					
		TIME/ VOLUME	TEMP CENT.	COND. umhos	COND. @ 25	pH	Eh
Barr Lock: <u>ON</u>		1. 1651	12.0	8500		9.16	
Casing Dia: (in.)	<u>2"</u>	2. 1653	13.	9500		9.19	
Total Depth (ft.)	<u>34.5</u>	3. 1655	13	9500	12100	9.19	
Static Depth (ft.)	<u>6.54</u>	4.					
Water Depth:	<u>28</u>	5.					
Well Vol. (gal.)	<u>4.5</u>	6.					
Purge Method:	<u>cent</u>	7.					
Samp. Method:	<u>Barter</u>	Appearance: <u>orange/white</u>					
Start Time:	<u>1645</u>	Odor: <u>YK</u>					
Stop Time:	<u>1655</u>	Comments: <u>M-1</u>					
Duration: (min.)	<u>10</u>						
Rate, gpm:	<u>2</u>						
Volume Purged:	<u>22.5</u>						
Samplers: <u>JEG K5J</u>		Others Present: _____					
gen _____		VOC <u>6</u> COD _____ TOC _____ semi-volatile <u>4</u> f. metal <u>2</u> t. metal _____					
nitro _____		cyanide <u>2</u> oil & grease _____ 200 ml filter _____ 500 ml filter _____					
others _____							

# Barr

Engineering Company

## FIELD LOG DATA SHEET

Station: MW55-1

Client: WCP RI/FS

Project No. 1131-419-10103JISL311

Location: \_\_\_\_\_

Date: 4/8/92

Sample Time: 1220 → 1259

General		Stabilization Test					
		TIME/ VOLUME	TEMP CENT.	COND. umhos	COND. @ 25	pH	Eh
Barr Lock: (Y)N	<u>2</u>	1. 4.5	9.0	350		7.5	
Casing Dia: (in.)	2"	2. 6.0	9.0	340		7.4	
Total Depth (ft.)	16	3. 7.5	9.0	340		7.4	
Static Depth (ft.)	7.32	4. 9.0	9.0	340	475	7.4	
Water Depth:	8.5	5.					
Well Vol. (gal.)	1.5	6.					
Purge Method:	Centr.	7.					
Samp. Method:	Dailer	Appearance:					
Start Time:	1207	Odor:					
Stop Time:	1214	Comments: MS/MSD  10% clouds, 50°F, SE @ 10-15 mph YSI Conductivity - redline OK ORION pH - 7.00 : 10.00					
Duration: (min.)	7						
Rate, gpm:	1						
Volume Purged:	7.5						
Samplers: K35 JEC		Others Present: pek Lynch					
gen _____		VOC <u>9</u> COD _____ TOC _____ semi-volatile <u>6</u> f. metal <u>3</u> t. metal _____					
nitro _____		cyanide <u>3</u> oil & grease _____ 200 ml filter _____ 500 ml filter _____					
others _____							



# Barr

Engineering Company

## FIELD LOG DATA SHEET

Station: MW50-1

Client: WCP RI/FS

Project No. 1131-1417-10103JIS431

Location: \_\_\_\_\_

Date: 4/8/92

Sample Time: 1320

General		Stabilization Test					
		TIME/ VOLUME	TEMP CENT.	COND. umhos	COND. @ 25	pH	Eh
Barr Lock: <u>N</u>		1. 10.5	11.0	2900		8.2	
Casing Dia: (in.)	2"	2. 14.0	11.0	3300		8.2	
Total Depth (ft.)	28.5	3. 17.5	11.0	3300		8.2	
Static Depth (ft.)	7.93	4. 21.	11.0	3000	4400	8.2	
Water Depth:	20.5	5.					
Well Vol. (gal.)	3.5	6.					
Purge Method:	Cent	7.					
Samp. Method:	Bailer	Appearance: <u>Orange</u>					
Start Time:	1303	Odor: <u>yes</u>					
Stop Time:	1312	Comments:					
Duration: (min.)	9						
Rate, gpm:	2						
Volume Purged:	17.5						
Samplers: <u>KST JEG</u>		Others Present: <u>PCK LYNCH</u>					
gen _____		VOC <u>3</u> COD _____ TOC _____ semi-volatile <u>2</u> f. metal <u>1</u> t. metal _____					
nitro _____		cyanide <u>1</u> oil & grease _____ 200 ml filter _____ 500 ml filter _____					
others _____							

## ***Appendix I***

### ***Hydrogeologic Model Development***

CHAIN OF CUSTODY  
BARR ENGINEERING CO.  
7803 GLENROY ROAD  
MINNEAPOLIS, MN 55439

PROJECT NUMBER 13149-1003 JSL31

NO:

SAMPLE IDENTIFICATION	COLLECTION		GRAB	COMP.	BLANK	VOLATILE ORGANIC	SEMIVOLATILE ORGANIC	FILTERED METALS	UNFILTERED METALS	GENERAL	CYANIDE	NUTRIENTS	OIL AND GREASE	TOC	SULFIDE	DIOXIN	TOTAL NO. OF CONTAINERS	PROJECT MANAGER:	PROJECT CONTACT:	LABORATORY:	REMARKS/ANALYSIS REQUIRED:				
	DATE	TIME																							
MW55-1	4/8/92		X			3	2											5	JSL	SOE	CH2M HILL	Level 3 GAO			
MW55-1/M5			X			3	2											5	See						
MW55-1/M5D			X			3	2											5	See						
MW65-1			X			3												3	See						
MW6D-1			X			3												3	See						
MW5D-1			X			3												3	See						
M-2			X			3												3	See						
E-3-2			X			3												3	See						
SAMPLED BY: Eric Garmann KSS																			RELINQUISHED BY: [Signature]	DATE: 4/8/92	TIME:	RECEIVED BY LAB:	DATE:	TIME:	
RECEIVED BY:																			RELINQUISHED BY:	DATE:	TIME:	RECEIVED BY LAB:	DATE:	TIME:	
RECEIVED BY:																			RELINQUISHED BY:	DATE:	TIME:	RECEIVED BY LAB:	DATE:	TIME:	
REMARKS:																			SAMPLES SHIPPED VIA [ ] AIR FREIGHT [ ] EXP. [ ] SAMPLER [ ] OTHER [ ]		AIR BILL NUMBER:		DATE:		TIME:

PROJECT NUMBER № 01543  
13/49-1003 TSL31  
NO:

DISTRIBUTION: WHITE-ORIGINAL ACCOMPANIES SHIPMENT TO LAB, RETURNS TO BARR WITH RESULTS; YELLOW-LAB COPY; PINK-LAB COORDINATOR; GOLD-FIELD COPY

CHAIN OF CUSTODY  
BARR ENGINEERING CO.  
7803 GLENROY ROAD  
MINNEAPOLIS, MN 55439

PROJECT NUMBER 01544

131/49-1003511311

NO:

SAMPLE  
IDENTIFICATION

COLLECTION

DATE TIME

GRAB  
COMP.  
BLANK

VOLATILE ORGANIC

SEMIVOLATILE ORGANIC

FILTERED METALS

UNFILTERED METALS

GENERAL

CYANIDE

NUTRIENTS

OIL AND GREASE

TOC

SULFIDE

DIOXIN

TOTAL NO. OF CONTAINERS

CONTAINER TYPE AND NUMBER

PROJECT MANAGER:

PROJECT CONTACT:

LABORATORY:

REMARKS/ANALYSIS REQUIRED:

See 1/15/14

CH2M41:11

505

USC

SAMPLED BY:

Eric Gabrielson 1055

RECEIVED BY:

RECEIVED BY:

REMARKS:

RELINQUISHED BY:

1/15/14

RELINQUISHED BY:

RELINQUISHED BY:

DATE TIME

DATE TIME

RECEIVED BY LAB:

RECEIVED BY LAB:

RECEIVED BY LAB:

RECEIVED BY LAB:

DATE TIME

DATE TIME

DATE TIME

AIR BILL NUMBER:

SAMPLES SHIPPED VIA  
☐ AIR FREIGHTED. ☐ EXP. ☐ SAMPLER  
☐ OTHER

DISTRIBUTION: WHITE-ORIGINAL (COMPANIES EQUIPMENT) LOW-LAB RETURNS TO LAB WITH RESYTS; LOW-LAB COPY; PINK-LAB COORDINATOR; GOLD-FIELD COPY

CLAIN OF CUSTODY  
BARR ENGINEERING CO.  
7803 GLENROY ROAD  
MINNEAPOLIS, MN 55439

PROJECT NUMBER 89-01312

13149-101317

NO:

SAMPLE IDENTIFICATION

COLLECTION DATE TIME

GRAB  
COMP.  
BLANK

VOLATILE ORGANIC  
SEMIVOLATILE ORGANIC  
FILTERED METALS  
UNFILTERED METALS  
GENERAL  
CYANIDE  
NUTRIENTS  
OIL AND GREASE  
TOC  
SULFIDE  
DIOXIN

TOTAL NO. OF CONTAINERS

CONTAINER TYPE AND NUMBER

PROJECT MANAGER:

PROJECT CONTACT:

LABORATORY:

REMARKS/

ANALYSIS REQUIRED:

Level 3 QA/QC

See List

M-1 4/7/92 X X Z  
MM4D-1 X X Z  
MM4S-1 X X Z

SAMPLED BY:

RELINQUISHED BY:

DATE TIME

RECEIVED BY LAB:

DATE TIME

RECEIVED BY:

RELINQUISHED BY:

DATE TIME

RECEIVED BY LAB:

DATE TIME

RECEIVED BY:

RELINQUISHED BY:

DATE TIME

RECEIVED BY LAB:

DATE TIME

REMARKS:

SAMPLES SHIPPED VIA  
☐ AIR FREIGHT ☐ FED. EXP. ☐ SAMPLER  
☐ OTHER

AIR BILL NUMBER:

PROJECT NUMBER **HP-01541**  
13/49-003 JSIL31  
NO:

PROJECT NUMBER **HP-01541**  
13/49-003 JSIL31  
NO:

SAMPLE IDENTIFICATION	COLLECTION		GRAB	COMP.	BY ANY
	DATE	TIME			

[illegible][illegible]

PROJECT MANAGER:	JSL
PROJECT CONTACT:	SDI
LABORATORY:	CH <sub>2</sub> MHI, I
REMARKS/ ANALYSIS REQUIRED:	Level 3 QA/QC

SAMPLED BY: <i>ERIC CABRERA KST</i>	RELINQUISHED BY: <i>[Signature]</i>	DATE <i>4/7/92</i>	TIME	RECEIVED BY LAB:	DATE	TIME
RECEIVED BY:	RELINQUISHED BY:	DATE	TIME	RECEIVED BY LAB:	DATE	TIME
RECEIVED BY:	RELINQUISHED BY:	DATE	TIME	RECEIVED BY LAB:	DATE	TIME
REMARKS: <i>[Handwritten text]</i>	SAMPLES SHIPPED VIA <input type="checkbox"/> AIR FREIGHT <input type="checkbox"/> FED. EXP. <input checked="" type="checkbox"/> SAMPLER <input type="checkbox"/> OTHER _____			AIR BILL NUMBER:		

DISTRIBUTION: WHITE-ORIGINAL ACCOMPANIES SHIPMENT, LAB. RETURNS TO BARR WITH RESULTS; LOW-LAB COPY; PINK-LAB COORDINATOR; GOLD-FIELD COPY





**CHAIN OF CUSTODY  
BARR ENGINEERING CO.  
7803 GLENROY ROAD  
MINNEAPOLIS, MN 55439**

PROJECT NUMBER 1349-003 JSL31

**NO:**

SAMPLE IDENTIFICATION	COLLECTION		GRAB	COMP.	BLANK
	DATE	TIME			

MW3 S-1	4/7/92		X	
MW3 D-1			X	
FB-1				X
MW4 S-1			X	
MW4 D-1			X	
M-1			X	
TR-1				X

[illegible]

TOTAL NO. OF CONTAINERS	PROJECT MANAGER:
	ISL
	PROJECT CONTACT:
	SDI
	LABORATORY:
CH <sub>2</sub> M+H.I.I	
REMARKS/ ANALYSIS REQUIRED:	
Level 3 QA/QC	

SAMPLED BY: <i>Eric Caperton KSS</i>	RELINQUISHED BY: <i>4/7/92</i>	DATE <i>4/7/92</i>	TIME	RECEIVED BY LAB:	DATE	TIME
RECEIVED BY:	RELINQUISHED BY:	DATE	TIME	RECEIVED BY LAB:	DATE	TIME
RECEIVED BY:	RELINQUISHED BY:	DATE	TIME	RECEIVED BY LAB:	DATE	TIME
REMARKS:	SAMPLES SHIPPED VIA <input type="checkbox"/> AIR FREIGHT <input type="checkbox"/> FED. EXP. <input checked="" type="checkbox"/> SAMPLER <input type="checkbox"/> OTHER _____			AIR BILL NUMBER:		

DISTRIBUTION: WHITE-ORIGINAL ACCOMPANIES SHIPMENT TO LAB. RETURNS TO BARR WITH RESULTS: ( LOW-LAB COPY; PINK-LAB COORDINATOR; GOLD-FIELD COPY

1082

PROJECT:

## SAMPLING REQUEST FORM

13149-003 31

SAMPLE ORDER AND LOCATION	STABILIZE	PREVIOUS VOLUME	40ML VIAL	40ML VIAL W/HCL	125ML AMBER W/TEFLON	500ML AMBER W/TEFLON	1L AMBER W/TEFLON	2L AMBER W/TEFLON	250ML PLASTIC	500ML PLASTIC	1L PLASTIC	250ML PLASTIC W/HNO3	500ML PLASTIC W/HNO3	1L PLASTIC W/HNO3	250ML PLASTIC W/H2SO4	500ML PLASTIC W/H2SO4	1L PLASTIC W/H2SO4	1500ML GLASS W/H2SO4	1L PLASTIC W/NaOH + ASCORBIC ACID	METHANE FLOW	EH	APPEARANCE	TEMPERATURE	CONDUCTIVITY	PH	WATER LEVEL
1. P101	/																									X
2. P102	/																									X
3. P103	/																									X
4. P104	/																									X
5. Harbor	/																									X
6. MW3S	X		3				2					1							1			X	X	X	X	X
7. MW3D	X		3				2					1							1			X	X	X	X	X
8. MW4S	X		3				2					1							1			X	X	X	X	X
9. MW4D	X		3				2					1							1			X	X	X	X	X
10. MW5S	X		3				2					1							1			X	X	X	X	X
11. MW5D	X		3				2					1							1			X	X	X	X	X
12. MW6S	X		3				2					1							1			X	X	X	X	X
(1) LABORATORY	F		C				C					C	C						C			F	F	F	F	F

(1) LABORATORY CODES: A = ASPEN P = PACE E = ENSECO F = FIELD/BARR C = CH2M HILL B = BRAUN D = EDI

BARR CONTACT \_\_\_\_\_ SPLIT \_\_\_\_\_ SCHEDULED DATE April 6-10, 92 COMPLETION DATE \_\_\_\_\_

SPECIAL INSTRUCTIONS CLP procedures

PROJECT MGR. JSL/KAF SAMPLER \_\_\_\_\_ FORM COMPLETED BY: KAF DATE: 4-2-92

**BARR ENGINEERING CO.**  
7803 GLENROY ROAD  
MINNEAPOLIS, MN 55439

PROJECT NUMBER	AP 01548
13/49-003	ISL31
NO:	

[illegible]

SAMPLED BY: ERIC GABRIELSON K5J	RELINQUISHED BY: <i>[Signature]</i>	DATE 4/17/72	TIME	RECEIVED BY LAB:	DATE	TIME
RECEIVED BY:	RELINQUISHED BY:	DATE	TIME	RECEIVED BY LAB:	DATE	TIME
RECEIVED BY:	RELINQUISHED BY:	DATE	TIME	RECEIVED BY LAB:	DATE	TIME
REMARKS:	SAMPLES SHIPPED VIA <input type="checkbox"/> AIR FREIGHT <input type="checkbox"/> FED. EXP. <input type="checkbox"/> SAMPLER <input type="checkbox"/> OTHER _____			AIR BILL NUMBER:		

~~DISTRIBUTION: WHITE-ORIGINAL ACCOMPANIES SHIPMENT TO LAB, RETURNS TO BARR WITH RESULTS; YELLOW-LAB COPY; PINK-LAB COORDINATOR; GOLD-FIELD COPY~~

**GROUNDWATER SAMPLING AND ANALYSIS REQUEST**PROJECT NUMBER 13/49-C03 JSL 31

PROJECT TYPE:

PROJECT NAME WCP RI/FSMONITORING ☐RI ☒PROJECT MANAGER/DESIGNATE JSL / KAFOTHER ☐PROJECT DESCRIPTION/SITE HISTORY Phase I RI/FS / former coal gasification siteSITE LOCATION Waukegan, IllinoisQAPP YES ☒ NO ☐TURN AROUND TIME normalSITE SAFETY PLAN YES ☒ NO ☐DATE OF SCHEDULED SAMPLING April 6-10, 1992AGENCY NOTIFICATION/SPLIT YES ☐ NO ☒AGENCY CONTACT                     PHONE NUMBER                     

SAMPLING LOCATION	SAMPLING ORDER				ANALYSES REQUESTED
	WELL DIAMETER	TOTAL DEPTH	DEPTH TO WATER		
P101					water level with tape and chalk total well depth
P102					
P103					
P104					
Harbor					total well depth
mw35					
mw3D					
mw45					
mw4D					CLP-RAS TCL Volatiles
mw55					CLP-RAS TCL Semivolatiles
mw5D					CLP-RAS TCL Pesticides/PCBs
mw65					CLP-RAS TAL Metals/Cyanide
mw6D					
mw15					
mw1D					
carbon filter influent					
carbon filter effluent					

QC REQUIRED STANDARD ☐ SPECIAL NEEDS CLP proceduresDATA MANAGEMENT NEEDS data validation and entry - CLP protocolLABORATORY PREFERENCE CH<sub>2</sub>M HillMDL/METHOD REQUIREMENTS                     COMMENTS:

282

PROJECT: 13149-003 31

SAMPLING REQUEST FORM

SAMPLE ORDER AND LOCATION	STABILIZE	PREVIOUS VOLUME	40ML VIAL	40ML VIAL W/HCL	125ML AMBER W/TEFLON	500ML AMBER W/TEFLON	1L AMBER W/TEFLON	2L AMBER W/TEFLON	250ML PLASTIC	500ML PLASTIC	1L PLASTIC	250ML PLASTIC W/HNO3	500ML PLASTIC W/HNO3	1L PLASTIC W/HNO3	250ML PLASTIC W/H2SO4	500ML PLASTIC W/H2SO4	1L PLASTIC W/H2SO4	1500ML GLASS W/H2SO4	1L PLASTIC W/NaOH + ASCORBIC ACID	METHANE FLOW	EH	APPEARANCE	TEMPERATURE	CONDUCTIVITY	PH	WATER LEVEL
1. MW6D	X		3				2					X										X	X	X	X	
2. MW15	X		3				2					X										X	X	X	X	
3. MW1D	X		3				2					X										X	X	X	X	
4. carbon filter infl			3				2					X										X	X	X	X	
5. carbon filter effl			3				2					X										X	X	X	X	
6. (MW4D) M-1			3				2					X										X	X	X	X	
7. (MW6S) M-2			3				2					X										X	X	X	X	
8. MW55 MS			3				2					X										X	X	X	X	
9. MW55 MSD			3				2					X										X	X	X	X	
10. FB-1			3				2					X														
11. FB-2			3				2					X														
12.																										
(1) LABORATORY	F		C				C					CC							C			F	F	F	F	

(1) LABORATORY CODES: A = ASPEN P = PACE E = ENSECO F = FIELD/BARR C = CH2M HILL B = BRAUN D = EDI

BARR CONTACT \_\_\_\_\_ SPLIT \_\_\_\_\_ SCHEDULED DATE April 6-10 COMPLETION DATE \_\_\_\_\_  
 SPECIAL INSTRUCTIONS CLP Procedures

PROJECT MGR. JSL/KAF SAMPLER \_\_\_\_\_ FORM COMPLETED BY: KAF DATE: 4-2-92

DISTRIBUTION: WHITE- PROJECT FILE: YELLOW- LAB COORDINATOR: PINK- PROJECT MANAGER

# Barr

Engineering Company

## FIELD LOG DATA SHEET

Station: INFLUENT

Client WAKEGAN WCP RI/FS Project No. 113-49-003JSLB1

Location: \_\_\_\_\_ Date: 4/9/92 Sample Time: 1134

General		Stabilization Test					
		TIME/ VOLUME	TEMP CENT.	COND. umhos	COND. @ 25	pH	Eh
Barr Lock: Y N	_____	1.	11.0	4500	6000	8.3	
Casing Dia: (in.)	_____	2.					
Total Depth (ft.)	_____	3.					
Static Depth (ft.)	_____	4.					
Water Depth:	_____	5.					
Well Vol. (gal.)	_____	6.					
Purge Method:	_____	7.					
Samp. Method:	_____	Appearance:					
Start Time:	_____	Odor:					
Stop Time:	_____	Comments: 150 GAL IN TANK					
Duration: (min.)	_____	2.2 <del>PPM</del> PPM ORGANIC VAPORS IN TANK					
Rate, gpm:	_____	OVM					
Volume Purged:	_____	"INSIDE OF TANK"					
Samplers:		Others Present:					
gen _____		VOC <u>3</u> COD _____ TOC _____ semi-volatile <u>2</u> f. metal <u>1</u> t. metal _____					
nitro _____		cyanide <u>1</u> oil & grease _____ 200 ml filter _____ 500 ml filter _____					
others _____							

# Barr

Engineering Company

## FIELD LOG DATA SHEET

Station: effluent

Client: WAKEGAN WCP RI/FS Project No. 17-1491-003E51311

Location: \_\_\_\_\_ Date: 4/9/92 Sample Time: 1155

General		Stabilization Test					
		TIME/ VOLUME	TEMP CENT.	COND. umhos	COND. @ 25	pH	Eh
Barr Lock: Y N		1. <u>1155</u>	<u>10</u>	<u>6000</u>		<u>8.2</u>	
Casing Dia: (in.)		2.					
Total Depth (ft.)		3. <u>1740</u>	<u>9.0</u>	<u>6500</u>	<u>9000</u>	<u>8.2</u>	
Static Depth (ft.)		4.					
Water Depth:		5.					
Well Vol. (gal.)		6.					
Purge Method:		7.					
Samp. Method:		Appearance: <u>slight grey</u>					
Start Time:		Odor: <u>yes</u>					
Stop Time:		Comments: <u>0.0 ovm readings</u> <u>Clear, slight grey, headspace SAN</u>					
Duration: (min.)							
Rate, gpm:							
Volume Purged:							
Samplers:		Others Present:					
gen _____		VOC <u>3</u> COD _____ TOC _____ semi-volatile <u>2</u> f. metal <u>1</u> t. metal _____					
nitro _____		cyanide <u>1</u> oil & grease _____ 200 ml filter _____ 500 ml filter _____					
others _____		_____					

# Barr

Engineering Company

## FIELD LOG DATA SHEET

Station: MWGS-1

Client: WCP RT/FS

Project No. 113-149-10103JISK311

Location: \_\_\_\_\_ Date: 4/18/92 Sample Time: 1520

General		Stabilization Test					
		TIME/ VOLUME	TEMP CENT.	COND. umhos	COND. @ 25	pH	Eh
Barr Lock: <input checked="" type="checkbox"/> N		1. 4.5	11.0	950		7.6	
Casing Dia: (in.)	2"	2. 6.0	11.0	800		7.5	
Total Depth (ft.)	17	3. 7.5	11.0	800		7.5	
Static Depth (ft.)	7.70	4. 9.0	11.0	800	1100	7.5	
Water Depth:	9.5	5.					
Well Vol. (gal.)	1.5	6.					
Purge Method:	Cent	7.					
Samp. Method:	Butler	Appearance:					
Start Time:	1504	Odor:					
Stop Time:	1509	Comments: <u>M-2</u>					
Duration: (min.)	5						
Rate, gpm:	2						
Volume Purged:	10						
Samplers: <u>JEG KSS</u>		Others Present:					
gen _____ VOC <u>B</u> COD _____ TOC _____ semi-volatile <u>4</u> f. metal <u>2</u> t. metal _____							
nitro _____ cyanide <u>2</u> oil & grease _____ 200 ml filter _____ 500 ml filter _____							
others _____							



# Barr

Engineering Company

## FIELD LOG DATA SHEET

Station: MW60-1

Client: WCP RI/FS.

Project No. 1131-14191-101031514011

Location: \_\_\_\_\_ Date: 4/8/92 Sample Time: 1610

General		Stabilization Test					
		TIME/ VOLUME	TEMP CENT.	COND. umhos	COND. @ 25	pH	Eh
Barr Lock: <input checked="" type="radio"/> N		1. <u>10.5</u>	<u>11.0</u>	<u>10,100</u>		<u>7.5</u>	
Casing Dia: (in.)	<u>2"</u>	2. <u>14.0</u>	<u>11.0</u>	<u>10,100</u>		<u>7.5</u>	
Total Depth (ft.)	<u>29.5</u>	3. <u>17.5</u>	<u>11.0</u>	<u>10,100</u>	<u>13,500</u>	<u>7.5</u>	
Static Depth (ft.)	<u>7.81</u>	4.					
Water Depth:	<u>21.5</u>	5.					
Well Vol. (gal.)	<u>3.5</u>	6.					
Purge Method:	<u>Cent</u>	7.					
Samp. Method:	<u>Bailer</u>	Appearance: <u>orange / milky</u>					
Start Time:	<u>1547</u>	Odor: <u>yes</u>					
Stop Time:	<u>1556</u>	Comments:					
Duration: (min.)	<u>09</u>						
Rate, gpm:	<u>2</u>						
Volume Purged:	<u>17.5</u>						
Samplers: <u>JEG KSJ</u>		Others Present:					
gen _____ VOC <u>3</u> COD _____ TOC _____ semi-volatile <u>2</u> f. metal <u>1</u> t. metal _____							
nitro _____ cyanide <u>1</u> oil & grease _____ 200 ml filter _____ 500 ml filter _____							
others _____							

# Barr

Engineering Company

## FIELD LOG DATA SHEET

Station: MWIS-1

Client: WCP RI/FS

Project No. 1131491-0103JISL311

Location: \_\_\_\_\_ Date: 4/9/92 Sample Time: \_\_\_\_\_

General		Stabilization Test					
		TIME/ VOLUME	TEMP CENT.	COND. umhos	COND. @ 25	pH	Eh
Barr Lock	<u>(Y)</u> N	1. <u>6/GAL</u>	<u>11.0</u>	<u>1000</u>		<u>7.2</u>	
Casing Dia: (in.)	<u>2"</u>	2. <u>8/GAL</u>	<u>11.0</u>	<u>900</u>		<u>7.2</u>	
Total Depth (ft.)	<u><del>20.75</del></u>	3. <u>10/GAL</u>	<u>11.0</u>	<u>900</u>		<u>7.2</u>	
Static Depth (ft.)	<u>5.97</u>	4. <u>12/GAL</u>	<u>11.0</u>	<u>900</u>	<u>1200</u>	<u>7.2</u>	
Water Depth:	<u>14</u>	5.					
Well Vol. (gal.)	<u>2</u>	6.					
Purge Method:	<u>Cent</u>	7.					
Samp. Method:	<u>Baiter</u>	Appearance:					
Start Time:	<u>0952</u>	Odor:					
Stop Time:	<u>1004</u>	Comments: <u>FB-2</u>					
Duration: (min.)	<u>12</u>						
Rate, gpm:	<u>1</u>						
Volume Purged:	<u>12 GAL</u>						
Samplers: <u>JEG KSJ</u>		Others Present:					
gen _____		VOC <u>3</u> COD _____ TOC _____ semi-volatile <u>2</u> f. metal <u>1</u> t. metal _____					
nitro _____		cyanide <u>1</u> oil & grease _____ 200 ml filter _____ 500 ml filter _____					
others _____							

# Barr

Engineering Company

## FIELD LOG DATA SHEET

Station: MW1P

Client: WCP RI/FS

Project No. 131-1419-00BJSL311

Location: \_\_\_\_\_ Date: 4/9/92 Sample Time: 1035

General		Stabilization Test					
		TIME/ VOLUME	TEMP CENT.	COND. umhos	COND. @ 25	pH	Eh
Barr Lock <input checked="" type="radio"/> Y <input type="radio"/> N		1. 12/GAL	12.0	5000		8.6	
Casing Dia: (in.)	2"	2. 16/GAL	12.0	5000		8.6	
Total Depth (ft.)	30	3. 20/GAL	12.0	5000	6500	8.6	
Static Depth (ft.)	5.84	4.					
Water Depth:	24	5.					
Well Vol. (gal.)	4	6.					
Purge Method:	cent	7.					
Samp. Method:	Bailer	Appearance: <u>Foamy</u>					
Start Time:	1014	Odor: <u>Yer</u>					
Stop Time:	1021	Comments:					
Duration: (min.)	7						
Rate, gpm:	3						
Volume Purged:	20						
Samplers:		Others Present:					
gen _____ VOC <u>3</u> COD _____ TOC _____ semi-volatile <u>2</u> f. metal <u>1</u> t. metal _____							
nitro _____ cyanide <u>1</u> oil & grease _____ 200 ml filter _____ 500 ml filter _____							
others _____							

## APPENDIX I

### HYDROGEOLOGIC MODEL DEVELOPMENT

A preliminary simulation of groundwater flow in the vicinity of the site was performed using the Single Layer Analytic Element Model (SLAEM). SLAEM is described in the Revised Technical Memorandum, Proposed Modeling for RI/FS, Waukegan Manufactured Gas and Coke Plant (WCP) Site. The preliminary simulation was developed to provide an initial evaluation of steady-state groundwater flow patterns, to provide guidance in locating monitoring wells to be installed during the second phase of the investigation, to identify data gaps to be addressed during the second phase of the investigation, and to design the pumping test to be performed during Phase II.

The conceptual hydrogeologic model for the site consists of an unconfined homogeneous sand aquifer which overlies a relatively impermeable clay till. The aquifer is recharged by precipitation in areas not covered by buildings or impermeable materials, and groundwater may discharge to Lake Michigan, Waukegan Harbor, and the North Ditch north of OMC Plant No. 2. Given that the aquifer is essentially homogeneous and bounded on four sides by surface water bodies with similar water elevations, conceptual long-term groundwater flow patterns may be expected to consist of a groundwater divide (or mound) centered on the peninsula.

Several simplifying assumptions about the hydrogeologic conditions of the site were made during development of the model. The validity of these assumptions must be reevaluated with the additional hydrogeologic data that will be collected during the second phase of this investigation. First, it was assumed that the hydraulic conductivity of the sand unit is constant because the hydraulic conductivity estimates for the upper and basal portions of the sand aquifer are similar. Boring logs indicate that discontinuous layers of silty sand and silt with sand are present within the sand unit, but information on their extent and hydraulic properties is not available. However, the hydraulic conductivity estimates obtained during the first phase of the investigation are representative of both sands and silty sands (Fetter, 1988). Second, the

aquifer base is assumed to be horizontal and not sloping. Third, the entire thickness of the aquifer is assumed to discharge to the North Ditch in areas north of OMC Plant No. 2. Finally, groundwater elevations measured on May 7, 1992 (the middle of a two-month period of water level measurements), are assumed to be representative of average steady-state flow patterns. Harbor levels remained essentially constant ( $580.5 \pm 0.1$ ) feet MSL) during the measurement period.

The Phase I modeling approach was to adjust infiltration until calibration was achieved, given: that predicted groundwater flow directions for the conceptual model would be essentially controlled by constant head boundaries and the proximity of those boundaries to areas receiving or not receiving infiltration; that the predicted groundwater elevations would be controlled by values of hydraulic conductivity and infiltration rate; and that both the constant head boundaries and hydraulic conductivity would remain constant in the model. If the infiltration rate necessary to achieve calibration was reasonable, it could also be concluded that the estimate of hydraulic conductivity used in the model was reasonable.

The configurations of hydrogeologic features included in the preliminary simulation of groundwater flow at the WCP site are discussed in the following paragraphs and illustrated on Figures I-1 through I-2. The data files for the model are attached.

The model addresses two-dimensional horizontal flow in the unconsolidated sand unit. The aquifer in the model has a hydraulic conductivity of 6 feet/day ( $2.1 \times 10^{-3}$  cm/sec) beneath the site and in the vicinity of the OMC Plant No. 2 site (Figure I-1; JRB, 1981) and an assumed hydraulic conductivity of 20 feet/day everywhere else. Because the aquifer beneath the site and in the vicinity of OMC Plant No. 2 is bounded on all sides by a constant head boundary, as described below, the magnitude of the hydraulic conductivity outside these constant head boundaries (20 feet/day or  $7.1 \times 10^{-3}$  cm/sec) does not affect the solution for the aquifer beneath the site. The porosity of the unit was assumed to be 0.30 (Fetter, 1988). The impermeable lower boundary of the model is the till unit. The elevation of the base of the aquifer is 558 feet MSL, the average elevation at which the till unit was encountered in the soil borings.

The upper boundary of the aquifer is treated as an unconfined surface within the sand unit.

The presence of Lake Michigan/Waukegan Harbor on the east, south, and west sides of the site and the new boat slip are simulated using a series of head-specified linesinks. Based on the measurements of the water level in the harbor (Table 2.2-20), the elevation of the lake, harbor, and slip in the simulation was set at 580.5 feet MSL.

According to the 1981 JRB report for the OMC Plant No. 2 site, the ditch north of that site receives groundwater flow most of the year and has a water elevation that is an average of 0.5 feet higher than the lake (JRB, 1981). For this reason, the ditch is simulated as a head-specified linesink with an elevation of 581 feet MSL (Figure I-1).

The bentonite slurry wall on the east end of the new slip is simulated as a leaky wall with a thickness of 2 feet, an assumed porosity of 0.45, and an assumed hydraulic conductivity of  $10^{-6}$  cm/sec.

The bluff to the west of the site represents the western boundary of the sand aquifer. The bluff could have been simulated by pinching the sand aquifer out using a series of thickness inhomogeneities or by placing a linesink with a specified head along the bluff. Because marshes exist at the base of the bluff northwest of the site, the bluff is represented by a linesink instead of inhomogeneities. The specified head of the linesink is 580 feet MSL, the approximate elevation of the groundwater in the marshes northwest of the site (Figure I-1).

Recharge to the aquifer is simulated as a large given-strength areal element centered on the peninsula (Figure I-2). Downward vertical hydraulic gradients in the sand aquifer indicate that the peninsula is a recharge area. The infiltration rate is set at 0.0013 feet/day, which is the equivalent of about 5.7 inches/year. This infiltration rate represents the infiltration rate that was necessary to achieve model calibration. It is considered a reasonable value for the hydrologic setting of the site because it falls within the range

of infiltration rates (5.3 to 7.4 inches per year) published for surficial sand and gravel aquifers in northeast Illinois (Schicht et al., 1976).

Large areas of no infiltration, namely the OMC Plant No. 1 and Plant No. 2 and their adjacent parking lots, were simulated as areal elements having infiltration rates equal but opposite to the simulated recharge rate (Figure I-2).

The preliminary simulation was calibrated by fitting the simulated groundwater elevations at the shallow monitoring wells and piezometers to the actual field measurements made at these wells. The computed groundwater elevations were fitted to the groundwater elevation measurements made on May 7, 1992. In order to achieve model calibration, the infiltration rate was adjusted by trial and error until the differences between the observed and computed values at 90 percent of the observation points (8 of 9 observation points) were less than the total error associated with the observed groundwater elevations. A comparison between the observed and computed groundwater elevations is summarized in Table I-1. The total error associated with the observed groundwater elevations is presented in Table I-2. The largest source of error in the groundwater elevation measurements is due to the variation in groundwater elevations observed over the two-month monitoring period. Since the water level in the harbor remained essentially constant over this period, the calibration could not be more certain than the observed variation in groundwater levels.

The computed potentiometric surface for the preliminary simulation of current site conditions is shown on Figure I-3. The simulation shows that there is a potential for a groundwater mound on-site, centered on the peninsula. Predicted groundwater flow is towards the ditch and lake from the northern boundary of the site, toward the harbor and slip from most of the site, and toward the lake from the eastern fringe of the site. Groundwater from the southern portion of the site is predicted to be flowing to both the lake and harbor.

The groundwater flow patterns predicted by the preliminary model were compared to contour maps of measured groundwater elevations to assess the representativeness of the predicted flow-patterns and to help identify data

gaps. Groundwater elevation contour maps prepared from measured data are shown on Figures 2.2-5 through 2.2-8. A second, more interpretive groundwater elevation contour map was prepared from the May 7, 1992 measured data to provide an alternative representation of flow patterns for comparison to the model results. This contour map is shown on Figure 2.2-9 and incorporates both the measured groundwater elevation data for May 7, 1992 and conceptual ideas of groundwater flow patterns (as derived from the preliminary model).

The general patterns of groundwater flow that were indicated by results of preliminary modeling indicate a potential for eastward flow from the eastern fringe of the site. This pattern of flow differs from that inferred from the water table elevation contour interpretations shown on Figures 2.2-5 through 2.2-8, which indicate flow toward the southeast from the northeast corner of the site. However, as shown on Figure 2.2-9, the actual water level data are not necessarily inconsistent with the concept of eastward flow from the eastern fringe of the site. In order to more fully assess the representativeness of the groundwater flow patterns predicted by the preliminary model, groundwater elevation measurements from the southern and northeastern portions of the site, as well as from areas north and east of the site, will be necessary. Section 3.3 describes the rationale for the locations of additional monitoring wells to be installed during the second phase of the investigation to provide data for such an assessment.

The preliminary groundwater flow modeling identified several data gaps to be addressed in the second phase of the investigation. These include the need for: water level measurements on the northeastern and southern portions of the site as well as north and east of the site to better define groundwater flow patterns, water level measurements in the North Ditch north of OMC Plant No. 2 to better understand the hydraulic connection between the North Ditch and the aquifer; more frequent water level measurements over a longer period of time to better understand the nature and magnitude of the variations in groundwater flow patterns and elevations over time; and geologic/hydrogeologic data to assess variable zones that may be present within the sand aquifer to determine their extent and hydraulic influence. Each of these data gaps is addressed in the work plan for the second phase of the investigation.



In addition to being used to assess groundwater flow patterns and identify data gaps, the preliminary model was used to design the pumping test to be conducted during the Phase II investigation. First, a general pumping well location was chosen based on the following factors: proximity to several possible monitoring points; location outside of source areas; and location near (but not adjacent to) surface water. For these reasons, it was decided to conduct pumping test scenarios in the vicinity of Monitoring Wells MW-1S and MW-1D and Piezometer P-104. The scenarios were conducted using the transient well feature in SLAEM and a specific storage of  $0.01 \text{ feet}^{-1}$ . Different pumping well locations (from 15 to 100 feet south and 0 to 120 feet east of Monitoring Wells MW-1S), pumping rates (10 to 25 gpm), and pumping test durations (one to two days) were simulated in an effort to optimize drawdown in the observation wells (MW-1S, MW-1D, P-104) and minimize the amount of water produced. The pumping well data file is attached. Two scenarios predicted observable drawdowns at Wells MW-1S and MW-1D and minimized water production. Each scenario had one pumping well that was pumping at a rate of 15 gpm. In one scenario, the pumping well was located 15 feet south of Well MW-1S. In the other scenario, the pumping well was located 25 feet south of Well MW-1S. The predicted drawdowns for these scenarios after one day of pumping are shown on Figures I-4 and I-5, respectively. None of the simulations predicted observable drawdown at Piezometer P-104.

TABLE I-1

GROUNDWATER FLOW MODEL CALIBRATION  
OBSERVED AND CALCULATED GROUNDWATER ELEVATIONS

MONITORING WELL	OBSERVED ELEVATIONS (FT. MSL) 5/7/92	CALCULATED ELEVATIONS (FT. MSL)	DIFFERENCE (FT.)
MW-1S	581.63	581.49	-.14
MW-3S	582.27	582.22	-.05
MW-4S	582.15	582.39	.23
MW-5S	580.73	580.58	-.15
MW-6S	580.86	580.42	-0.44
P-101	581.80	581.61	-.19
P-102	582.36	582.15	-.21
P-103	581.81	582.36	.55
P-104	582.15	582.28	.13
MEAN ABSOLUTE ERROR			.23

TABLE I-2

## GROUNDWATER ELEVATION ERROR ANALYSIS

SOURCE OF ERROR	MAGNITUDE (FT.)
Well Survey Elevations	$\pm 0.05$
Water Level Measurements	$\pm 0.02$
Average Absolute Difference in Groundwater Elevation Measurements Over the Period of April 7 to May 7, 1992	$\pm 0.40$
Total Error	$\pm 0.47$




Figure I-1  
GROUNDWATER FLOW SIMULATION  
ANALYTIC ELEMENTS




Figure I-2

GROUNDWATER FLOW SIMULATION  
CURRENT SITE CONDITIONS  
ANALYTIC ELEMENT LAYOUT




Figure I-3

PRELIMINARY GROUNDWATER FLOW SIMULATION  
CURRENT SITE CONDITIONS




Figure I-4

PREDICTED DRAWDOWN  
PUMPING WELL LOCATED 25 FEET  
SOUTH OF MW-1S




Figure I-5

PREDICTED DRAWDOWN  
PUMPING WELL LOCATED 15 FEET  
SOUTH OF MW-1S



\*\*\*\*\*  
\* FILENAME: WPCAL6 \*  
\* CALLFILE FOR SLAEM MODEL OF WAUKEGAN COKE PLANT SITE\*  
\* NEW SLIP AND DITCH ARE PRESENT \*  
\* WCP R1/FS PHASE I 13/49-003JSL33 \*  
\* JULY 10, 1992 \*  
\*\*\*\*\*

CALL WCPAQU.DAT \* GLOBAL AQUIFER DATA FILE  
CALL WCPINF2.DAT \* INFILTRATION AREAL ELEMENT MINUS BLDs AND PARKING LOTS  
CALL LAKE.DAT \* LINE SINK IN LAKE MICHIGAN  
CALL WCPMAP.DAT \* MAP FILE  
CALL WCPLINE3.DAT \* LAKE MICHIGAN AND HARBOR LINE SINKS  
CALL WCPDROOT.DAT \* SLURRY WALL OF SLIP  
CALL WCPDOUB3.DAT \* HYDRAULIC CONDUCTIVITY INHOMOGENEITY OF SITE  
CALL WCPDITCH.DAT \* DITCH NORTH OF SITE  
END

RET

\*\*\*\*\*

\* FILENAME: WCPAQU.DAT \*

\* GLOBAL AQUIFER FILE \*

\* WCP RI/FS PHASE I 13/49-003JSL33 \*

\* JUNE 5, 1992 \*

\*\*\*\*\*

WINDOW -3000 -3000 6000 6000

REF

0 5000 580 \* ELEVATION OF LAKE MICHIGAN IN FEET MSL

RET

AQUI

BASE 558

PERM 20 \* FEET/DAY

THICK 100

POR .3

SS .001

RET

RET

SWI

BACK

RET

\*\*\*\*\*

\* FILENAME: WCPINF2.DAT \*

\* INFILTRATION FILE \*

\* NO INFILTRATION ON BLDG AND LOTS \*

\* WCP RI/FS PHASE I 13/49-003JSL33 \*

\* JULY 10, 1992 \*

\*\*\*\*\*

RET

ARE

GIVEN

\* -9340 -9240 -9340 10760 10660 10760 10660 -9240 -.001 [INF] \*INFILTRATION

-9400 -10000 -9400 10000 10600 10000 10600 -10000 -.0013 [INF] \*INFILTRATION

-584.989 2212.13 -1.76896 2608.36 1218.70 2591.14 1218.70 2143.27 .0013

-652.793 2229.35 -666.301 1557.93 364.267 1592.36 364.267 2194.92 .0013

364.267 1833.38 364.267 1592.36 825.387 1592.36 811.879 1833.38 .0013

811.879 2160.48 811.879 1402.99 1218.70 1385.77 1218.70 2160.48 .0013

-29.0495 -9.24476 -69.5730 -422.425 1083.09 -456.857 1110.11 -26.4606 .0013

RET

RET

SWI

BACK

\*\*\*\*\*  
\* FILENAME: LAKE.DAT \*  
\* LINE SINK IN LAKE MICHIGAN \*  
\* WCP RI/FS PHASE I 13/49-003JSL33 \*  
\* JUNE 5, 1992 \*  
\*\*\*\*\*

RET

LINE LINE

HEAD

-0.382313E+02 -0.300000E+04 580  
0.974238E+03 -0.267817E+04 580  
0.274606E+04 -0.171414E+04 580  
0.401165E+04 -0.106949E+03 580  
0.451788E+04 0.214293E+04 580  
0.502411E+04 0.407146E+04 580

RET

RET

SWI

BACK

\*\*\*\*\*  
\* FILENAME: WCPMAP.DAT \*  
\* MAP FILE FOR THE WAUKEGAN COKE PLANT SITE \*  
\* WCP RI/FS PHASE I 13/49-003JSL33 \*  
\* JUNE 5, 1992 \*  
\*\*\*\*\*

RET

RET

MAP

PLOT ON

CURVE \* SITE BOUNDARY

-45.6872 -8.49399

1116.94 -18.2034

1126.22 370.631

1100.25 373.873

1131.99 877.556

1207.01 1381.08

397.047 1392.66

212.914 1411.43

-45.6872 -8.49399

CURVE \* OMC OFFICE

1016.46 57.7289

1016.23 -6.03198

1059.52 -5.40117

1059.76 59.9341

1016.46 57.7289

CURVE \* OMC OFFICE (LARGE)

962.582 396.412

963.110 324.776

952.087 324.029

954.261 272.067

963.709 272.820

964.184 186.228

1068.88 186.637

1070.25 348.792

1064.74 349.599

1064.78 361.407

1052.2 363.026

1052.32 397.662

962.582 396.412

CURVE \* CANONIE TRAILER

878.272 591.938

878.843 532.110

901.671 532.027

904.234 587.908

878.272 591.938  
CURVE \* SOIL STOCKPILE  
261.936 817.724  
267.531 623.269  
461.173 621.783  
461.094 817.792  
261.936 817.724  
CURVE \* LARSEN GATE  
673.316 1383.79  
672.645 1198.02  
685.231 1195.61  
685.035 923.252  
380.296 896.014  
382.581 874.752  
119.580 852.087  
CURVE \* OMC PLANT 1  
-30.9679 -47.4554  
47.3005 -15.2524  
63.5569 -70.1022  
228.570 -68.4812  
236.891 -115.551  
928.685 -140.189  
929.071 -179.478  
1015.27 -155.056  
1008.26 -241.569  
1039.54 -225.544  
1040.16 -288.407  
1008.80 -296.573  
1017.28 -359.358  
1087.92 -350.806  
1080.83 -429.461  
192.754 -422.467  
177.656 -485.484  
91.4525 -509.907  
98.3842 -415.536  
27.5868 -408.373  
20.5779 -494.886  
-42.3614 -487.646  
-58.7722 -417.080  
-66.9380 -385.726  
-68.2502 -252.144  
-22.1074 -149.529  
-30.9679 -47.4554  
CURVE \* OMC PLANT 2  
-660.008 1588.80

660.177 1593.91  
659.714 1641.05  
816.947 1634.74  
834.824 1414.88  
1220.16 1387.23  
1220.45 2157.37  
953.369 2146.89  
945.126 2186.10  
827.182 2192.80  
814.091 1925.48  
735.513 1924.71  
728.504 1838.19  
366.969 1842.50  
371.276 2204.04  
-650.621 2233.29  
-664.330 2028.83  
-703.465 2012.73  
-708.852 1761.21  
-661.706 1761.67  
-660.008 1588.80

CURVE \* LARSEN MARINE

-41.1988 1269.64  
-87.0026 1158.56  
24.0836 1112.75  
62.1084 1215.84  
-41.1988 1269.64

CURVE \* LARSEN MARINE

-508.662 1413.09  
-150.650 1197.13  
-88.3094 1253.21  
-318.695 1368.38  
-81.5096 1332.20  
-58.3904 1371.97  
-508.662 1413.09

CURVE \* WATERWORKS BUILDING

389.516 -783.577  
391.259 -909.785  
533.461 -923.601  
531.501 -781.616  
537.646 -655.299  
450.443 -624.944  
452.512 -774.817  
389.516 -783.577

POINT

235.660 1403.45 \* P-101

1157.41 1367.96 \* P-102  
668.253 403.398 \* P-103  
774.191 902.794 \* P-104  
753.488 1378.38 \* MW-3S  
753.432 1365.80 \* MW-3D  
1070.31 504.591 \* MW-4S  
1075.85 513.998 \* MW-4D  
10.3217 202.728 \* MW-5S  
11.9143 207.437 \* MW-5D  
121.572 838.07 \* MW-6S  
121.621 849.072 \* MW-6D  
530.194 822.128 \* MW-1S  
527.026 816.640 \* MW-1D

CURVE \* LARSEN MARINE

53.9722 1131.73  
83.9402 1297.45  
181.321 1278.85  
153.724 1115.48  
53.9722 1131.73

CURVE \* SCALE BAR 1000 FEET LONG

1300 -833  
2300 -833

RET

RET

SWI

BACK

CURVE \* 581 WATER TABLE ELEVATION

169.354 1159.31  
347.047 1175.03  
478.225 1157.95  
565.276 1115.13  
604.972 1026.93  
592.824 945.246  
507.723 895.319  
388.175 876.196  
243.440 848.537  
178.817 808.738  
141.471 716.161  
133.046 587.303  
157.357 396.211  
201.513 249.831  
300.122 154.299  
411.524 108.224  
537.952 83.3053  
714.852 97.4613



844.752 147.191  
939.312 203.364  
1043.44 292.504  
1140.59 399.752  
1201.95 591.253  
1223.91 760.921  
1245.89 932.946  
1259.87 1075.14  
1275.36 1200.82  
1299.71 1375.98

CURVE \* 582 WATER TABLE ELEVATION

458.788 1385.17  
538.490 1279.51  
596.269 1192.80  
647.616 1073.11  
688.046 973.122  
714.147 831.537  
735.497 682.114  
811.959 554.455  
926.314 465.141  
1030.02 457.612  
1087.64 512.375  
1103.79 612.119  
1120.91 751.156  
1147.71 949.097  
1178.68 1200.46  
1203.76 1362.25  
1222.39 1488.71

RET

RET

SWI

BACK

\*\*\*\*\*  
\* FILENAME: WCPLINE3.DAT \*  
\* LINESINKS REPRESENTING LAKE MICHIGAN, THE HARBOR, AND THE BLUFF \*  
\* THE NEW SLIP AND DITCH ARE PRESENT \*  
\* WCP RI/FS PHASE I 13/49-003JSL33 \*  
\* JUNE 12, 1992 \*  
\*\*\*\*\*

RET

RET

LINE \* LAKE MICHIGAN

HEAD

4816.24 13916.7 4870.43 12810.8 580  
4870.43 12810.8 4565.89 10064.6 580  
4565.89 10064.6 4675.58 9313.23 580  
4675.58 9313.23 4457.39 8853.39 580  
4457.39 8853.39 4428.73 7196.27 580  
4428.73 7196.27 4035.46 6850.58 580  
4035.46 6850.58 2927.35 6906.25 580  
2927.35 6906.25 2184.42 6765.33 580  
2184.42 6765.33 2038.79 6212.77 580  
2038.79 6212.77 2756.63 6046.99 580  
2756.63 6046.99 2943.44 6506.19 580  
2943.44 6506.19 3182.83 6699.54 580  
3182.83 6699.54 3920.82 6699.05 580  
3920.82 6699.05 3769.20 5675.32 580  
3769.20 5675.32 2372.00 3377.63 580  
2372.00 3377.63 2266.09 2802.34 580  
2266.09 2802.34 2076.21 2492.245 580  
2076.21 2492.245 2001.54 2405.52 580  
2001.54 2405.52 1886.33 2182.15 580  
1886.33 2182.15 1788.31 1414.6745 580  
1788.31 1414.6745 1690.29 647.199 580  
1690.29 647.199 1765.405 240.504 580  
1765.405 240.504 1840.52 -166.191 580  
1840.52 -166.191 1663.545 -150.211 580.5  
1663.545 -150.211 1486.57 -134.231 580.5  
1486.57 -134.231 1324.885 -479.0745 580.5  
1324.885 -479.0745 1163.20 -823.918 580.5  
1163.20 -823.918 1170.76 -1000.404 580.5  
1170.76 -1000.404 1178.32 -1176.89 580.5  
1178.32 -1176.89 923.11625 -1174.2975 580.5  
923.11625 -1174.2975 667.9125 -1171.705 580.5  
667.9125 -1171.705 412.70875 -1169.1125 580.5  
412.70875 -1169.1125 157.505 -1166.52 580.5  
157.505 -1166.52 72.9635 -1064.2408 580.5

72.9635 -1064.2408 -11.578 -961.9615 580.5  
-11.578 -961.9615 -96.1195 -859.68225 580.5  
-96.1195 -859.68225 -180.661 -757.403 580.5  
-180.661 -757.403 -159.0975 -470.40303 580.5  
-159.0975 -470.40303 -137.534 -183.403 580.5  
-137.534 -183.403 -92.30935 -92.186671 580.5  
-92.30935 -92.186671 -47.0847 -.970341 580.5  
\*-47.0847 -.970341 91.3485 985.828 580.5 \* TURN OFF WHEN SLIP IS ON  
-47.0847 -.970341 105.520 883.356 580.5 \* SLIP  
105.520 883.356 342.178 905.628 580.5 \* SLIP  
342.178 905.628 342.215 924.548 580.5 \* SLIP  
342.215 924.548 515.000 941.173 580.5 \* SLIP  
RET \* SLIP  
RET \* SLIP  
LINE \* SLIP  
HEAD \* SLIP  
504.000 1109.52 339.405 1092.77 580.5 \* SLIP  
339.405 1092.77 342.507 1071.54 580.5 \* SLIP  
342.507 1071.54 182.897 1054.57 580.5 \* SLIP  
182.897 1054.57 171.001 1001.92 580.5 \* SLIP  
171.001 1001.92 127.760 998.867 580.5 \* SLIP  
127.760 998.867 91.3485 985.828 580.5 \* SLIP  
91.3485 985.828 -458.782 1309.48 580.5  
-458.782 1309.48 -481.192 1254.06 580.5  
-481.192 1254.06 -88.2545 853.922 580.5  
-88.2545 853.922 -182.025 451.596 580.5  
-182.025 451.596 -301.192 519.798 580.5  
-301.192 519.798 -346.660 440.353 580.5  
-346.660 440.353 -251.281 2.67227 580.5  
-251.281 2.67227 -412.521 -173.368 580.5  
-412.521 -173.368 -1050.18 292.390 580.5  
-1050.18 292.390 -1127.20 220.146 580.5  
-1127.20 220.146 -575.377 -270.935 580.5  
-575.377 -270.935 -709.932 -1741.81 580.5  
-709.932 -1741.81 -927.237 -1864.05 580.5  
-927.237 -1864.05 -908.638 -2766.51 580.5  
-908.638 -2766.51 -1230.47 -3149.99 580.5  
-1230.47 -3149.99 -1561.39 -6901.65 580  
-1561.39 -6901.65 -1465.38 -8132.26 580  
RET  
RET  
LINE \* BLUFF 600 FT MSL  
HEAD  
-952.018 11528.9 -1814.39 7279.58 580  
-1814.39 7279.58 -2191.77 1972.49 580

RET  
RET  
SWI  
BACK

\*\*\*\*\*  
\* FILENAME: WCPDROOT.DAT \*  
\* DROOT ELEMENT REPRESENTING THE SLURRY WALL OF THE NEW SLIP \*  
\* WCP RI/FS PHASE I 13/49-003JSL33 \*  
\* JUNE 5, 1992 \*  
\*\*\*\*\*

RET

DROOT \* SLURRY WALL OF NEW SLIP

LEAK

505.944 1109.52 536.623 1109.49 710 2 .45

539.770 1110.28 548.286 945.080 710 2 .45

543.565 944.297 516.817 941.173 710 2 .45

RET

RET

SWI

BACK

\*\*\*\*\*  
\* FILENAME: WCPDOUB3.DAT \*  
\* DOUBLET ELEMENT REPRESENTING HYDRAULIC CONDUCTIVITY OF THE \*  
\* WAUKEGAN COKE PLANT SITE \*  
\* THE NEW SLIP IS PRESENT \*  
\* WCP RI/FS PHASE I 13/49-003JSL33 \*  
\* JUNE 12, 1992 \*  
\*\*\*\*\*

RET

RET

doub

inhom 6 100 558 .3

1788.31 1414.6745

1690.29 647.199

1765.405 240.504

1840.52 -166.191

1663.545 -150.211

1486.57 -134.231

1324.885 -479.0745

1163.20 -823.918

1170.76 -1000.404

1178.32 -1176.89

923.11625 -1174.2975

667.9125 -1171.705

412.70875 -1169.1125

157.505 -1166.52

72.9635 -1064.2408

-11.578 -961.9615

-96.1195 -859.68225

-180.661 -757.403

-159.0975 -470.40303

-137.534 -183.403

-92.30935 -92.186671

\*-47.0847 -.970341 \* TURN OFF WHEN SLIP IS ON

-47.0847 -.970341 \* SLIP

105.520 883.356 \* SLIP

342.178 905.628 \* SLIP

342.215 924.548 \* SLIP

515.000 941.173 \* SLIP

504.000 1109.52 \* SLIP

339.405 1092.77 \* SLIP

342.507 1071.54 \* SLIP

182.897 1054.57 \* SLIP

171.001 1001.92 \* SLIP

127.760 998.867 \* SLIP

91.3485 985.828  
-458.782 1309.48  
-927.451 1690.90  
-805.707 2156.09  
-691.411 2574.01  
-554.215 3070.80  
-353.605 3513.09  
-222.535 3813.17  
272.793 3841.15  
784.269 3822.08  
1288.15 3771.47  
1775.55 3807.25  
2137.30 3818.32  
2664.51 3799.39  
2400.69 3388.01  
2379.67 3096.77  
2266.09 2802.34  
2076.21 2492.245  
1886.33 2182.15  
RET  
RET  
SWI  
BACK

\*\*\*\*\*  
\* FILENAME: WCPDITCH.DAT \*  
\* LINE SINK REPRESENTING LINE SINK NORTH OF SITE \*  
\* WCP RI/FS PHASE I 13/49-003JSL33 \*  
\* JUNE 12, 1992 \*  
\*\*\*\*\*

RET

RET

LINE

HEAD

-674.645 2240.11 -550.247 2508.56 581  
-550.247 2508.56 -124.879 2479.57 581  
-124.879 2479.57 -39.4300 2676.93 581  
-39.4300 2676.93 480.376 2656.38 581  
480.376 2656.38 1086.79 2636.33 581  
1086.79 2636.33 1834.70 2656.50 581  
1834.70 2656.50 2001.54 2405.52 581

RET

RET

SWI

BACK



\*\*\*\*\*  
\* FILENAME: WCPPWELL.DAT \*  
\* PUMPING TEST DESIGN \*  
\* WCP RI/FS PHASE I 13/49-003JSL33 \*  
\* JUNE 5, 1992 \*  
\*\*\*\*\*

RET

WELL

TWELL

530.194 807.128 2888 0 \* PUMPING WELL 15 FEET SOUTH OF MW-1S, 15 GPM  
530.194 807.128 -2888 1 \* SHUT OFF PUMPING WELL AFTER ONE DAY  
\*530.194 797.128 2888 0 \* PUMPING WELL 25 FEET SOUTH OF MW-1S, 15 GPM  
\*530.194 797.128 -2888 1 \* SHUT OFF PUMPING WELL AFTER ONE DAY  
\*530.194 797.128 4813 0 \* PUMPING WELL 25 FEET SOUTH OF MW-1S, 25 GPM  
\*530.194 797.128 -4813 1 \* SHUT OFF PUMPING WELL AFTER ONE DAY  
\*530.194 772.128 1925 0 \* PUMPING WELL 50 FEET SOUTH OF MW-1S, 10 GPM  
\*530.194 772.128 -1925 2 \* SHUT OFF PUMPING WELL AFTER TWO DAYS  
\*530.194 722.128 2888 0 \* PUMPING WELL 100 FEET SOUTH OF MW-1S, 15 GPM  
\*530.194 722.128 -2888 1 \* SHUT OFF PUMPING WELL AFTER ONE DAY  
\*580.194 747.128 2888 0 \* PUMPING WELL 75 FT SOUTH AND 50 FT E OF MW-1S, 15 GPM  
\*580.194 747.128 -2888 2 \* SHUT OFF PUMPING WELL AFTER TWO DAYS  
\*650.194 822.128 2888 0 \* PUMPING WELL 120 FEET EAST OF MW-1S, 15 GPM  
\*650.194 822.128 -2888 2 \* SHUT OFF PUMPING WELL AFTER TWO DAYS

RET


RET

SWI

BACK

***Appendix J***

***IEPA Investigation  
Soil Quality Data***



PUT SIZE HERE 6-oz. Cone Puff  
PUT ORDER NUMBER HERE NLD 980993570

**TABLE 4-1**  
**SUMMARY**

**GENERAL NOTE**

**POULICES (C)**

4-5-74

2005  
01-01

1003  
11-5  
-4-88

44-38861-17

6-7-77

2005  
36-45

24-45

2-17-88

$$\frac{X107}{517}$$

**Diagnosis**

# Vingl Oloride Chloroethane

## References

### 1.1-Dachkornett

**1,2-Dichloroethane**

1,2-Dichloroethane (15%)

1,1,1-trichloroethane

**Handchlorien**

5-1,3-Dichloro

**Dihydroxyacetone**

**Erasmus**

4-11-2-Pen

Let's achieve with

8.2.2.2-165 and

## Hydrogen

**My home (booked)**

**STANDARD**  
**(3)**

**Phenyl**  
**bi-(2-O-allyl) ether**

11

11

•

11

11

21

2

1

•

**新 516 号 516**

第 4-1 頁



PUT SITE NAME HERE  
PUT USER NAME OR HERE

## TABLE 4-1

### Summary

**SERIALS P. 0207**

[illegible]

POSTAGE WILL BE PAID BY ADDRESSEE

1990



**PUT SITE NAME HERE.  
PUT URSUM NUMBER HERE**

**TABLE 4-1**  
**SUMMARY**

[illegible]



**PUT SITE NAME HERE**  
**PUT LISTEN NUMBER HERE**

**TABLE 4-1**  
**Summary**

## SAFETY POINT

6-44-59

KAG  
 6-10-59

BAK  
 6-10-59

6-26-59

**10-ethyl-7-oxohept-5-enylamine**

## 5. The company: Phosphor

## Product literature

**Presently**

**800-441-4411**

三、

**Page**

**Diethylbenzylphthalate**

### 3,3'-Bis(4-methoxyphenyl)-

**On the**

### 6.2-Ethylhexylphthalate

Do not delay! Get the

**Learn On Your Own**

**Revised July 1999**

### Abstract 1, 2, 3 and 4 were

**Diabetes & Insulin**

only 1000 copies

CPH3 + PAPH2

1000

二、

三三三

**4015-001**

**James Earl Ray (alias)**

三

## Myxobolus spenioides

**Exhibit 1**

1546-1547

6-11-56

## Butterfly II

1-100

**Endorsement**

**Exhibit (Merits)**

**End in Kerala**

PUT SJTE ABOVE HERE  
PUT USEPA NUMBER HERE

**ADAMS**  
**1-1 37841**

[illegible]

PUT SITE NAME HERE  
PUT USOPR NUMBER HERE

TABLE 4-1  
Summary

SPALLS POINT	10075 6-10-95	1008 6-10-95	1008 6-10-95
alpha-Chloroethane	-	-	-
gamma-Chloroethane	-	-	-
Isophane	-	-	-
1001.0R-1016	-	-	-
1001.0R-1221	-	-	-
1001.0R-1222	-	-	-
1001.0R-1242	-	-	-
1001.0R-1248	-	-	-
1001.0R-1254	-	-	-
1001.0R-1268	-	-	-

# INORGANICS

ALUMINUM	-1000	-340	-26.0 B
ANTIMONY	-0.5 B	-0.3 u	-0.4 u
ARSENIC	-38.0	-3.9	-0.2 u
BARIUM	-12.0	-16.0 B	-0.3 u
BERYLLIUM	-76	-2.9	-0.1 u
BROMINE	-2.1	-1.9	-0.2 u
CALCIUM	-33500	-24300	-23.4 u
CARBON	-17.0	-10.0	-0.6 u
COPPER	-6.4 B	-4.0 B	-0.6 B
COPPER	-3.0	-8.7	-0.6 B
IRON	-24600	-3700	-7.4 u
LEAD	-91.0	-4.0	-2.6 u
MANGANESE	-1300	-12.4 u	-12.4 u
MERURY	-38.0	-0.0 u	-0.2 u
NICKEL	-150	-8.8	-1.1 B
POTASSIUM	-570 B	-110 B	-62.0 u
SELENIUM	-0.6 B	-0.2 u	-0.2 u
SILVER	-1.4 B	-0.7 B	-0.9 B
SODIUM	-570 B	-340 B	-33.0 B
TALLIUM	-0.3 B	-0.1 u	-0.2 u
THALLIUM	-16.0	-9.4	-0.4 B
ZINC	-128	-50.0	-12.2 u
CHLORIDE	-3.1	-0.7 u	-10.0 u
SULFIDE	-	-	-

## ORGANIC DATA QUALIFIERS

- U - Indicates compound was analyzed for but not detected.
- J - Indicates an estimated value. This flag is used either when estimating a concentration for tentatively identified compounds where a 1:1 response is assumed, or when the mass spectral data indicate the presence of a compound that meets the identification criteria but the result is less than the sample quantitation limit but greater than zero.
- C - This flag applies to pesticide results where the identification has been confirmed by GC/MS.
- B - This flag is used when the analyte is found in the associated blank as well as in the sample.
- E - This flag identifies compounds whose concentrations exceed the calibration range of the GC/MS instrument for that specific analysis. This flag will not apply to pesticide/PCB's analyzed by GC/EC methods.
- D - This flag identifies all compounds identified in an analysis at a secondary dilution factor.
- A - This flag indicates that a TIC is a suspected aldol-condensation product.
- X - Other specific flags and footnotes may be required to properly define the results. If used, they must be fully described and such description attached to the Sample Data Summary Package and the Case Narrative.

## INORGANIC DATA QUALIFIERS

## C (Concentration) Qualifier:

- B - Indicates the reported value is less than the Contract Required Detection Limit (CRDL) but greater than the Instrument Detection Limit (IDL).
- U - Indicates compound was analyzed for but not detected.

## Q Qualifier:

- E - The reported value is estimated because of the presence of interference.
- M - Duplicate injection precision not met.
- N - Spiked sample recovery not within control limits.
- S - The reported value was determined by the Method of Standard Additions (MSA).
- W - Post-digestion spike for Furnace AA analysis is out of control limits (85-115%), while the sample absorbance is less than 50% of spike absorbance.
- \* - Duplicate analysis not within control limits.
- + - Correlation coefficient for the MSA is less than 0.995.

## M (Method) Qualifier Enter:

- "P" for ICP
- "A" for Flame AA
- "F" for Furnace AA
- "CV" for Manual Cold Vapor AA
- "AV" for Automated Cold Vapor AA
- "AS" for Semi-Automated Spectrophotometric
- "C" for Manual Spectrophotometric
- "T" for Titrimetric
- "NR" if the analyte is not required to be analyzed.

## ***Appendix K***

### ***Laboratory Standard Operating Procedures Additional Parameters***

<u>METHOD</u>	<u>METHOD REFERENCE</u>
ALKALINITY	EPA 310.1
ACIDITY	EPA 305.1
AMMONIA NITROGEN	EPA 350.2
ARSENIC (III) AND ARSENIC (V)	USGS
BOD	EPA 405.1
CATION-EXCHANGE CAPACITY OF SOILS	EPA9081
CHLORIDE	EPA 407 B
COD	EPA 410.4
pH	EPA 150.1
SULFATE	EPA 375.4
SULFIDE	EPA 376.1
TOTAL HARDNESS	EPA 130.2
TOTAL DISSOLVED SOLIDS	EPA 160.1
TOTAL ORGANIC CARBON	EPA 415.1
THIOCYANATE	SM 4500-CN-M
TOTAL AND AMENABLE CYANIDE	EPA 9010A/9012A
WEAK ACID DISSOCIABLE CYANIDE	SM 4500-CN-I

## ***ALKALINITY***

Method 310.1 (Titrimetric, pH 4.5)

Optimum Concentration Range:  
Sensitivity:  
Approximate Detection Limit:  
LIMS Test Code: ALK  
EPA Holding Time: 14 Days

### **1.0 Method Summary:**

An unaltered sample is titrated to an electrometrically determined end point of pH 4.5. The sample must not be filtered, diluted, concentrated, or altered in any way.

### **2.0 Bench Sheets:**

Fill out the ALKALINITY bench sheet before beginning any analyses. Include all pertinent information such as sample size, dilution factors, dates of analysis, and sample ID. As the analysis proceeds, problems, titration values, and other information are written on the bench sheet immediately. The analyst must initial and date the bench sheet when the sample run is completed.

### **3.0 Spreadsheet:**

All sample data and QC data should be entered into the ALKALINITY computer spreadsheet program within 24 hours after the analysis is completed. All calculations, whether manual or by computer, must be completed within 24 hours after analysis is completed as well. Date and initial the bench sheet when the data is entered into the spreadsheet program. Results will be copied onto the bench sheets where appropriate, to facilitate entry of data into LIMS. When bench sheets are completed, a copy is made for each sample group or client represented in the analytical run. Client/sample names are highlighted. The original bench sheet is placed into the parameter binder with other information. Copies for each client are included with the client- or sample-specific file, to facilitate the final review of



a specific client's samples before the report is issued to the client.

When all sample and QC data have been entered, all calculations have been made, and the spreadsheet information has been saved to disk, the analyst will print hard copies of the related analytical data, control charts, and other pertinent areas of the spreadsheet. These hard copies will be initialled, and clipped to the original bench sheet. The analyst will review the data according to section 6 in the SOP manual. This review should be done within 24 hours of the analysis. When the analyst has completed the review, the data packet is placed into the parameter binder in the laboratory with the time noted on the bench sheet.

#### **4.0 Data Review Process:**

After the data review process has been completed (see Section 6 of the SOP Manual), within 24 hours it is the responsibility of the analyst to enter the data into LIMS or have a data-entry clerk enter the data into LIMS. The person who enters the data will initial and date the bench sheet with a time, and the binder will be returned to the laboratory.

#### **5.0 Quality Control Samples:**

For ALKALINITY analyses, the following control samples are included on the bench sheet and should be run with each batch of samples:

- \* method blank
- \* QC check sample
- \* duplicate samples

Acceptance limits for these quality control samples are as follows:

- \* method blank - The analyst should run a sample of distilled, deionized water through the procedure as indicated, and use this as a comparison sample for the "blank." Values for pH and alkalinity of the water can be entered on a spreadsheet to document the reproducibility of the procedure and the

quality of the water being used for analyses in the wet chemistry section.

- \* QC check sample - The spreadsheet has an area for entering data from the QC check sample. True value is given and the % recovery is calculated. This is charted on a control chart and statistical information is generated. The recovery on the QC sample must be within  $\pm 3S$  for acceptance. When the QC recovery is outside this range, the system must be checked, a new QC sample made up, and the associated batch of samples must be re-analyzed. This must be documented on a corrective action report.
- \* duplicate samples - Generally an RPD of 20 is considered the outside limit. The spreadsheet has an area for entry of duplicate analysis data. This will be charted after each analytical run. Acceptance limits are RPD inside  $\pm 3S$ .

#### 6.1 Apparatus:

- a. pH meter or electrically operated titrator that uses a glass electrode and can be read to 0.05 pH units.
- b. Appropriate glass vessels to keep the air space above the solution at a minimum.
- c. Magnetic stirrer, pipets, standard laboratory equipment.
- d. Burets, pyrex, 50, 25, 10 mL.

#### 6.2 Reagents:

- a. Sodium carbonate solution, approximately 0.05 N:  
Place 2.5 g (to nearest mg)  $\text{Na}_2\text{CO}_3$  (dried at  $250^\circ\text{C}$  for 4 hours and cooled in desiccator) into a 1 L volumetric flask and dilute to the mark.
- b. Standard acid (sulfuric or hydrochloric), 0.1 N:  
Dilute 3.0 mL concentrated  $\text{H}_2\text{SO}_4$  or 8.3 mL concentrated HCl to about 1 L with distilled water.

- 1) Standardize versus 40.0 mL of 0.05 N  $\text{Na}_2\text{CO}_3$  solution with about 60 mL distilled water.
- 2) Titrate potentiometrically to pH of about 5. Lift electrode and rinse into beaker. Boil solution gently for 3-5 minutes under a watch glass cover. Cool to room temperature. Rinse cover glass into beaker. Continue titration to the pH inflection point.
- 3) Calculate normality by using:

$$N = \frac{A \times B}{53.00 \times C}$$

where A = g  $\text{Na}_2\text{CO}_3$  weighed in 1 L  
B = mL  $\text{Na}_2\text{CO}_3$  solution  
C = mL acid used to inflection point

- c. Standard acid (sulfuric or hydrochloric), 0.02 N: Dilute 200.0 mL of 0.1000 N standard acid to 1 L with distilled water. Standardize by potentiometric titration of 15.0 mL and 0.05 N  $\text{Na}_2\text{CO}_3$  solution as above.

### 6.3 Procedure:

- a. The pH meter must be calibrated before running this analysis. Check the calibration log for the pH meter to determine if the meter has been calibrated on this date. If not, calibrate the meter using the SOP for pH, found in this SOP manual.
- b. Sample size:
  - 1) Use a sufficiently large volume of titrant (>20 mL in a 50 mL buret) to obtain good precision while keeping volume low enough to permit sharp end point.
  - 2) For <1000 mg  $\text{CaCO}_3$  /L use 0.02 N titrant.
  - 3) For >1000 mg  $\text{CaCO}_3$  /L use 0.1 N titrant.

c. Potentiometric titration:

- 1) Place sample in flask by pipetting with pipet tip near bottom of flask.
- 2) Measure and record pH of sample.
- 3) Add standard acid, being careful to stir thoroughly but gently to allow needle to obtain equilibrium.
- 4) Titrate to pH 4.5. Record volume of titrant.

d. Potentiometric titration of low alkalinity:

- 1) For alkalinity of <20 mg/L titrate 100-200 mL as above using a 10 mL microburet and 0.02 N acid solution.
- 2) Stop titration at pH in range of 4.3-4.7, record volume and exact pH. Very carefully add titrant to lower pH by exactly 0.3 pH units. Record volume of titrant.

6.4 Calculation:

a. Potentiometric titration to pH 4.5:

$$\text{alkalinity, mg/L CaCO}_3 = \frac{A \times N \times 50\,000}{\text{mL of sample}}$$

where: A = mL standard acid  
N = normality standard acid

b. Potentiometric titration of low alkalinity:

$$\text{alkalinity, mg/L CaCO}_3 = \frac{(2B - C) \times N \times 50\,000}{\text{mL of sample}}$$

where: B = mL titrant to first recorded pH  
C = total mL titrant to reach pH exactly 0.3 pH units lower  
N = normality of acid

**6.4 Reporting:**

a. Alkalinity is reported in units of mg/L CaCO<sub>3</sub> .

**7.0 Notes:**

- 7.1. This method is suitable for all concentration ranges of alkalinity. However, appropriate aliquots should be used to avoid a titration volume greater than 50 mL.
- 7.2. The sample must not be filtered, diluted, concentrated, or altered in any way.
- 7.3. The sample should be refrigerated at 4°C and run as soon as possible. Do not open the sample bottle before analysis.
- 7.4. For samples having high concentrations of mineral acids, such as mine wastes and associated receiving waters, titrate to an electrometric endpoint of pH 3.9.
- 7.5. Oil and grease, by coating the pH electrode, may also interfere, causing sluggish response.

CH2M HILL/MGM SOP (Acidity)  
Rev. 0 1/30/89

## **ACIDITY**

Method 305.1 (Titrimetric)

Optimum Concentration Range:  
Sensitivity:  
Approximate Detection Limit:  
LIMS Test Code: ACID  
EPA Holding Time: 14 Days

### **1.0 Method Summary:**

The pH of the sample is determined and a measured amount of standard acid is added, as needed, to lower the pH to 4 or less. Hydrogen peroxide is added, the solution boiled for several minutes, cooled, and titrated electrometrically with standard alkali to pH 8.2.

### **2.0 Bench Sheets:**

Fill out the ACIDITY bench sheet before beginning any analyses. Include all pertinent information such as sample size, dilution factors, dates of analysis, and sample ID. As the analysis proceeds, problems, titration values, and other information are written on the bench sheet immediately. The analyst must initial and date the bench sheet when the sample run is completed.

### **3.0 Spreadsheet:**

All sample data and QC data should be entered into the ACIDITY computer spreadsheet program within 24 hours after the analysis is completed. All calculations, whether manual or by computer, must be completed within 24 hours after analysis is completed as well. Date and initial the bench sheet when the data is entered into the spreadsheet program. Results will be copied onto the bench sheets where appropriate, to facilitate entry of data into LIMS. When bench sheets are completed, a copy is made for each sample group or client represented in the analytical run. Client/sample names are highlighted. The original bench sheet is placed into the parameter binder with other information.

CH2M HILL/MGM SOP (Acidity)  
Rev. 0 1/30/89

Copies for each client are included with the client- or sample-specific file, to facilitate the final review of a specific client's samples before the report is issued to the client.

When all sample and QC data have been entered, all calculations have been made, and the spreadsheet information has been saved to disk, the analyst will print hard copies of the related analytical data, control charts, and other pertinent areas of the spreadsheet. These hard copies will be initialled, and clipped to the original bench sheet. The analyst will review the data according to section 6 in the SOP manual. This review should be done within 24 hours of the analysis. When the analyst has completed the review, the data packet is placed into the parameter binder in the laboratory with the time noted on the bench sheet.

**4.0 Data Review Process:**

After the data review process has been completed (see Section 6 of the SOP), within 24 hours it is the responsibility of the analyst to enter the data into LIMS or to have a data-entry clerk enter the data into LIMS. The person who enters the data will initial and date the bench sheet with a time, and the binder will be returned to the laboratory.

**5.0 Quality Control Samples:**

For ACIDITY analyses, the following control samples are included on the bench sheet and should be run with each batch of samples:

- \* method blank
- \* QC check sample
- \* duplicate samples

Acceptance limits for these quality control samples are as follows:

- \* method blank - The analyst should run a sample of distilled, deionized water through the procedure as indicated, and use this as a comparison sample for the "blank." Values for pH and acidity of the water can be entered on a

CH2M HILL/MGM SOP (Acidity)Rev. 0 1/30/89

spreadsheet to document the reproducibility of the procedure and the quality of the water being used for analyses in wet chemistry.

- \* QC check sample - The spreadsheet has an area for entering data from the QC check sample. True value is given and the % recovery is calculated. This is charted on a control chart and statistical information is generated. The recovery on the QC sample must be within  $\pm 3S$  for acceptance. When the QC recovery is outside this range, the system must be checked, a new QC sample made up, and the associated batch of samples must be re-analyzed. This must be documented on a corrective action report.
- \* duplicate samples - Generally an RPD of 20 is considered the outside limit. The spreadsheet has an area for entry of duplicate analysis data. This will be charted after each analytical run. Acceptance limits are RPD inside  $\pm 3S$ .

#### 6.1 Apparatus:

- a. pH meter, suitable for electrometric titrations
- b. ordinary laboratory glassware

#### 6.2 Reagents:

- a. Hydrogen peroxide ( $H_2O_2$ , 30% solution): Available commercially.
- b. Standard sodium hydroxide, 0.02 N: Dissolve 8 g NaOH in distilled water in a 1000 mL volumetric flask. Mix thoroughly, cool, and dilute to volume with distilled water.
- c. Standard sulfuric acid, 0.02 N: Add 5.6 mL concentrated sulfuric acid to water in a 1000 mL volumetric flask. Dilute to volume and mix well.



CH2M HILL/MGM SOP (Acidity)  
Rev. 0 1/30/89

**6.3 Procedure:**

- a. The pH meter must be calibrated before this analysis is begun. Check the calibration log for this date to see that the pH meter has been calibrated today. If not, calibrate using the SOP for pH, located in the SOP Manual.
- b. Pipet 50 mL of the sample into a 250 mL beaker.
- c. Measure the pH of the sample. If the pH is above 4.0, add standard sulfuric acid in 5.0 mL increments to lower the pH to 4.0 or less. If the initial pH is less than 4.0, the incremental addition of sulfuric acid is not required.
- d. Add 5 drops hydrogen peroxide solution.
- e. Heat the sample to boiling and continue boiling for 2 to 4 minutes. In some instances the concentration of ferrous iron is such that an additional amount of hydrogen peroxide and a slightly longer boiling time may be required.
- f. Cool the sample to room temperature and titrate electrometrically with standard sodium hydroxide to pH 8.2.

**6.4 Calculation:**

a. 
$$\text{Acidity as mg/L CaCO}_3 = \frac{[(A \times B) - (C \times D)] \times 50,000}{\text{mL of sample}}$$

where: A = vol.std. NaOH used in titration  
B = normality of std. NaOH solution  
C = vol.std. sulfuric acid used to produce pH <4.0  
D = normality of std. sulfuric acid

- b. If it is desired to report acidity in milliequivalents per liter, the reported values as CaCO<sub>3</sub> are divided by 50.

CH2M HILL/MGM SOP (Acidity)  
Rev. 0 1/30/89

**6.5 Reporting:**

- a. Acidity is reported in units of mg/L  $\text{CaCO}_3$ .
- b. Reporting limits: Values below 10 mg/L are reported as <10.

**7.0 Notes:**

- 7.1. The method covers the range from approximately 10 mg/L acidity to approximately 1000 mg/L as  $\text{CaCO}_3$  using a 50 mL sample.
- 7.2. The method measures the mineral acidity of a sample plus the acidity resulting from oxidation and hydrolysis of polyvalent cations, including salts of iron and aluminum.
- 7.3. Suspended matter present in the sample, or precipitates formed during the titration may cause a sluggish electrode response. This may be offset by allowing a 15-20 second pause between additions of titrant or by slow dropwise addition of titrant as the endpoint pH is approached.

**NH3**  
(Nitrogen, Ammonia)

Method 350.2 (Titrimetric Procedure - Distillation)

Optimum Concentration Range:  
Sensitivity:  
Approximate Detection Limit:  
LIMS Test Code: NH3  
Holding Time: 28 Days

**1.0 Method Summary:**

The sample is buffered at a pH of 9.5 with a borate buffer in order to decrease hydrolysis of cyanates and organic nitrogen compounds, and is then distilled into a solution of boric acid. The ammonia in the distillate is determined titrimetrically with standard sulfuric acid with the use of a mixed indicator.

**2.0 Bench Sheets:**

Fill out the NH3-AMMONIA bench sheet before beginning any analyses. Include all pertinent information such as sample size, dilution factors, dates of analysis, and sample ID. As the analysis proceeds, problems, variations, and other information are written on the bench sheet immediately. The analyst must initial and date the bench sheet when the sample run is set up and when the run is completed.

**3.0 Spreadsheet:**

All sample data and QC data should be entered into the NH3-AMMONIA computer spreadsheet program within 24 hours after the analysis is completed. Calculations can be done manually or by use of the computer program. Date and initial the bench sheet when the data is entered into the spreadsheet program. When all QC data have been entered, all calculations have been made, and the spreadsheet information has been saved to disk, the analyst will print hard copies of the related control charts, and other pertinent areas of the spreadsheet. These hard copies will be initialled, and clipped to the original bench sheet.

When bench sheets are completed, the analyst will make copies for each client/sample group represented in the analytical run. The original bench sheet is put into the parameter binder with other pertinent information, for data review and for data entry. Copies are filed with client- or sample-specific files, to facilitate the final review of the final report for a client or sample group.

The analyst then reviews the data according to section 6 in the SOP manual. This review should be done within 24 hours of the analysis. When the analyst has completed the review, the data packet is placed in the parameter binder in the laboratory with the time noted on the bench sheet.

#### **4.0 Data Review Process:**

After the data review process has been completed (see Section 6 of the SOP Manual), within 24 hours, it is the responsibility of the analyst to enter the data into LIMS or to have the data-entry clerk enter the data into LIMS. The person who enters the data will initial and date the bench sheet, with a time, and the binder will be returned to the laboratory.

#### **5.0 Quality Control Samples:**

For NH3-AMMONIA analyses, the following control samples are included on the bench sheet and should be run with each batch of samples:

- \* method blank
- \* QC check sample
- \* duplicate samples

Acceptance limits for these quality control samples are as follows:

- \* method blank - if the analyte of interest is detected in the method blank, any sample in which the analyte is present at < 10X the level detected in the blank must be re-analyzed. The spreadsheet has a section for entering blank result data.

- \* QC check sample - The spreadsheet has an area for entering data from the QC check sample. True value is given and the % recovery is calculated. This is charted on a control chart and statistical information is generated. The recovery on the QC sample must be within  $\pm 3S$  for acceptance. When the QC recovery is outside this range, the system must be checked, a new QC sample made up, and the associated batch of samples must be re-analyzed. This must be documented on a corrective action report.
- \* duplicate samples - Generally an RPD of 20 is considered the outside limit. The spreadsheet has an area for entry of duplicate analysis data. This will be charted after each analytical run. Acceptance limits are RPD inside  $\pm 3S$ .

## 6.0 Analytical Procedure:

### 6.1 Apparatus:

- a. An all-glass distilling apparatus with an 800-1000 mL flask.
- b. Erlenmeyer flasks: The distillate is collected in 500 mL glass-stoppered flasks. These flasks should be marked at the 350 mL and 500 mL volumes. With such markings, it is not necessary to transfer the distillate to volumetric flasks.

### 6.2 Reagents:

- a. Distilled water should be free of ammonia. All solutions should be made with ammonia-free water.
- b. Ammonium chloride, stock solution: 1.0 mL = 1.0 mg  $\text{NH}_4\text{-N}$ : Dissolve 3.819 g  $\text{NH}_4\text{Cl}$  in distilled water and bring to volume in a 1 L volumetric flask.
- c. Ammonium chloride, standard solution: 1.0 mL = 0.01 mg: Dilute 10.0 mL of stock

solution to 1 L in a volumetric flask.

- d. Boric acid solution (20g/L): Dissolve 20 g  $H_3BO_3$  in distilled water and dilute to 1 L.
- e. Mixed indicator: Mix 2 volumes of 0.2% methyl red in 95% ethyl alcohol with 1 volume of 0.2% methylene blue in 95% ethyl alcohol. This solution should be prepared fresh every 30 days.
- g. Borate buffer:
  - 1) Sodium tetraborate solution, 0.025 M: Add 5.0 g anhydrous sodium tetraborate or 9.5 g hydrated sodium tetraborate to 1 L water.
  - 2) Add 88 mL of 0.1 N NaOH solution to 500 mL of 0.025 M sodium tetraborate solution and dilute to 1 L with distilled water.
- h. Sulfuric acid, standard solution, 0.02 N;  
(1 mL = 0.28 mg  $NH_3-N$ ):
  - 1) Prepare a stock solution of approximately 0.1 N acid by diluting 3 mL of concentrated  $H_2SO_4$  to 1 L with  $CO_2$ -free distilled water. Dilute 200 mL of this solution to 1 L with  $CO_2$ -free distilled water.
  - 2) Standardize the acid against the  $Na_2CO_3$  solution. See i, below.
- i.  $Na_2CO_3$ , 0.0200 N: Dissolve 1.060 g anhydrous  $Na_2CO_3$ , oven-dried at  $140^\circ C$ , and dilute to 1 L with  $CO_2$ -free distilled water.
- j. Sodium hydroxide, 1 N: Dissolve 40 g NaOH in ammonia-free water and dilute to 1 L.
- k. De-chlorinating agents: Dissolve 3.5 g sodium thiosulfate in distilled water and dilute to 1 L.  
  
1 mL of this solution will remove 1 mg/L of residual chlorine in 500 mL of sample.

6.3 Procedure:

6.3.1 Preparation of equipment:

- 1) Add 500 mL of distilled water to an 800 mL Kjeldahl flask. The addition of boiling chips which have been previously treated with dilute NaOH will prevent bumping.
- 2) Steam out the distillation apparatus until the distillate shows no trace of ammonia with Nessler reagent.

6.3.2 Sample preparation:

- 1) Remove the residual chlorine in the sample by adding dechlorinating agent equivalent to the chlorine residual.
- 2) To 400 mL of sample, add 1 N NaOH until the pH is 9.5, checking the pH during addition with a pH meter or by use of short-range pH paper.

6.3.3 Distillation:

- 1) Transfer the sample, the pH of which has been adjusted to 9.5, to an 800 mL Kjeldahl flask and add 25 mL of the borate buffer. Distill 300 mL at the rate of 6-10 mL/minute into 50 mL of 2% boric acid contained in a 500 mL Erlenmeyer flask.
- 2) The condenser tip or an extension of the tip must extend below the level of the boric acid solution.

6.3.4 Determination of ammonia in distillate:

- 1) Determine the ammonia content of the distillate titrimetrically.
- 2) Add 3 drops of the mixed indicator to the distillate and titrate the ammonia with the 0.02 N  $H_2SO_4$ , matching the end point against a blank containing the

same volume of distilled water and H<sub>3</sub>BO<sub>3</sub> solution.

6.3.5 Standards:

- 1) It is not necessary that all standards be distilled in the same manner as the samples.
- 2) It is recommended that at least two standards, low and high, be distilled and compared to similar values on the curve to insure that the distillation technique is reliable.

6.4 Calculation: For titrimetric determinations:

$$\text{mg/L NH}_3\text{-N} = \frac{A \times 0.28 \times 1000}{S}$$

where: A = mL 0.02 N H<sub>2</sub>SO<sub>4</sub> used  
S = mL sample

7.0 Reporting:

- a. Ammonia-nitrogen is reported in units of mg/L.
- b. Values below 0.1 mg/L are reported as <0.1.

8.0 Notes:

- 8.1 The method covers the range from about 0.05 to 1.0 mg NH<sub>3</sub>-N/L for the titrimetric procedure.
- 8.2 Samples may be preserved with 2 mL concentrated H<sub>2</sub>SO<sub>4</sub> per liter and stored at 4°C.
- 8.3 Cyanate will hydrolyze to some extent, even at pH of 9.5.
- 8.4 Residual chlorine must be removed by pretreatment of the sample with sodium thiosulfate before distillation.





Engineers  
Planners  
Economists  
Scientists

## STANDARD OPERATING PROCEDURE

### SEPARATION PROCEDURE FOR ARSENIC (III) AND ARSENIC (V)

#### IN GROUND WATER AND SURFACE WATER

#### METHOD REFERENCE

Walter H. Picklin, Separation of Arsenic (III) and Arsenic (V) in Ground Water and Surface Water, Talanta, Vol. 30, No. 5, 1983.

#### Reagents:

1. Hydrochloric Acid (HCL) concentrated, "Baker Analyzed" Reagent grade JT9535-33
2. Glacial Acetic acid, VWR Reagent ACS VWO125-3
3. Sodium Hydroxide, EM Science Reagent Grade, Solid pellets, EM-SX0590-3
4. Sodium Arsenite, Baker Analyzed, Solid Crystal, JT3487-04
5. Sodium Arsenate-Dibasic, 7-Hydrate, Granular, Baker Analyzed JT3486-04
6. Nickel Standard, 1000 ppm, EM Science Lot 8210, used for Modifier JT2784-1
7. Nanopure deionized water
8. Ion exchange resin: Dowex 1X8 anion (100-200 mesh) Bio-Rad P/N745-1441

#### Apparatus:

- Resin columns: Glass econo-columns, 10 cm X 7 mm disposable; Bio-Rad P/N737-0710
- Test Tubes: Glass, 12 ml VWR 60825-630

#### Chemical Preparation:

1. To prepare 0.12 M HCL, add 10 ml of conc HCL to a 1 liter volumetric flask and dilute to mark with nanopure deionized water.
2. To prepare 1 M NaOH, add 40.0 gms of Sodium Hydroxide to a 1 liter volumetric flask and dilute to mark with nanopure deionized water.



3. To prepare 1 M Acetic Acid, add 57.5 mls of Reagent grade Glacial Acetic Acid to a 1 liter volumetric flask and dilute to 1 liter with nanopure deionized water.

4. To prepare a 1000 ppm solution of As (III), add 1.7339 gms of Sodium Arsenite ( $\text{NaAsO}_2$ ) to a 1 liter volumetric flask, add 900 ml nanopure water to dissolve, 10 ml of conc HCL to preserve and then dilute to 1 liter with nanopure deionized water.

5. To prepare a 1000 ppm solution of As (V), dissolve 4.1645 gms of Sodium Arsenate-Dibasic, 7-Hydrate in a 1 liter flask with 900 mls of nanopure water, preserve with 10 ml of conc HCL and dilute to 1 liter with nanopure deionized water.

#### Column Preparation:

1. To prepare the columns for Arsenic separation, weigh out 2.3 grams of Bio-Rad Dowex 1X8 anion-resin, 100-200 mesh.

2. Slurry pack the resin with nanopure water into Bio-Rad 10 cm X 7 mm disposable econo-columns.

3. Convert the resin to the acetate form by adding 3 mls of 1M NaOH and allow to drain through the column, followed by 15 mls of nanopure deionized water rinse.

4. Then add 5 ml of 1M Acetic Acid and allow to drain through the column, followed by a final 15 ml nanopure deionized water rinse.

5. Columns are then capped while still wet to keep moist and dust free.

#### Separation Procedure:

1. Acidify 100 mls of 0.45 micron filtered samples with 1 ml of conc HCL.

2. To separate the samples for Arsenic (III) and (V), uncap the prepared columns and add 5 ml of acidified sample and allow to drain from the column into a 12 ml glass test tube.

3. Next add 5 ml of 0.12 M HCL to the column, allow to drain, and collect in the test tube containing the eluted 5 ml sample.

4. Remove the test tube, cap, mix and save as fraction 1 for Arsenic (III) analysis.



5. Repeat by adding 2-5 ml portions of 0.12 M HCL to the column and collect both elutriates together in a second tube for analysis.

6. Cap and mix the second tube, then label as fraction 2 for Arsenic (V) analysis.

#### Quality Control:

1. Preparation blanks of 0.12M HCL are passed through the procedure exactly as the samples at 1 in 20.

2. Column performance is monitored by passing of 5 mls of mixed standard at 20 ug/l of both As (III) and As (V) through the procedure exactly as the samples. *50 ug/L 2*

3. Duplicate samples are speciated and analyzed at 1 in 20.

4. Matrix spikes at 20 ug/l of both As (III) and As (V) of a mixed standard are prepared and analyzed exactly as the samples at 1 in 20.

#### Analysis:

Analyze the fractions by Zeeman graphite furnace atomic absorption spectroscopy using EPA method 206.2, 600/4-79-020.

TOTAL P.07

# SEPARATION OF ARSENIC(III) AND ARSENIC(V) IN GROUND WATERS BY ION-EXCHANGE

WALTER H. FICKLIN

U.S. Geological Survey, Box 25046, Denver, CO 80225, U.S.A.

(Received 17 August 1982, Accepted 5 November 1982)

**Summary**—The predominant species of arsenic in ground water are probably arsenite and arsenate. These can be separated with a strong anion-exchange resin (Dowex 1 x 8; 100–200 mesh, acetate form) in a 10 cm x 7 mm column. Samples are filtered and acidified with concentrated hydrochloric acid (1 ml per 100 ml of sample) at the sample site. Five ml of the acidified sample are used for the separation. At this acidity, As(III) passes through the acetate-form resin, and As(V) is retained. As(V) is eluted by passage of 0.12M hydrochloric acid through the column (resulting in conversion of the resin back into the chloride form). Samples are collected in 5-ml portions up to a total of 20 ml. The arsenic concentration in each portion is determined by graphite-furnace atomic-absorption spectrophotometry. The first two fractions give the As(III) concentration and the last two the As(V) concentration. The detection limit for the concentration of each species is 1 µg/l.

Arsenic in ground waters occurs in the oxidation states As(III) and As(V). Recently Cherry *et al.*<sup>1</sup> proposed that the concentrations of As(III) and As(V) could be used to calculate the oxidation-reduction potential of a ground water sample. The redox potential is an important factor in the study of ground waters as a sample medium for geochemical exploration.

A popular method<sup>2,3</sup> for determining low levels of As(III) and As(V) involves generation of arsine, coupled with atomic-absorption detection. Careful control of sample pH is required in order to generate arsine selectively from As(III).<sup>2,3</sup> The sample must also be analyzed very soon after collection or stabilized in some way to prevent oxidation of As(III). Acidification with hydrochloric acid prevents the oxidation<sup>4</sup> but the pH must then be carefully adjusted before the analysis. Nakashima<sup>5</sup> added Zr(IV) and potassium iodide to the acidified sample to generate arsine selectively from As(III). All the methods require complex equipment and procedures.

A simple separation of As(III) and As(V) based on ion-exchange is presented here. The sample can be stored in acidified solution or the separation can be performed at the sample site before any chemical change can take place. The use of an anion-exchange resin for separation of arsenic species in water has been investigated by Heary and Thorpe,<sup>6</sup> but they used separate portions of sample water for determination of As(III) and As(V). Pacey and Ford used a similar ion-exchange method to determine organic and inorganic arsenic species,<sup>7</sup> with detection by graphite-furnace atomic-absorption spectrophotometry (GFAAS).

GFAAS determination of arsenic, with addition of nickel, is well established.<sup>8</sup> Small volumes of sample are required and a detection limit of 1 µg/l. is readily achieved. GFAAS was therefore chosen for the determinations in the present work.

## EXPERIMENTAL

### Apparatus

A Perkin-Elmer model 703 atomic-absorption spectrophotometer\* equipped with a deuterium arc background corrector and an HGA-2200 graphite furnace was used for arsenic determination. Glass "secco-columns" were obtained from Bio-Rad Laboratories (Richmond, California). The samples were injected manually by Eppendorf pipette or with a Perkin-Elmer As-1 auto-sampler.

### Reagents

Hydrochloric acid, nitric acid, acetic acid, sodium arsenite, disodium hydrogen arsenate heptahydrate, sodium hydride and nickel nitrate 6-hydrate were "Baker Analyzed", supplied by J. T. Baker Chemical Co. Dowex 1 x 8 anion-exchange resin (100–200 mesh) was supplied by Bio-Rad Laboratories. Demineralized water was obtained from a Millipore Milli-Q water system.

### Column preparation

Glass "secco-columns" (10 cm x 7 mm) were used for all separations. Enough resin (2.3 g) was slurry-packed into the column to fill it to within 1 or 2 mm of the top. The resin was supplied in the chloride form and required conversion into the acetate form through the hydride form as intermediate. This was achieved by allowing 3 ml of 1M sodium hydride to drain through the resin, followed by 15 ml of water and then 5 ml of 1M acetic acid. The resin was rinsed once more with water, leaving the resin in the acetate form. A small amount of water was added to the columns to keep the resin moist. The columns were capped to prevent contamination from dust.

### Procedure

At the sample site, 50 ml of water were filtered through a 0.45-µm membrane filter (to remove particulate matter that might contain soluble or acid-leachable arsenic), and

\*Any use of trade names is for descriptive purposes only and does not imply endorsement by the U.S. Geological Survey.

Table 1. Instrumental parameters for graphite-furnace atomic-absorption spectrometer

Drying	60 sec	100 C	
Charring	20 sec	950 C	
Atomizing	6 sec	2700 C	Interrupt mode
Purge gas	Argon		
Source	Electrodeless discharge lamp		

then acidified with 0.5 ml of concentrated hydrochloric acid. Five ml of the acidified sample were allowed to pass through the resin in the column, followed by 15 ml of 0.12*M* hydrochloric acid as eluent, added in three separate 5-ml portions. The successive 5-ml fractions of effluent (one from the sample, three from the eluent) were collected in 6-ml vials, which were then capped. The As(III) from the sample was in the first two fractions and the As(V) in the last two.

Table 2. Results for arsenic speciation in ground waters and acid mine waters

Sample	As(III), μg/l.	As(V), μg/l.	Total As, μg/l.
M002*	23	7	30
M021*	<1	3	3
M022*	2	5	7
M027*	1	18	18
M030*	2	6	8
M043	1	6	8
M045*	54	16	69
BV-012*	8	6	14
BV-020*	2	4	5
BV-039*	<1	5	5
BV-041*	<1	5	5
BV-046*	1	10	11
MS-02†	13	1	15
MS-03†	5	2	7
MS-04†	5	2	7
MS-06†	5	1	6
MS-08†	4	1	6
Salt Spring, Utah	1400	1180	2450

\*Irrigation well water, Beaver Area, Utah.

†Acid mine water, Colorado.




Fig. 1. Separation of As(III) and As(V): a, b, d, 25-ml sample; interrupted mode; 10-ml fractions; c, 10-ml sample; 25-ml fractions; interrupted mode.

nick and  
through  
of 0.12M  
rate 3-ml  
(one from  
d in 6-ml  
he sample  
last two.

Table 3. Recovery of added arsenic

Sample	As(III), µg/l.	As(V), µg/l.	As(III), µg/l.	As(V), µg/l.
M-007	1	18	6	24
BV-012	6	5	12	10
BV-041	<1	5	5	11
BV-046	1	10	7	16
Virginia Canyon Mine	2	1	6	6
Lucania Mine	1	<1	6	6

\*Spiked with 5 µg of arsenic per litre.

Table 4. Sample-site separation compared to laboratory separation

Sample site	Sample site		Laboratory		Total, µg/l.
	As(III), µg/l.	As(V), µg/l.	As(III), µg/l.	As(V), µg/l.	
Rockford Tunnel	3	<1	3	<1	3
Virginia Canyon Mine	2	1	2	1	3
Idaho Spring Mine	14	<1	15	<1	13
Lucania Mine	1	<1	<1	<1	1

The unused sample was brought back to the laboratory for further study by the same procedure.

Arsenic was determined in each portion of sample by graphite-furnace atomic-absorption spectrophotometry. An equal volume of 200-mg/l. nickel solution was added to the volume of sample in the graphite furnace (generally, 25 µl). The instrumental parameters are shown in Table 1. A calibration graph was constructed by analysing standards in the same way. Total arsenic for each sample was determined directly in the same manner, with an appropriate aliquot of the original sample.

## RESULTS

Two ground-water samples and two laboratory standards with measurable concentrations of both As(III) and As(V) were introduced into the columns described. The effluent was collected in twenty successive 1-ml portions, each of which was analysed for arsenic. Plots of absorption signals (peak-heights) vs. eluate volume showed a definite chromatographic separation of two arsenic species (Fig. 1). All of the As(III) is eluted in the first 10 ml of effluent, there being little or no retention of As(III) by the acetate form of the resin. As the eluent (hydrochloric acid) passes through the column, the resin is converted from the acetate form into the chloride form, which has little or no affinity for As(V) in the acidic medium, and the arsenic(V) is eluted in the 13th and 14th 1-ml fractions. The change from acetate form to chloride form is evidenced by an accompanying slight colour change proceeding down the column. As(III) and As(V) in 13 ground-water samples from Utah and 5 acid mine waters from Colorado, that had been filtered and acidified at the sample site, were separated in the laboratory. The results are shown in Table 2.

Recovery studies involved adding As(III) and As(V) (each at the 5-µg/l. level) to each of six samples. The results in Table 3 for the spiked and original samples show that the recoveries of As(III) and As(V) ranged from 80 to 120%, respectively, which is satisfactory at this level. That all of the

Table 5. Mean and standard deviation (S) for six separations of two samples

M002		BV012	
As(III), µg/l.	As(V), µg/l.	As(III), µg/l.	As(V), µg/l.
24	7	10	6
24	6	8	7
22	8	8	7
23	8	9	7
25	6	9	6
21	7	8	6
Mean = 23.3	7.0	8.7	6.5
S = 1.4	0.9	0.8	0.6

arsenic is recovered can also be seen from the data in Table 2.

Separations of the arsenic species in some acid mine waters collected in the front range area of Colorado were done at the sample site and later in the laboratory. The values shown in Table 4 show satisfactory agreement between the two sets of results.

Two samples (M-002 and BV-012) were analysed six times each. The values, means and standard deviations are listed in Table 5.

A separation in the field takes about 15 min. In the laboratory, several columns can be used simultaneously for analysis of a number of samples. The columns are inexpensive and can be used several times before the resin must be replaced.

## REFERENCES

1. J. A. Cherry, A. U. Shaikh, D. E. Tallman and R. V. Nicholson, *J. Hydrol.*, 1979, 43, 373.
2. J. Aggett and A. C. Aspell, *Analyst*, 1976, 101, 341.
3. A. U. Shaikh and D. E. Tallman, *Anal. Chem. Acta*, 1978, 98, 251.
4. C. Venghou and H. Agemian, *Analyst*, 1980, 105, 737.
5. S. Nakashima, *ibid.*, 1979, 104, 172.
6. P. T. Henry and T. M. Thorpe, *Anal. Chem.*, 1980, 52, 80.
7. G. E. Peery and J. A. Ford, *Talanta*, 1981, 28, 935.
8. K. C. Tam, *Env. Sci. Technol.*, 1974, 8, 734.

BOD  
(Biochemical Oxygen Demand)

Method 405.1

Optimum Concentration Range: 10-300 mg/l  
Sensitivity: 4 mg/l  
Approximate Detection Limit: 10 mg/l  
LIMS Test Code: BOD5  
Holding Time: 2 Days to Begin Incubation

1.0 Method Summary:

The sample of waste, or an appropriate dilution, is incubated for 5 days at 20°C in the dark. The reduction in dissolved oxygen concentration during the incubation period yields a measure of the biochemical oxygen demand.

2.0 Bench Sheets:

Fill out the BOD bench sheet before beginning any analyses. Include all pertinent information such as sample size, dilution factors, dates of analysis, and sample ID. As the analysis proceeds, problems, variations, and other information are written on the bench sheet immediately. The analyst must initial and date the bench sheet when the sample run is set up and when the run is completed.

3.0 Spreadsheet:

All sample data and QC data should be entered into the BOD computer spreadsheet program within 24 hours after the analysis is completed. Calculations can be done manually or by use of the computer program. Date and initial the bench sheet when the data is entered into the spreadsheet program. When all QC data have been

entered, all calculations have been made, and the spreadsheet information has been saved to disk, the analyst will print hard copies of the related control charts, and other pertinent areas of the spreadsheet. These hard copies will be initialled, and clipped to the original bench sheet. When bench sheets are completed, the analyst will make copies for each client/sample group represented in the analytical run. The original bench sheet is put into the parameter binder with other pertinent information, for data review and for data entry. Copies are filed with client- or sample-specific files, to facilitate the final review of the final report for a client or sample group.

The analyst then reviews the data according to section 6 in the SOP manual. This review should be done within 24 hours of the analysis. When the analyst has completed the review, the data packet is placed in the parameter binder in the laboratory with the time noted on the bench sheet.

#### 4.0 Data Review Process:

After the data review process has been completed (see Section 6 of the SOP Manual), within 24 hours, it is the responsibility of the analyst to enter the data into LIMS or to have the data-entry clerk enter the data into LIMS. The person who enters the data will initial and date the bench sheet, with a time, and the binder will be returned to the laboratory.

#### 5.0 Quality Control Samples:

For BOD analyses, the following control samples are included on the bench sheet and should be run with each batch of samples:

- \* method blank (dilution water blank)
- \* QC check sample
- \* duplicate samples



Acceptance limits for these quality control samples are as follows:

- \* method blank (dilution water blank) - An unseeded dilution water blank should be used as a rough check on the quality of this water and the cleanliness of the incubation bottles. The DO uptake should not exceed 0.2 mg/l.
- \* QC check sample - The spreadsheet has an area for entering data from the QC check sample. True value is given and the % recovery is calculated. This is charted on a control chart and statistical information is generated. The recovery on the QC sample must be within  $\pm 3S$  for acceptance. When the QC recovery is outside this range, the system must be checked, a new QC sample made up, and the associated batch of samples must be re-analyzed. This must be documented on a corrective action report.
- \* duplicate samples - Generally an RPD of 20 is considered the outside limit. The spreadsheet has an area for entry of duplicate analysis data. This will be charted after each analytical run. Acceptance limits are RPD inside  $+ 3S$ .

#### 6.0 Calibration of DO meter:

- 6.1. Calibration against the Winkler method must be performed daily, and must be done prior to each set of DO measurements; results of calibration must be logged into the DO calibration log maintained close to the instrument.

6.1.1 Calibration is done on the dilution water. Initial calibration range should be between 7 mg/L and 9 mg/L. If the value is too low, dilution water should be aerated; if too high, a new water source should be obtained.

6.1.2 Taking meter reading:

- a. Fill 2 BOD bottles with dilution water. Be careful not to agitate or aerate the water as the bottles are filled. Fill from the bottom to the top using a glass tube or rod.
- b. Cap both bottles immediately.
- c. Insert probe into Bottle 1; turn agitator to ON; allow to agitate for 3 minutes.
- d. Read meter in mg/L. Record reading in DO logbook.
- e. On Bottle 2, perform the modified Winkler. See Attachment A for this procedure.
- f. With probe in Bottle 1, adjust the meter reading to agree with the results in mg/L O<sub>2</sub> obtained from the Winkler procedure.
- g. Do not turn off the DO meter between the calibration and other readings to be made on the same day.

6.2. Reagents:

- a) manganous sulfate solution: Dissolve 480 g manganous sulfate ( $\text{MnSO}_4 \cdot 4\text{H}_2\text{O}$ ) in distilled water and dilute to 1 L.
- b) Alkaline iodide-azide solution: Dissolve 500 g of NaOH, or 700 g of KOH and 135 g NaI, or 150 g of KI in distilled water and dilute to 1 L. To this solution, add 10 g of  $\text{NaN}_3$  (sodium azide) dissolved in 40 mL distilled water.
- c) concentrated sulfuric acid
- d) starch solution: available commercially.
- e) potassium fluoride solution: Dissolve 40 g  $\text{KF} \cdot 2\text{H}_2\text{O}$  in distilled water and dilute to 100 mL.
- f) sodium thiosulfate, stock solution, 0.75 N: Dissolve 186.15 g  $\text{Na}_2\text{S}_2\text{O}_3 \cdot 5\text{H}_2\text{O}$  in boiled and cooled distilled water and dilute to 1 L. Preserve by adding 5 mL chloroform.
- g) sodium thiosulfate standard titrant, 0.0375N: Prepare by diluting 50.0 mL of stock solution to 1 L. Preserve by adding 5 mL chloroform. Standard sodium thiosulfate, exactly 0.0375N is equivalent to 0.300 mg of DO per 1.00 mL. Standardize with 0.0375 N potassium biiodate.
- h) potassium biiodate, 0.0375 N: For stock solution dissolve 4.873 g of potassium biiodate, previously dried 2 hours at  $103^\circ\text{C}$  in 1000 mL distilled water. To prepare working standard, dilute 250 mL to 1000 mL for 0.0375 N.

6.3 Standardization of sodium thiosulfate:

- 6.3.1 Dissolve approximately 2 g KI in 100 to 150 mL distilled water; add 10 mL of 10%  $H_2SO_4$  followed by 20 mL standard potassium biiodate. Place in dark for 5 minutes, dilute to 300 mL, and titrate with the standard sodium thiosulfate to a pale straw color. Add 1-2 mL starch solution and continue the titration drop by drop until the blue color disappears.
- 6.3.2 Run in duplicate. Duplicate determinations should agree within 0.05 mL.
- 6.3.3 To the calibration sample, add 2 mL manganous sulfate, followed by 2 mL of the alkaline iodide-azide solution, well below the surface of the liquid. Stopper with care to exclude air bubbles; mix well by inverting the bottle several times. When the precipitate settles, leaving a clear supernatant, shake again. When settling has produced at least 200 mL clear supernatant, carefully remove the stopper, and immediately add 2 mL concentrated  $H_2SO_4$ , allowing the acid to run down the neck of the bottle, re-stopper, and mix by gentle inversion until the iodine is uniformly distributed throughout the bottle. Complete the analysis within 45 minutes.
- 6.3.4 Transfer 203 mL of the contents to a wide-mouth flask. Titrate with 0.025 N sodium thiosulfate to a pale straw color. Add 1-2 mL of starch solution and continue to titrate to the first disappearance of the blue color.

6.3.5 Calculation:

- a. Each ml of 0.025 N sodium thiosulfate is equivalent to 1 mg DO.
- b. This procedure should be compared with the results using the DO meter. All results should be recorded in the DO calibration log kept close to the instrument.

7.0 BOD Analysis:

7.1 Apparatus:

- a. incubation bottles: 250mL-300mL with ground-glass stoppers.

Clean bottles with detergent, rinse thoroughly and drain before use.

Use a water-seal. Invert bottles in a water bath or add water to the flared mouth of the BOD bottle. Place a paper or plastic cup over the flared mouth to reduce evaporation of the seal during incubation.

- b. air incubator or water bath: thermostatically controlled at  $20^{\circ} \pm 1^{\circ}\text{C}$ . All light must be excluded during incubation to prevent photosynthetic production of DO.

7.2 Reagents:

- a. phosphate buffer solution

Dissolve 8.5 g  $\text{KH}_2\text{PO}_4$ , 21.75 g  $\text{K}_2\text{HPO}_4$ , 33.4 g  $\text{Na}_2\text{HPO}_4 \cdot 7\text{H}_2\text{O}$ , and 1.7 g  $\text{NH}_4\text{Cl}$  in about 500 mL distilled water and dilute to

1 L. Check the pH using a pH meter which has been properly calibrated. The pH should be 7.2 without further adjustment.

Discard any BOD reagent which shows any sign of biological growth in the stock bottle.

**b. magnesium sulfate solution**

Dissolve 22.5 g  $\text{MgSO}_4 \cdot 7\text{H}_2\text{O}$  in distilled water and dilute to 1 L.

**c. calcium chloride solution**

Dissolve 27.5 g  $\text{CaCl}_2$  in distilled water and dilute to 1 L.

**d. ferric chloride solution**

Dissolve 0.25 g  $\text{FeCl}_3 \cdot 6\text{H}_2\text{O}$  in distilled water and dilute to 1 L.

**e. acid and alkali solutions, 1N**

$\text{H}_2\text{SO}_4$  - Add 28 mL concentrated sulfuric acid to about 500 mL distilled water. Dilute to 1 L and mix well.

$\text{NaOH}$  - Add 40 g of  $\text{NaOH}$  to about 500 mL distilled water. Dilute to 1 L and mix well.

**f. sodium sulfite solution, 0.025N**

Dissolve 1.575 g  $\text{Na}_2\text{SO}_3$  in 1 L distilled water. This solution is not stable; prepare daily.

**g. nitrification inhibitor: Available commercially**

**h. glucose-glutamic acid solution**

Dry reagent-grade glucose and reagent-grade glutamic acid at 103°C for 1 hour. Add 150 mg glucose and 150 mg glutamic acid to distilled water and dilute to 1 L. Prepare fresh immediately before use.

i. sodium thiosulfate, 0.025 N:

Dissolve 6.205 g  $\text{Na}_2\text{S}_2\text{O}_3 \cdot 5\text{H}_2\text{O}$  in distilled water. Dilute to 1 L. Standardize.

7.3 Procedure:

7.3.1 Preparation of dilution water: Place desired volume of water in a suitable bottle and add 1 mL each of the phosphate buffer on day of analysis,  $\text{MgSO}_4$ ,  $\text{CaCl}_2$ , and  $\text{FeCl}_3$  solutions per liter of water. Seed dilution water, if desired. Test dilution water and store so that water of assured quality is always on hand.

7.3.2 Dilution water check: If dilution water has not been stored for quality improvement, add sufficient seeding material to produce a DO uptake of 0.05 to 0.1 mg/L in 5 d at 20°C. Do not seed dilution water that has been stored for quality improvement. Incubate a BOD bottle full of dilution water for 5 d at 20°C. Determine initial and final DO. The DO uptake in 5 days should not be more than 0.2 mg/L, and preferably not more than 0.1 mg/L.

Before use, bring dilution water temperature to 20°C. Saturate with DO by

shaking in a partially filled bottle or by aerating with filtered air. Protect water quality by using clean glassware, tubing, and bottles.

- 7.3.3 Glucose-glutamic acid check: THIS CHECK MUST BE DONE AT LEAST ONCE A WEEK. IF THERE IS NO EPA QC CHECK SAMPLE AVAILABLE, THE SUGAR SAMPLE MUST BE RUN WITH EVERY BATCH OF BODs.

Use a mixture of 150 mg glucose/L and 150 mg glutamic acid/L as a standard "check" solution. Determine the 5-day 20°C BOD of a 2% dilution of the glucose-glutamic acid standard check solution.

If the BOD value is outside the range of  $200 \pm 37$  mg/L, reject any BOD determinations made with the seed and dilution water and seek the cause of the problem.

- 7.3.4 Seeding: Some samples do not contain a sufficient microbial population. For such wastes, seed the dilution water by adding a population of microorganisms. The preferred seed is effluent from a biological treatment system processing the waste.

Determine BOD of the seeding material as for any other sample. This is the seed control. From the value of the seed control and a knowledge of the seeding material dilution determine seed DO uptake. To determine a sample DO uptake, subtract the seed DO uptake from the total DO uptake. The DO uptake of the seeded dilution water should be between 0.6 and 1.0 mg/L.



7.3.5 Sample pretreatment:

- a. Samples containing caustic alkalinity or acidity: neutralize samples to pH 6.5 to 7.5 with  $\text{H}_2\text{SO}_4$  or NaOH. The sample should not be diluted by more than 0.5%. The pH of seeded dilution water should not be affected by the lowest sample dilution.
- b. Samples containing residual chlorine: If residual chlorine is present, dechlorinate and seed the dilution water. Destroy chlorine by adding  $\text{Na}_2\text{SO}_3$  solution.
  - 1) Determine required volume of  $\text{Na}_2\text{SO}_3$  on a 100-mL to 1000-mL portion of neutralized sample, by adding 10 mL of 1+1 acetic acid, 10 mL potassium iodide solution (10g/100mL), and titrating with 0.025N  $\text{Na}_2\text{SO}_3$  to the starch-iodine endpoint.
  - 2) Add to the neutralized sample the volume of  $\text{Na}_2\text{SO}_3$  solution determined by the above test, mix, and after 10 to 20 minutes, check sample for residual chlorine.
- c. Samples supersaturated with DO: Samples containing more than 9 mg/L DO at 20°C may be brought to saturation by bringing sample to about 20°C in a partially filled bottle while shaking or aerating with compressed air.
- d. Nitrification inhibition: If the 5-day CBOD is requested, add 3.33 mg 2-chloro-6 (trichloro methyl) pyridine to each

bottle before capping or add sufficient amounts to the dilution water to make a final concentration of 10mg/L. Note the use of nitrogen inhibition in reporting results as Carbonaceous BOD.

- 7.3.6 Dilution technique: Make several dilutions of prepared sample to obtain a DO uptake in the range of 2 mg/L after 5 d incubation. In the absence of prior knowledge, use:

0.0 - 1.0% for strong industrial wastes  
1.0 - 5.0 % for raw and settled wastewater  
5.0 - 25.0% for biologically treated effluent  
25.0 - 100% for polluted river waters

Prepare dilutions in volumetric flasks or directly in BOD bottles. Record dilution factors directly onto bench sheets as samples are diluted and prepared. A minimum of 3 dilutions are set up for each sample.

- 7.3.7 Determination of initial DO: If the sample contains materials that react rapidly with DO, determine initial DO immediately after filling BOD bottle. If rapid initial DO uptake is insignificant, the time period between preparing dilution and measuring initial DO is not critical.

- 7.3.8 Dilution water blank: Use a dilution water blank as a rough check on the quality of dilution water and BOD bottle cleanliness. With each batch of samples, incubate a bottle of unseeded dilution water. Determine initial and final DO uptake. The

DO uptake should not be more than 0.2 mg/L and preferably not more than 0.1 mg/L. If greater than 0.2 mg/l, the cause will be investigated and annotation made on the case narratives for affected samples.

7.3.9 Seed blank: With each batch of samples, incubate a bottle of seeded dilution water. Determine initial and final DO uptake.

7.3.10 Filled BOD sample bottles are covered with inverted paper cups to reduce evaporation, and placed in the BOD incubator at 20°C for 5 days. Final BOD values are determined at the end of the incubation period.

7.3.11 Using the DO probe to determine DO values:

- a. The DO meter is usually left on. After the meter has been calibrated, the samples can be read. Switch is set to DO MEASURED.
- b. Probe is placed into a beaker of distilled water and rinsed well. This is repeated after each sample reading.
- c. Probe is placed into a BOD sample bottle and the stirrer turned on. The meter is allowed to stabilize for a minimum of 3 minutes. Reading is recorded on bench sheet.

7.4 Calculation:

The bench sheets used (see example on following page) make the calculation of the DO very simple. Each column is used to record a specific value:

Column 0	= mls. of sample into BOD bottle
1	= dilution factor: 300ml divided by the mls of sample used = DF
2	= BOD bottle number
3	= initial DO uptake reading
4	= final DO uptake reading
5	= DO depletion (found by subtracting the value in column 4 from the value in column 3)
6	= % depletion (found by taking the depletion from column 5 and dividing it by the initial DO uptake from column 3. This is then multiplied by 100)
7	= BOD value (found by multiplying the DO depletion from column 5 by the dilution factor in column 1)

8.0 Reporting:

- a. BODs are reported in mg/L O<sub>2</sub> of original sample.
- b. Values below 2 mg/L are reported as < 2 mg/L O<sub>2</sub>.

CH2M HILL/MGM SOP (BOD)  
Rev. 0 1/30/89 -

## METHOD 9081

### CATION-EXCHANGE CAPACITY OF SOILS (SODIUM ACETATE)

#### 1.0 SCOPE AND APPLICATION

1.1 Method 9081 is applicable to most soils, including calcareous and noncalcareous soils. The method of cation-exchange capacity by summation (Chapman, 1965, p. 900; see Paragraph 10.1) should be employed for distinctly acid soils.

#### 2.0 SUMMARY OF METHOD

2.1 The soil sample is mixed with an excess of sodium acetate solution, resulting in an exchange of the added sodium cations for the matrix cations. Subsequently, the sample is washed with isopropyl alcohol. An ammonium acetate solution is then added, which replaces the adsorbed sodium with ammonium. The concentration of displaced sodium is then determined by atomic absorption, emission spectroscopy, or an equivalent means.

#### 3.0 INTERFERENCES

3.1 Interferences can occur during analysis of the extract for sodium content. Thoroughly investigate the chosen analytical method for potential interferences.

#### 4.0 APPARATUS AND MATERIALS

4.1 Centrifuge tube and stopper: 50-mL, round-bottom, narrow neck.

4.2 Mechanical shaker.

4.3 Volumetric flask: 100-mL.

#### 5.0 REAGENTS

5.1 Sodium acetate (NaOAc), 1.0 N: Dissolve 136 g of  $\text{NaC}_2\text{H}_3\text{O}_2 \cdot 3\text{H}_2\text{O}$  in water and dilute it to 1,000 mL. The pH of this solution should be 8.2. If needed, add a few drops of acetic acid or NaOH solution to bring the reaction of the solution to pH 8.2.

5.2 Ammonium acetate ( $\text{NH}_4\text{OAc}$ ), 1 N: Dilute 114 mL of glacial acetic acid (99.5%) with water to a volume of approximately 1 liter. Then add 138 mL of concentrated ammonium hydroxide ( $\text{NH}_4\text{OH}$ ) and add water to obtain a volume of about 1,980 mL. Check the pH of the resulting solution, add more  $\text{NH}_4\text{OH}$ , as needed, to obtain a pH of 7, and dilute the solution to a volume of 2 liters with water.

### 5.3 Isopropyl alcohol: 99%.

## 6.0 SAMPLE COLLECTION, PRESERVATION, AND HANDLING

6.1 All samples must be collected using a sampling plan that addresses the considerations discussed in Chapter Nine of this manual.

## 7.0 PROCEDURE

7.1 Weigh 4 g of medium- or fine-textured soil or 6 g of coarse-textured soil and transfer the sample to a 50-mL, round-bottom, narrow-neck centrifuge tube. (A fine soil has >50% of the particles <0.074 mm, medium soil has >50% >0.425 mm, while a coarse soil has more than 50% of its particles >2 mm.

7.2 Add 33 mL of 1.0 N NaOAc solution, stopper the tube, shake it in a mechanical shaker for 5 min, and centrifuge it until the supernatant liquid is clear.

7.3 Decant the liquid, and repeat Paragraph 7.2 three more times.

7.4 Add 33 mL of 99% isopropyl alcohol, stopper the tube, shake it in a mechanical shaker for 5 min, and centrifuge it until the supernatant liquid is clear.

7.5 Repeat the procedure described in Paragraph 7.4 two more times.

7.6 Add 33 mL of  $\text{NH}_4\text{OAc}$  solution, stopper the tube, shake it in a mechanical shaker for 5 min, and centrifuge it until the supernatant liquid is clear. Decant the washing into a 100-mL volumetric flask.

7.7 Repeat the procedure described in Paragraph 7.6 two more times.

7.8 Dilute the combined washing to the 100-mL mark with ammonium acetate solution and determine the sodium concentration by atomic absorption, emission spectroscopy, or an equivalent method.

## 8.0 QUALITY CONTROL

8.1 All quality control data should be maintained and available for easy reference or inspection.

8.2 Employ a minimum of one blank per sample batch to determine if contamination or any memory effects are occurring.

8.3 Materials of known cation-exchange capacity must be routinely analyzed.

## 9.0 METHOD PERFORMANCE


9.1 No data provided.

## 10.0 REFERENCES

10.1 This method is based on Chapman, H.D., "Cation-exchange Capacity," pp. 891-900, in C.A. Black (ed.), Method of Soil Analysis, Part 2: Chemical and Microbiological Properties, Am. Soc. Agron., Madison, Wisconsin (1965).



METHOD 9081  
CATION-EXCHANGE CAPACITY OF SOILS (SODIUM ACETATE)



## **CHLORIDE**

Method 407 B (Titration, Mercuric Nitrate)

Optimum Concentration Range:  
Sensitivity:  
Approximate Detection Limit:  
LIMS Test Code: CL-  
Holding Time: 28 Days

### **1.0 Method Summary:**

An acidified sample is titrated with mercuric nitrate in the presence of mixed diphenylcarbazone-bromophenol blue indicator. The end point of the titration is the formation of the blue-violet mercury diphenylcarbazone complex.

### **2.0 Bench Sheets:**

Fill out the CHLORIDE bench sheet before beginning any analyses. Include all pertinent information such as sample size, dilution factors, dates of analysis, and sample ID. As the analysis proceeds, problems, titration values, and other information are written on the bench sheet immediately. The analyst must initial and date the bench sheet when the sample run is completed.

### **3.0 Spreadsheets:**

All sample data and QC data should be entered into the CHLORIDE computer spreadsheet program within 24 hours after the analysis is completed. All calculations, whether manual or by computer, must be completed within 24 hours after analysis is completed as well. Date and initial the bench sheet when the data is entered into the spreadsheet program. Results will be copied onto the bench sheets where appropriate, to facilitate entry of data into LIMS. When bench sheets are completed, a copy is made for each sample group or client represented in the analytical run. Client/sample names are highlighted. The original bench sheet is placed into the parameter binder with other information. Copies for each client are included with the client- or

sample-specific file, to facilitate the final review of a specific client's samples before the report is issued to the client.

When all sample and QC data have been entered, all calculations have been made, and the spreadsheet information has been saved to disk, the analyst will print hard copies of the related analytical data, control charts, and other pertinent areas of the spreadsheet. These hard copies will be intitalled, and clipped to the original bench sheet. The analyst will review the data according to Section 6 in the SOP manual. This review should be done within 24 hours of the analysis. When the analyst has completed the review, the data packet is placed into the parameter binder in the laboratory with the time noted on the bench sheet.

#### **4.0 Data Review Process:**

After the data review process has been completed (see Section 6 of the SOP manual), within 24 hours it is the responsibility of the analyst to enter the data into LIMS or to have a data-entry clerk enter the data into LIMS. The person who enters the data will initial and date the bench sheet with a time, and the binder will be returned to the laboratory.

#### **5.0 Quality Control Samples:**

For CHLORIDE analyses, the following control samples are included on the bench sheet and should be run with each batch of samples:

- \* method blank
- \* QC check sample or method blank spike
- \* duplicate samples
- \* matrix spike/matrix spike duplicate (if required by a specific contract)

Acceptance limits for these quality control samples are as follows:

- \* method blank - if the analyte of interest is detected in the method blank, any sample in which the analyte is present at < 10X the level detected in the blank must be re-analyzed. The

spreadsheet has a section for entering blank result data.

- \* QC check sample - The spreadsheet has an area for entering data from the QC check sample. True value is given and the % recovery is calculated. This is charted on a control chart and statistical information is generated. The recovery on the QC sample must be within  $\pm 3S$  for acceptance. When the QC recovery is outside this range, the system must be checked, a new QC sample made up, and the associated batch of samples must be re-analyzed.
- \* duplicate samples - Generally an RPD of 20 is considered the outside limit. The spreadsheet has an area for entry of duplicate analysis data. This will be charted after each analytical run. Acceptance limits are RPD inside  $\pm 3S$ .

## **6.0 Analytical Procedure:**

### **6.1 Apparatus:**

- a. Erlenmeyer flask, 250-ml
- b. Microburet, 5-ml with 0.01-mL graduations

### **6.2 Reagents:**

- a. Standard sodium chloride, 0.0141N

Dissolve 824.0 mg NaCl (dried at 140°C) in distilled water and dilute to 1000 mL. (1.00 ml = 500 ug Cl<sup>-</sup>)

- b. Nitric acid, HNO<sub>3</sub>, 0.1 N

Add 6.4 mL of conc. HNO<sub>3</sub> to 900 mL distilled water in a 1000-mL volumetric flask. Mix thoroughly. Add water to volume.

c. Sodium hydroxide, NaOH, 0.1 N

Add 4.0 g of NaOH to 900 mL distilled water in a 1000-mL volumetric flask. Mix thoroughly. Add water to volume.

d. Reagents for chloride concentrations <100 mg/L

1) Indicator-acidifier reagent

- a) Dissolve, in the order named, 250 mg s-diphenylcarbazone, 4.0 ml conc. HNO<sub>3</sub>, and 30 mg xylene cyanol PF in 100 mL 95% ethyl alcohol or isopropyl alcohol. Store in a dark bottle in a refrigerator.
- b) pH control is critical. Adjust pH of highly acid or alkaline samples to 2.5 0.1 with 0.1N HNO<sub>3</sub> or NaOH, not with sodium carbonate.

2) Standard mercuric nitrate titrant

- a) Available commercially.  
(1 mL = 5 mg Cl<sup>-</sup>)  
  
Store away from light in a dark bottle.
- b) Standardization:  
  
Use a 100-mL or smaller portion. Add 1.0 mL indicator-acidifier reagent. Titrate with 0.0141N Hg(NO<sub>3</sub>)<sub>2</sub> titrant to a definite purple endpoint.

e. Reagents for chloride concentrations >100 mg/L

1) Mixed indicator reagent

Dissolve 0.50 g diphenylcarbazone

powder and 0.05 g bromphenol blue powder in 75 mL 95% ethyl or isopropyl alcohol and dilute to 100 mL with the same alcohol.

2) Strong standard mercuric nitrate titrant

Dilute from commercial stock.  
(1.00 mL = 5.00 mg  $\text{Cl}^-$ )

6.3 Procedure:

a. Titration of chloride concentrations less than 100 mg/L: Use a 100-mL sample or smaller portion so that the chloride content is less than 10 mg.

- 1) Add 1.0 mL indicator-acidifier reagent. (The color of the solution should be green-blue at this point. A light green indicates pH <2; a pure blue indicates pH >3.8.) For most potable waters, the pH after this addition will be 2.4-2.6. For highly alkaline or acid waters, adjust pH to about 8 before adding indicator-acidifier reagent.
- 2) Titrate with 0.0141N  $\text{Hg}(\text{NO}_3)_2$  titrant to a definite purple end point. The solution turns from green-blue to blue a few drops before the end point.
- 3) Determine the blank by titrating 100 mL distilled water containing 10 mg  $\text{NaHCO}_3$ .

b. Titration of chloride concentrations greater than 100 mg/L: Use a sample portion (5 to 50 mL) requiring less than 5 mL to reach the end point. Measure into a 150-mL beaker.

- 1) Add approximately 0.5 mL mixed indicator reagent and mix well. The color should be purple.

- 2) Add 0.1N HNO<sub>3</sub> dropwise until the color just turns yellow.
- 3) Titrate with 0.141N Hg(NO<sub>3</sub>)<sub>2</sub> titrant to first permanent dark purple.
- 4) Titrate a distilled water blank using the same procedure.

**6.4 Calculation:**

$$1) \quad \text{mg Cl/L} = \frac{(A - B) \times N \times 35.450}{\text{mL sample}}$$

where:

A = mL titration for sample

B = mL titration for blank

N = normality of Hg(NO<sub>3</sub>)<sub>2</sub>

$$2) \quad \text{mg NaCl/L} = (\text{mg Cl/L}) \times 1.65$$

**7.0 Reporting:**

- a. Chloride is reported in units of mg Cl/L.
- b. Values lower than 5 mg/L are reported as <5mg/L.

**8.0 Notes:**

- 8.1. Increasing the strength of the titrant and modifying the indicator mixtures extend the range of measurable chloride concentrations.
- 8.2. Bromide and iodide are titrated with Hg(NO<sub>3</sub>)<sub>2</sub> in the same manner as chloride. Chromate, ferric, and sulfite ions interfere when present in excess of 10 mg/L.
- 8.3. The indicator-acidifier reagent is not stable indefinitely. Deterioration causes a slow end

point and high results. Reagent a) contains sufficient  $\text{HNO}_3$  to neutralize a total alkalinity of 150 mg as  $\text{CaCO}_3$ /L to the proper pH in a 100-mL sample. The amount of  $\text{HNO}_3$  can be adjusted to accomodate samples of alkalinity different from 150 mg/L.



## CHEMICAL OXYGEN DEMAND

### Method 410.4 (Colorimetric)

Linear Concentration Range: 20 - 900 mg/l

Approximate Detection Limit: 20 mg/l

LIMS Test Code: COD4

Holding Time: 28 days

#### 1.0 Scope and Application

1.1 This method covers the determination of COD in surface waters, domestic and industrial wastes.

1.2 The applicable range is 20 to 900 mg/l.

#### 2.0 Summary Method

2.1 Sample, blanks and standards in sealed tubes are heated in an over or block-digester in the presence of dichromate at 150° C. After two hours, the tubes are removed from the over or digester, cooled and measured spectrophotometrically at 600 nm.

#### 3.0 Sample Handling and Preservation

3.1 Collect the samples in glass bottles if possible. Use of plastic containers is permissible if it is known that no oraganic contaminants are present in the containers.

3.2 Samples should be preserved with sulfuric acid to a pH < 2 and maintained at 4° C until analysis.

#### 4.0 Interferences

4.1 Chlorides are quantitatively oxidized by dichromate and represent a positive interference. Mercuric sulfate is added to the digestion tubes to complex the chlorides.

#### 5.0 Apparatus

5.1 Drying oven or block digesgor, 500° C

5.2 Corning culture tubes, 16 x 100 mm or 25 x 150 mm with Teflon lined screw cap

5.3 Spectrophotometer

5.4 Muffle furnace, 500° C

5.5 Commercially available twist micro EPA approved digestion tubes (available from BioScience Inc., 174-318 Standard COD Vials).

## 6.0 Reagents

6.1 Digestion solution: Add 10.2 K<sub>2</sub>Cr<sub>2</sub>O<sub>7</sub>, 167 ml conc. H<sub>2</sub>SO<sub>4</sub> and 33.3 g HgSO<sub>4</sub> to 500 ml of distilled water, cool and dilute to 1 liter.

6.2 Catalyst solution: Add 22 g Ag<sub>2</sub>SO<sub>4</sub> to a 4.09kg bottle of conc. H<sub>2</sub>SO<sub>4</sub>. Stir until dissolved.

6.3 Sampler wash solution: Add 500 ml of conc H<sub>2</sub>SO<sub>4</sub> to 500 ml of distilled water.

6.4 Stock potassium acid phthalate: Dissolve 0.850 g in 800 ml of distilled water and dilute to 1 liter. 1 ml = 1 mg COD. Potassium acid phthalate must be crushed and dried for 72 hours at 120° C and desiccated before weighing.

6.4.1 Prepare a series of standard solutions that cover the expected sample concentrations by diluting appropriate volumes of the stock standard.

### Standards

ml of Stock KHP/100 ml	Conc of mg/l COD
2	20
5	50
10	100
25	250
40	400
60	600
90	900

## 7.0 Procedure

7.1 Wash all culture tubes and screw caps with 20% H<sub>2</sub>SO<sub>4</sub> before their first use to prevent contamination. Trace contamination may be removed from the tubes by igniting them in a muffle oven at 500° C for 1 hour.

7.2 Lab prepared Vials.

7.2.1 Add 2.5 ml of sample to the 16 x 100 mm tubes.

7.2.2 Add 1.5 ml of digestion solution (6.1) and mix.

- 7.2.3 Add 3.5 ml of catalyst solution (6.2) carefully down the side of the culture tubes.
- 7.2.4 Cap tightly and shake to mix layers
- 7.2.5 Process standards and blanks exactly as the samples.
- 7.2.6 Place in over or block digester at 150° C for two hours.
- 7.2.7 Cool, and place standards in sampler in order of decreasing concentration. Completely filling sampler tray with unknown samples.
- 7.2.8 Measure color intensity on Spectrophotometer at 600 nm.
- 7.3 Commercially Available Micro Vials
  - 7.3.1 Add 2.5 ml of sample to prepared vials.
  - 7.3.2 Replace cap firmly and shake to mix layers.
  - 7.3.3 Place in oven or block digester at 150° C for two hours.
  - 7.3.4 Cool
  - 7.3.5 Place layer of digested sample or standards in a standard 10 mm Quarts cell\*.
  - 7.3.6 Measure color intensity on spectrophotometer at 600 nm.

\* Care should be taken not to get the mercuric sulfate in the UV cell.

- 8.0 Bench Sheets: Fill out the COD bench sheet before beginning any analyses. Include all pertinent information such as sample size, dilution factors, dates of analysis, and sample ID. As the analysis proceeds, problems, variations, and other information are written on the bench sheet immediately. The analyst must initial and date the bench sheet when the sample run is set up and when the run is completed.
- 9.0 Spreadsheet: All sample data and QC data should be entered into the COD computer spreadsheet program within 24 hours after the analysis is completed. Calculations can be done manually or by use of the computer program. Date and initial the bench sheet when the data is entered into the spreadsheet program. When all QC data have been entered, all calculations have been made, and the spreadsheet information has been saved to disk, the analyst will print hard copies of the related control charts, and other pertinent areas of the spreadsheet. These hard copies will be initialled, and clipped to the original bench sheet. When bench sheets are

completed, the analyst will make copies for each client/sample group represented in the analytical run. The original bench sheet is put into the parameter binder with other pertinent information, for data review and for data entry. Copies are filed with client-or sample-specific files, to facilitate the final review of the final report for a client or sample group.

The analyst then reviews the data according to section 6 in the SOP manual. This review should be done within 24 hours of the analysis. When the analyst has completed the review, the data package is placed in the parameter binder in the laboratory with the time noted on the bench sheet.

10.0 Data Review Process: After the data review process has been completed (see Section 6 of the SOP Manual), within 24 hours, it is the responsibility of the analyst to enter the data into LIMS or to have the data-entry clerk enter the data into LIMS. The person who enters the data will initial and date the bench sheet, with a time, and the binder will be returned to the laboratory.

11.0 Quality Control Samples: For COD analyses, the following control samples are included on the bench sheets and should be run with each batch of samples:

- method blank (water blank)
- QC check sample
- duplicate samples

Acceptance limits for these quality control samples are as follows:

- method blank (water blank) - must be digested and analyzed with each digestion batch and have a result of  $< 20$  mg/l.
- QC check sample - The spreadsheet has an area for entering data from the QC check sample. True value is given and the % recovery is calculated. This is charted on a control chart and statistical information is generated. The recovery on the QC sample must be within  $\pm 3S$  for acceptance. When the QC recovery is outside this range, the system must be checked, a new QC sample made up, and the associated batch of samples must be re-analyzed. This must be documented on a corrective action report. QC sample must be digested and analyzed with each digestion batch. QC sample must be an independent check sample such as EPA Demand PE or a Demand PE from Analytical Products Group, Inc.
- Duplicate samples - Generally an RPD of 20 is considered the outside limit. The spreadsheet has an area for entry of

duplicate analysis data. This will be charted after each analytical run. Acceptance limits are RPD inside + 3S.

## **pH**

### Method 150.1 (Electrometric)

Optimum Concentration Range:  
Sensitivity:  
Approximate Detection Limit:  
LIMS Test Code: PH  
Holding Time: 0 (Must be run as soon as it reaches lab)

#### **1.0 Method Summary:**

The pH of a sample is determined electrometrically using either a glass electrode in combination with a reference potential or a combination electrode.

#### **2.0 Bench Sheets:**

Fill out the pH bench sheet before beginning any analyses. Include all pertinent information such as sample size, dilution factors, dates of analysis, and sample ID. As the analysis proceeds, problems, observed values, and other information are written on the bench sheet immediately. The analyst must initial and date the bench sheet when the sample run is completed.

#### **3.0 Spreadsheet:**

All sample data and QC data should be entered into the pH computer spreadsheet program within 24 hours after the analysis is completed. Date and initial the bench sheet when the data is entered into the spreadsheet program. When all QC data have been entered, all calculations have been made, and the spreadsheet information has been saved to disk, the analyst will print hard copies of the related control charts, and other pertinent areas of the spreadsheet. These hard copies will be initialled, and clipped to the original bench sheet.

When bench sheets are completed, the analyst will make copies for each client/sample group represented in the analytical run. The original bench sheet is put into the parameter binder with other pertinent information,

for data review and for data entry. Copies are filed with client- or sample-specific files, to facilitate the final review of the final report for a client or sample group.

The analyst then reviews the data according to section 6 in the SOP manual. This review should be done within 24 hours of the analysis. When the analyst has completed the review, the data packet is placed in the parameter binder in the laboratory with the time noted on the bench sheet.

#### **4.0 Data Review Process:**

After the data review process has been completed (see Section 6 of the SOP Manual), within 24 hours, it is the responsibility of the analyst to enter the data into LIMS or to have the data-entry clerk enter the data into LIMS. The person who enters the data will initial and date the bench sheet, with a time, and the binder will be returned to the laboratory.

#### **5.0 Quality Control Samples:**

For pH analyses, the following control samples are included on the bench sheet and should be run with each batch of samples:

- \* QC check sample

Acceptance limits for these quality control samples are as follows:

- \* QC check sample - The spreadsheet has an area for entering data from the QC check sample. True value is given and the % recovery is calculated. This is charted on a control chart and statistical information is generated.

The QC check sample can be either an EPA-prepared sample (WP or WS) or an independent commercial buffer of a pH different from those of the buffers used in calibrating and standardizing the pH meter.

**6.0 Analytical Procedure:**

**6.1 Apparatus:**

- a. pH meter - laboratory or field model.
- b. Glass electrode.
- c. Reference electrode - calomel, silver-silver chloride, or other reference electrode of constant potential.
- d. Magnetic stirrer and Teflon-coated stirring bar.
- e. Thermometer or temperature sensor for automatic compensation.

**6.2 Reagents:**

- a. Standard buffers are available commercially.

**6.3 Procedure:**

- a. Allow sample to reach room temperature.
- b. Standardize and calibrate the pH meter. Standardize with pH 7 buffer; adjust slope with pH 4 buffer. Then read pH 10 buffer. Record all readings in the pH calibration log.
- c. Place the sample in a clean glass beaker of adequate size for the electrode and the stirring bar.
- d. Check the temperature.
- e. After rinsing and gently wiping the electrodes, immerse them into the sample beaker and stir at a constant rate.
- f. Note the pH reading and the temperature.

**7.0 Reporting:**

- 7.1 Report pH in units to the nearest 0.1.



b. Report temperature to the nearest degree Centigrade.

**8.0 Notes:**

- 8.1 Samples should be analyzed as soon as possible, preferably in the field at the time of sampling.
- 8.2 Sample containers should be filled completely and kept sealed prior to analysis.
- 8.3 Coatings of oily material or particulate material can impair electrode response. Remove by gentle wiping or detergent washing.
- 8.4 Temperature error is sample dependent and cannot be controlled. It should therefore be noted by reporting both the pH and the temperature at the time of analysis.
- 8.5 Check to see that the electrode is clean, free of crystallized material, and completely filled with solution.

## ***SULFATE***

Method 375.4 (Turbidimetric)

Optimum Concentration Range:  
Sensitivity:  
Approximate Detection Limit:  
LIMS Test Code: SO4  
Holding Time: 28 Days

### **1.0 Method Summary:**

Sulfate ion is converted to a barium sulfate suspension under controlled conditions. The resulting turbidity is determined by a spectrophotometer or filter photometer and compared to a curve prepared from standard sulfate solutions.

### **2.0 Bench Sheets:**

Fill out the SULFATE bench sheet before beginning any analyses. Include all pertinent information such as sample size, dilution factors, dates of analysis, and sample ID. As the analysis proceeds, problems, instrument readings, variations, and other information are written on the bench sheet immediately. The analyst must initial and date the bench sheet when the sample run is set up and when the run is completed.

### **3.0 Spreadsheet:**

All sample data and QC data should be entered into the SULFATE computer spreadsheet program within 24 hours after the analysis is completed. Calculations can be done manually or by use of the computer program. Date and initial the bench sheet when the data is entered into the spreadsheet program.

When all QC data have been entered, all calculations have been made, and the spreadsheet information has been saved to disk, the analyst will print hard copies of the related control charts, and other pertinent areas of the spreadsheet. These hard copies will be initialed, and clipped to the original bench sheet. When bench sheets are completed, the analyst will make

copies for each client/sample group represented in the analytical run. The original bench sheet is put into the parameter binder with other pertinent information, for data review and for data entry. Copies are filed with client- or sample-specific files, to facilitate the final review of the final report for a client or sample group.

The analyst then reviews the data according to section 6 in the SOP manual. This review should be done within 24 hours of the analysis. When the analyst has completed the review, the data packet is placed in the parameter binder in the laboratory with the time noted on the bench sheet.

#### **4.0 Data Review Process:**

After the data review process has been completed (see Section 6 of the SOP Manual), within 24 hours, it is the responsibility of the analyst to enter the data into LIMS or to have the data-entry clerk enter the data into LIMS. The person who enters the data will initial and date the bench sheet, with a time, and the binder will be returned to the laboratory.

#### **5.0 Quality Control Samples:**

For SULFATE analyses, the following control samples are included on the bench sheet and should be run with each batch of samples:

- \* method blank
- \* QC check sample
- \* duplicate samples

Acceptance limits for these quality control samples are as follows:

- \* method blank - used to zero the instrument
- \* QC check sample - The spreadsheet has an area for entering data from the QC check sample. True value is given and the % recovery is calculated. This is charted on a control chart and statistical information is generated. The recovery on the QC sample must be within  $\pm 3S$  for acceptance. When the QC recovery is

outside this range, the system must be checked, a new QC sample made up, and the associated batch of samples must be re-analyzed. This must be documented on a corrective action report.

- \* duplicate samples - Generally an RPD of 20 is considered the outside limit. The spreadsheet has an area for entry of duplicate analysis data. This will be charted after each analytical run. Acceptance limits are RPD inside + 3S.

## **6.0 Analytical Procedure:**

### **6.1 Apparatus:**

- a. Magnetic stirrer, variable speed so it can be held constant just below splashing. Use identical size and shape stirring bars.
- b. Stopwatch or accurate timer.
- c. Measuring spoon, capacity 0.2 to 0.3 mL.

### **6.2 Reagents:**

- a. conditioning reagent: Place 30 mL concentrated HCl, 300 mL distilled water, 100 mL 95% ethanol or isopropanol and 75 g NaCl in solution in a container. Add 50 mL glycerol and mix.
- b. barium chloride, BaCl<sub>2</sub>, crystals, 20 to 30 mesh
- c. sodium carbonate solution, approximately 0.05 N: Dry 3 to 5 g primary standard Na<sub>2</sub>CO<sub>3</sub> at 250°C for 4 hours and cool in a desiccator. Weigh 2.5 g (to the nearest mg), transfer to a 1 L volumetric flask, and fill to the mark with distilled water.
- d. std sulfate solution (1.00 mL = 100 ug SO<sub>4</sub>): Dissolve 147.9 mg anhydrous Na<sub>2</sub>SO<sub>4</sub> in distilled water. Dilute to 1 L.

**6.3 Procedure:**

**6.3.1 Formation of barium sulfate turbidity:**

- 1) Read all samples prior to addition of barium chloride, in order to correct for sample turbidity.
- 2) Place 100 mL sample or a suitable portion diluted to 100 mL into a 250-mL erlenmeyer flask.
- 3) Add exactly 5.0 mL conditioning reagent.
- 4) Mix in the stirring apparatus.
- 5) While the mixture is being stirred, add a measuring spoonful of BaCl<sub>2</sub> crystals and begin timing immediately.
- 5) Stir exactly 1.0 minutes at constant speed.

**6.3.2 Measurement of barium sulfate turbidity:**

- 1) Immediately after the stirring period has ended, pour the solution into an absorbance cell.
- 2) Let stand for exactly 5 minutes.
- 3) Record the reading.

**6.3.3 Preparation of calibration curve:**

- 1) Prepare calibration curve using standard sulfate solution.
- 2) Dilute standards as follows:

<u>mL stock/100 mL</u>	<u>final conc. std</u>
0 mL	0 mg/L
1 mL	1 mg/L
5 mL	5 mg/L
10 mL	10 mg/L
25 mL	25 mg/L
40 mL	40 mg/L

- 3) Check reliability of calibration curve by running a standard with every 3 to 4 samples.

6.3.4. Correction for sample color and turbidity:

Run each sample using the procedure, without the addition of barium chloride.

6.4 Calculation:

- a. Read mg SO<sub>4</sub> from calibration curve, using the PE spreadsheet program.

$$b. \text{ mg SO}_4 / \text{L} = \frac{\text{mg SO}_4 \times 1000}{\text{mL sample}}$$

7.0 Reporting:

- a. Sulfate is reported in units of mg/L.
- b. Samples with values lower than 1 mg/L are reported in LIMS as <1.
- c. Samples with values higher than 40 mg/L must be diluted and re-analyzed.

**8.0 Notes:**

- 8.1 To obtain reliable readings, use a sample aliquot containing not more than 40 mg SO<sub>4</sub>/L.
- 8.2 Suspended matter and color interfere. Correct by running blanks from which the barium chloride has been omitted.
- 8.3 Preserve by refrigeration at 4°C.

## ***SULFIDE***

Method 376.1 (Titrimetric, Iodine)

Optimum Concentration Range:  
Sensitivity:  
Approximate Detection Limit:  
LIMS Test Code: S-  
Holding Time: 7 Days

### **1.0 Method Summary:**

Excess iodine is added to a sample which may or may not have been treated with zinc acetate to produce zinc sulfide. The iodine oxidizes the sulfide to sulfur under acidic conditions. The excess iodine is backtitrated with sodium thiosulfate or phenylarsine oxide.

### **2.0 Bench Sheets:**

Fill out the SULFIDE bench sheet before beginning any analyses. Include all pertinent information such as sample size, dilution factors, dates of analysis, and sample ID. As the analysis proceeds, problems, titration values, variations, and other information are written on the bench sheet immediately. The analyst must initial and date the bench sheet when the sample run is set up and when the run is completed.

### **3.0 Spreadsheet:**

All sample data and QC data should be entered into the SULFIDE computer spreadsheet program within 24 hours after the analysis is completed. Calculations can be done manually or by use of the computer program. Date and initial the bench sheet when the data is entered into the spreadsheet program. When all QC data have been entered, all calculations have been made, and the spreadsheet information has been saved to disk, the analyst will print hard copies of the related control charts, and other pertinent areas of the spreadsheet. These hard copies will be initialled, and clipped to the original bench sheet.



When bench sheets are completed, the analyst will make copies for each client/sample group represented in the analytical run. The original bench sheet is put into the parameter binder with other pertinent information, for data review and for data entry. Copies are filed with client- or sample-specific files, to facilitate the final review of the final report for a client or sample group.

The analyst then reviews the data according to section 6 in the SOP manual. This review should be done within 24 hours of the analysis. When the analyst has completed the review, the data packet is placed in the parameter binder in the laboratory with the time noted on the bench sheet.

#### **4.0 Data Review Process:**

After the data review process has been completed (see Section 6 of the SOP Manual), within 24 hours, it is the responsibility of the analyst to enter the data into LIMS or to have the data-entry clerk enter the data into LIMS. The person who enters the data will initial and date the bench sheet, with a time, and the binder will be returned to the laboratory.

#### **5.0 Quality Control Samples:**

For SULFIDE analyses, the following control samples are included on the bench sheet and should be run with each batch of samples:

- \* method blank
- \* QC check sample

Acceptance limits for these quality control samples are as follows:

- \* method blank - if the analyte of interest is detected in the method blank, any sample in which the analyte is present at  $< 10X$  the level detected in the blank must be re-analyzed. The spreadsheet has a section for entering blank result data.
- \* QC check sample - The spreadsheet has an area for entering data from the QC check sample.

True value is given and the % recovery is calculated. This is charted on a control chart and statistical information is generated. The recovery on the QC sample must be within  $\pm 3S$  for acceptance. When the QC recovery is outside this range, the system must be checked, a new QC sample made up, and the associated batch of samples must be re-analyzed. This must be documented on a corrective action report.

**6.0 Analytical Procedure:**

**6.1 Apparatus:**

- a. ordinary laboratory glassware

**6.2 Reagents:**

- a. Hydrochloric acid, HCl, 6 N: Place approximately 400 mL distilled water into a 1 L volumetric flask. Add 500 mL concentrated hydrochloric acid. Mix carefully. Bring to volume with distilled water.
- b. Standard sodium thiosulfate, 0.1 N: Dissolve 25 g  $\text{Na}_2\text{S}_2\text{O}_3 \cdot 5\text{H}_2\text{O}$  in 1 L freshly boiled distilled water.
- c. Sodium thiosulfate titrant, 0.025 N: Dilute standard sodium thiosulfate by placing 25 mL in a 100 mL volumetric flask. Add freshly boiled water to volume.
- d. Standard iodine solution, 0.0250 N:
  - 1) Dissolve 20 to 25 g KI in a little water in a 1 L volumetric and add 3.2 g iodine. Allow to dissolve. Dilute to 1 L and standardize against 0.0250 N sodium thiosulfate or phenylarsine oxide using a starch indicator.
  - 2) Standardization procedure: Titrate iodine solution with phenylarsine solution to a pale straw color. Add a small amount of indicator. After a

homogeneous blue color develops, continue to titrate drop by drop until the color disappears. Run in duplicate. Duplicate determinations should agree within 0.05 mL.

$$N(I_2) = \frac{\text{mL PAO} \times 0.0250}{20}$$

e. Phenylarsine oxide, 0.0250 N: commercially available.

f. Starch indicator: commercially available.

### 6.3 Procedure:

#### 6.3.1 Unprecipitated sample:

- 1) Place a known amount of standard iodine solution into a 500 mL flask. The amount should be estimated to be in excess of the amount of sulfide expected.
- 2) Add 2 mL of 6 N HCl.
- 3) If the iodine color disappears, add more iodine until the color remains. Record the total number of mL of standard iodine used in performing these steps.
- 4) Titrate with the reducing solution (0.0250 N sodium thiosulfate or 0.0250 N phenylarsine oxide solution) using a starch indicator until the blue color disappears. Record the number of mL used.

#### 6.3.2 Precipitated samples:

- 1) Add the reagents to the sample in the bottle.
- 2) Place a known amount of standard iodine solution in the bottle. The amount should be estimated to be in excess of the amount of sulfide expected.

- 3) Add 2 mL 6 N HCl.
- 4) If the iodine color disappears, add more iodine until color remains. Record the total number of mL of iodine solution used.
- 5) Titrate with reducing solution (sodium thiosulfate or PAO) using starch indicator until the blue color disappears. Record the number of mL used.

#### 6.3.3 Dewatered samples:

- 1) Return the glass fiber filter paper which contains the sample to the original bottle. Add 200 mL distilled water. Proceed with steps as above.
- 2) The calculation should be based on the volume of the original sample put through the filter.

#### 6.4 Calculation:

a. One mL of 0.0250 N standard iodine solution reacts with 0.4 mg sulfide present in the titration vessel.

b. Use the formula:

$$\text{mg/L sulfide} = \frac{400 (A-B)}{\text{mL sample}}$$

where: A = mL of 0.0250 N iodine solution

B = mL 0.0250 N reducing solution

#### 7.0 Reporting:

a. Sulfide is reported in units of mg/L.

- b. Reporting limits: Values below the level of 0.5 mg/L are reported as <0.5.

**8.0 Notes:**

- 8.1 Acid insoluble sulfides are not measured by the use of this test.
- 8.2 Reduced sulfur compounds such as sulfite, thiosulfate, and hydrosulfite, which decompose in acid, may yield erratic results.
- 8.3 Volatile iodine-consuming substances will give high results.
- 8.4 Samples must be taken with a minimum of aeration. Sulfide may be volatilized by aeration and any oxygen inadvertently added to the sample may convert the sulfide to an unmeasurable form.

***HARDNESS***  
(Total mg/L as CaCO<sub>3</sub>)

Method 130.2 (Titrimetric, EDTA)

Optimum Concentration Range:

Sensitivity:

Approximate Detection Limit:

LIMS Test Code: HARD

Holding Time: 6 Months

**1.0 Method Summary:**

Calcium and magnesium ions in the sample are sequestered upon the addition of disodium ethylenediamine tetraacetate (Na<sub>2</sub>EDTA). The end point of the reaction is detected by means of Eriochrome Black T indicator, which has a red color in the presence of calcium and magnesium and a blue color when the cations are sequestered.

**2.0 Bench Sheets:**

Fill out the HARDNESS bench sheet before beginning any analyses. Include all pertinent information such as sample size, dilution factors, dates of analysis, and sample ID. As the analysis proceeds, problems, variations, titration values, and other information are written on the bench sheet immediately. The analyst must initial and date the bench sheet when the sample run is set up and when the run is completed.

**3.0 Spreadsheet:**

All sample data and QC data should be entered into the HARDNESS computer spreadsheet program within 24 hours after the analysis is completed. Calculations can be done manually or by use of the computer program. Date and initial the bench sheet when the data is entered into the spreadsheet program. When all QC data have been entered, all calculations have been made, and the spreadsheet information has been saved to disk, the analyst will print hard copies of the related control charts, and other pertinent areas of the spreadsheet. These hard copies will be initialled, and clipped to the original bench sheet.

When bench sheets are completed, the analyst will make copies for each client/sample group represented in the analytical run. The original bench sheet is put into the parameter binder with other pertinent information, for data review and for data entry. Copies are filed with client- or sample-specific files, to facilitate the final review of the final report for a client or sample group.

The analyst then reviews the data according to section 6 in the SOP manual. This review should be done within 24 hours of the analysis. When the analyst has completed the review, the data packet is placed in the parameter binder in the laboratory with the time noted on the bench sheet.

#### **4.0 Data Review Process:**

After the data review process has been completed (see Section 6 of the SOP Manual), within 24 hours, it is the responsibility of the analyst to enter the data into LIMS or to have the data-entry clerk enter the data into LIMS. The person who enters the data will initial and date the bench sheet, with a time, and the binder will be returned to the laboratory.

#### **5.0 Quality Control Samples:**

For HARDNESS analyses, the following control samples are included on the bench sheet and should be run with each batch of samples:

- \* method blank
- \* QC check sample
- \* duplicate samples

Acceptance limits for these quality control samples are as follows:

- \* method blank - if the analyte of interest is detected in the method blank, any sample in which the analyte is present at < 10X the level detected in the blank must be re-analyzed. The spreadsheet has a section for entering blank result data.

- \* QC check sample - The spreadsheet has an area for entering data from the QC check sample. True value is given and the % recovery is calculated. This is charted on a control chart and statistical information is generated. The recovery on the QC sample must be within  $\pm 3S$  for acceptance. When the QC recovery is outside this range, the system must be checked, a new QC sample made up, and the associated batch of samples must be re-analyzed. This must be documented on a corrective action report.
- \* duplicate samples - Generally an RPD of 20 is considered the outside limit. The spreadsheet has an area for entry of duplicate analysis data. This will be charted after each analytical run. Acceptance limits are RPD inside  $\pm 3S$ .

## 6.0 Analytical Procedure:

### 6.1 Apparatus:

- a. Standard laboratory titrimetric equipment.

### 6.2 Reagents:

- a. Buffer solution

- 1) Dissolve 1.179 g disodium EDTA (analytical reagent grade) and 780 mg  $MgSO_4 \cdot 7H_2O$  (or 644 mg  $MgCl_2 \cdot 6H_2O$ ) in 50 mL distilled water. Add this solution to 250 mL volumetric flask containing 16.9 g  $NH_4Cl$  and 143 mL concentrated  $NH_4OH$  with mixing. Dilute to the mark with distilled water.
- 2) Store in a tightly stoppered plastic bottle; stable for approximately 1 month. Dispense with bulb operated pipet. Discard when 1-2 mL added to sample fails to produce a pH of 10.0 at the endpoint of titration.



3) Commercially available "odorless" buffers may also be used.

b. Indicator: Mix together 0.5 g Eriochrome Black T, and 4.5 g hydroxylamine HCl. Dilute to volume in a 100 mL volumetric flask with n-propyl alcohol.

c. Standard EDTA titrant, 0.02 N: Place 3.723 g analytical reagent grade disodium ethylenediamine tetraacetate dihydrate in a 1 L volumetric flask and dilute to the mark with distilled water. Check with standard calcium solution by titration. Store in polyethylene. Check monthly because of gradual deterioration.

1) Place 10.0 mL standard calcium solution in vessel containing about 50 mL distilled water. Add 1 mL buffer solution. Add 1-2 drops indicator or small scoop of dry indicator. Titrate slowly with continuous stirring until the last reddish tinge disappears; adding last few drops at 3-5 second intervals. At end point, the color is blue. Total titration should be 5 minutes from the time of buffer addition.

$$2) \text{ N of EDTA} = \frac{0.2}{\text{mL of EDTA}}$$

d. Standard calcium solution, 0.02 N:

1) Place 1.000 g anhydrous calcium carbonate (primary grade low in metals) in a 500 mL flask.

2) Add, a little at a time, 1+1 HCl until all the  $\text{CaCO}_3$  has been dissolved. Add 200 mL distilled water. Boil for a few minutes to expel  $\text{CO}_2$ .

3) Cool. Add a few drops of methyl red indicator and adjust to intermediate orange color by adding 3N  $\text{NH}_4\text{OH}$  or 1+1 HCl as required. Quantitatively transfer

to a 1 L volumetric flask and dilute to the mark with distilled water.

- e. Hydrochloric acid solution, 1+1: Dilute 500 mL concentrated HCl to 1000 mL with distilled water.
- f. Methyl red indicator: Dissolve 0.10 g methyl red in distilled water in a 100 mL volumetric. Dilute to the mark with distilled water.
- g. Ammonium hydroxide solution, 3 N: Dilute 210 mL of concentrated  $\text{NH}_4\text{OH}$  to 1 L with distilled water.
- h. Ammonium hydroxide solution, 1 N: Dilute 70 mL of concentrated  $\text{NH}_4\text{OH}$  to 1 L with distilled water.

### 6.3 Procedure:

#### 6.3.1 Pre-treatment:

- 1) For drinking waters, surface waters, saline waters, and dilutions thereof, no pre-treatment steps are necessary.
- 2) For most wastewaters, and highly polluted waters, the sample must be digested as given in the Atomic Absorption Methods section of the EPA methods manual.

#### 6.3.2 Titration of sample - normal to high hardness:

- 1) Sample should require <15 mL EDTA titrant and titration should be completed within 5 minutes of buffer addition.
- 2) Place 25 mL sample in titration vessel, neutralize with 1 N ammonium hydroxide and dilute to about 50 mL.
- 3) Add 1-2 mL buffer solution.
- 4) Add a small scoop of dried powder indicator formula.

- 5) Titrate slowly with continuous stirring with standard EDTA titrant until last reddish tint disappears. Solution is normally blue at end point.

6.3.3 Titration of sample - low hardness (< 5 mg/L)

- 1) Use a larger sample (100 mL)
- 2) Use proportionately larger amounts of buffer and indicator.
- 3) Use a microburet and run a blank using redistilled or deionized water.

6.4 Calculation:

$$\text{Hardness (EDTA)} = \frac{A \times N \times 50,000}{\text{mL sample}}$$

where: A = mL EDTA titrant  
N = normality of EDTA titrant

7.0 Reporting:

- a. Hardness is reported in mg CaCO<sub>3</sub>/L.
- b. Values below 4 mg/L are reported as <4.

8.0 Notes:

- 8.1 The method is suitable for all concentration ranges of hardness; however, in order to avoid large titration volumes, use a sample aliquot containing not more than 25 mg CaCO<sub>3</sub>.
- 8.2 Samples should be cooled to 4°C and preserved to pH <2 by addition of HNO<sub>3</sub>.

CH2M HILL/MGM SOP (Total Dissolved Solids)  
Rev. 0 1/30/89

**TOTAL DISSOLVED SOLIDS**  
(Residue, Filterable)

Method 160.1 (Gravimetric, Dried at 180°C)

Optimum Concentration Range: 10 mg/L - 20 000 mg/L

Sensitivity:

Approximate Detection Limit: 10 mg/L

LIMS Test Code: TDS

Holding Time: 7 Days

**1.0 Method Summary:**

A well-mixed sample is filtered through a standard glass fiber filter. The filtrate is evaporated and dried to constant weight at 180°C.

If TSS (Residue, Non-Filterable) is being determined, the filtrate from that method may be used for TDS (Residue, Filterable).

**2.0 Bench Sheets:**

Fill out the TOTAL DISSOLVED SOLIDS bench sheet before beginning any analyses. Include all pertinent information such as sample size, dilution factors, dates of analysis, and sample ID. As the analysis proceeds, problems, weights, variations, and other information are written on the bench sheet immediately. The analyst must initial and date the bench sheet when the sample run is set up and when the run is completed.

**3.0 Spreadsheet:**

All sample data and QC data should be entered into the TOTAL DISSOLVED SOLIDS computer spreadsheet program within 24 hours after the analysis is completed. Calculations can be done manually or by use of the computer program. Date and initial the bench sheet when the data is entered into the spreadsheet program. When all QC data have been entered, all calculations have been made, and the spreadsheet information has been saved to disk, the analyst will print hard copies of the related control charts, and other pertinent areas of the spreadsheet. These hard copies will be

CH2M HILL/MGM SOP (Total Dissolved Solids)  
Rev. 0 1/30/89

initialled, and clipped to the original bench sheet. When bench sheets are completed, the analyst will make copies for each client/sample group represented in the analytical run. The original bench sheet is put into the parameter binder with other pertinent information, for data review and for data entry. Copies are filed with client- or sample-specific files, to facilitate the final review of the final report for a client or sample group.

The analyst then reviews the data according to section 6 in the SOP manual. This review should be done within 24 hours of the analysis. When the analyst has completed the review, the data packet is placed in the parameter binder in the laboratory with the time noted on the bench sheet.

**4.0 Data Review Process:**

After the data review process has been completed (see Section 6 of the SOP Manual), within 24 hours, it is the responsibility of the analyst to enter the data into LIMS or to have the data-entry clerk enter the data into LIMS. The person who enters the data will initial and date the bench sheet, with a time, and the binder will be returned to the laboratory.

**5.0 Quality Control Samples:**

For TOTAL DISSOLVED SOLIDS analyses, the following control samples are included on the bench sheet and should be run with each batch of samples:

- \* method blank
- \* QC check sample
- \* duplicate samples

Acceptance limits for these quality control samples are as follows:

- \* method blank - if the analyte of interest is detected in the method blank, any sample in which the analyte is present at < 10X the level detected in the blank must be re-analyzed. The spreadsheet has a section for entering blank result data.

CH2M HILL/MGM SOP (Total Dissolved Solids)  
Rev. 0 1/30/89

- \* QC check sample - The spreadsheet has an area for entering data from the QC check sample. True value is given and the % recovery is calculated. This is charted on a control chart and statistical information is generated. The recovery on the QC sample must be within  $\pm 3S$  for acceptance. When the QC recovery is outside this range, the system must be checked, a new QC sample made up, and the associated batch of samples must be re-analyzed. This must be documented on a corrective action report.
- \* duplicate samples - Generally an RPD of 20 is considered the outside limit. The spreadsheet has an area for entry of duplicate analysis data. This will be charted after each analytical run. Acceptance limits are RPD inside  $+ 3S$ .

## 6.0 Analytical Procedure:

### 6.1 Apparatus:

- a. Glass fiber filter disks, 9.0 cm, without organic binder, Whatman type 934-AH, Gelman type A/E, or equivalent.
- b. Filter holder, membrane filter funnel, or Gooch crucible adapter.
- c. Suction flask, 500 mL
- d. Evaporating dishes, porcelain, 100 mL volume. (Vycor or platinum dishes may be substituted.)
- e. Drying oven, 180°C.
- f. Desiccator.
- g. Analytical balance capable of weighing to 0.1 mg.

CH2M HILL/MGM SOP (Total Dissolved Solids)  
Rev. 0 1/30/89

**6.2 Procedure:**

**6.2.1 Preparation of glass filter disk:**

- 1) Place the disk on the membrane filter apparatus or insert into bottom of a suitable Gooch crucible.
- 2) While a vacuum is applied, wash the disk with three successive 20 mL volumes of distilled water.
- 3) Remove all traces of water by continuing to apply vacuum after water has passed through. Discard all washings.

**6.2.2 Preparation of evaporating dishes:**

- 1) If volatile residue is also to be measured, heat the clean dish to 550°C for 1 hour in a muffle furnace. If only filterable residue is to be measured, heat the clean dish to 180°C for one hour.
- 2) Cool in desiccator and store until needed.
- 3) Weigh immediately before use.

**6.2.3 Analytical procedure:**

- 1) Assemble the filtering apparatus and begin suction.
- 2) Shake the sample vigorously and rapidly transfer 100 mL to the funnel by means of a 100 mL graduated cylinder. If total filterable residue is low, a larger volume may be filtered.
- 3) Filter the sample through the glass fiber filter, rinse with three 10 mL portions of distilled water and continue to apply vacuum for about 3 minutes after filtration is complete to remove as much water as possible.
- 4) Transfer 100 mL or a larger volume of the filtrate to a weighed evaporating dish and evaporate to dryness on a steam bath.

CH2M HILL/MGM SOP (Total Dissolved Solids)  
Rev. 0 1/30/89

- 5) Dry the evaporated sample for at least 1 hour at 180°C. Cool in a desiccator and weigh.
- 6) Repeat the drying cycle until a constant weight is obtained, or until weight loss is less than 0.5 mg.

**6.3 Calculation:**

Calculate filterable residue (TDS) as follows:

$$\text{TDS mg/L} = \frac{(A - B) \times 1000}{C}$$

where: A = weight of dried residue + dish in mg  
B = weight of dish in mg  
C = volume of sample used in mL

**7.0 Reporting:**

- a. Total dissolved solids (filterable residue) is reported in units of mg/L.
- b. Values below 10 mg/L are reported as <10.

**8.0 Notes:**

- 8.1 The practical range of determination is 10 mg/L to 20 000 mg/L.
- 8.2 Filterable residue is defined as those solids capable of passing through a glass fiber filter and dried to constant weight at 180°C.
- 8.3 Preservation of the sample is not practical; analysis should begin as soon as possible. Refrigeration or icing to 4°C to minimize microbiological decomposition of solids is recommended.
- 8.4 Highly mineralized waters containing significant concentrations of calcium, magnesium, chloride, and/or sulfate may be hygroscopic and will require prolonged drying, desiccation, and rapid weighing.



CH2M HILL/MGM SOP (Total Dissolved Solids)  
Rev. 0 1/30/89 -

- 8.5 Samples containing high concentrations of bicarbonate will require careful and possibly prolonged drying at 180°C to insure that all the bicarbonate is converted to carbonate.
- 8.6 Too much residue in the evaporating dish will crust over and entrap water that will not be driven off during drying. Total residue should be limited to about 200 mg.

SOP No.: I-0002-LGN

Rev. No.: 0

Date issued: \_\_\_\_\_

Date initiated: \_\_\_\_\_

Written by: K. Starcher

## TOTAL ORGANIC CARBON (TOC), WATER

### Method 415.1

Optimum Concentration Range:

Sensitivity:

Reporting Detection Limit: 1.0 mg/l

Reporting Units: mg/l

Significant Figures: 3

Holding Time: 28 Days

#### 1.0 Method Summary

- 1.1 The organic carbon in a sample is converted to carbon dioxide (CO<sub>2</sub>) by wet chemical oxidation. The CO<sub>2</sub> formed is measured directly by an infrared detector.
- 1.2 The TOC analyzer used is a Dohrmann DC-80 Total Organic Carbon Analyzer with an ASM-1 Autosampler.

#### 2.0 Bench Sheets

Benchsheets or laboratory notebooks are to be used to enter raw data. For this SOP the term benchsheet will be used to signify either a benchsheet or a notebook entry. Use a run log to reference autosampler positions and sample descriptions when setting up to run.

Include all pertinent information such as sample size, dilution factors, dates of analysis, and sample ID. When a run is finished, attach the instrument printout to the bench sheet. The analyst must initial and date the bench sheet when the sample run is completed.

#### 3.0 Spreadsheet

All sample data and QC data should be entered into the CYANIDE computer spreadsheet within 24 hours after the analysis is completed. Calculations can be

SOP No.: I-0002-LGN  
Rev. No.: 00  
Date issued: \_\_\_\_\_  
Date initiated: \_\_\_\_\_  
Written by: K. Starcher

done either by using the calculation area of the computer spreadsheet, or manually. Enter all QC data in the appropriate areas of the spreadsheet. Date and initial the bench sheet when the data is entered into the spreadsheet program.

#### 4.0 Data Review Process

Within 24 hours the data review process should be completed. It then becomes the responsibility of the analyst to enter the data onto the Work In Progress (WIP) sheets or LIMS System or to see that a data entry person does so. The person who enters the data will initial and date the bench sheet and file it.

#### 5.0 Quality Control Samples

The following quality control samples are required for TOC analysis:

- 5.1 Calibration Standard: The calibration standard is diluted from a standard CN solution in the concentration appropriate for the range to be used. This standard is used to calibrate the instrument.
- 5.2 ICVS: One ICVS must be run before each run of samples. On the run log, the ICVS must be identified. The ICVS may also serve as the LCS. The acceptable recovery range for ICVS is 90.0-110.0%.
- 5.3 Method Blank (Preparation or Reagent Blank): One method blank must be analyzed per run. On the run log, the method blank must be identified
- 5.4 LCS: May be the ICVS.
- 5.5 CCVS: A mid-range standard run after every 10 samples. Use the same CCVS throughout the run. The acceptable recovery range is 90.0-110.0%. If a CCVS exceeds this range, stop analyses, determine the problem, recalibrate and verify the curve, and rerun all samples run since the last acceptable CCVS.
- 5.6 Matrix Spike (MS): 1 per 20 samples.
- 5.7 Duplicates or Matrix Spike Duplicates (MSD): 1 per 20 samples.

SOP No.: I-0002-LGNRev. No.: 0

Date issued: \_\_\_\_\_

## 6.0 Sample Handling and Preservation

- 6.1 Samples are preserved with  $H_2SO_4$  (or HCl).
- 6.4 Samples must be stored at  $4^\circ C (\pm 2^\circ C)$  and must be analyzed within holding time of 28 days.
- 6.5 Interferences
  - 6.5.1 Carbonate and bicarbonate carbon are positive interferences. Acidifying and sparging the samples with oxygen will eliminate the interference.

## 7.0 Apparatus

- 7.1 Dohrmann DC-80 Total Organic Carbon Analyzer with ASM-1 Autosampler.

## 8.0 Reagents

- 8.1 Deionized water, organic free.
- 8.2 Potassium persulfate solution: Dissolve 20 g reagent grade potassium persulfate ( $K_2S_2O_8$ ) in 1 liter of reagent water. Add 1 ml concentrated phosphoric acid and mix. Store in a cool dark location. Shelf life is 1 month.
- 8.3 Organic carbon standards: Dry 3-5 g potassium hydrogen phthalate ( $C_8H_5O_4K$ , KHP) to a constant weight. Carefully weigh 2.125 g dried KHP, and dissolve in deionized water. Add 0.5 ml concentrated phosphoric acid and dilute to 500 ml in a volumetric flask. Store in dark glass, under refrigeration. Replace monthly.
  - 8.3.1 400 ppm standard solution: Dilute 200 ml of 2000 ppm stock standard solution to 1000 ml. Store in dark glass, under refrigeration. Prepare fresh weekly.
  - 8.3.2 For other standard concentrations, dilute the 2000 ppm stock solution appropriately.

SOP No.: I-0002-LGNRev. No.: 0

Date issued: \_\_\_\_\_

**9.0 Procedure:**

- 9.1 Follow instrument manufacturer's instruction for calibration, procedure, and calculations.
- 9.2 After instrument is calibrated, set up run as follows:
1. ICVS
  2. Method Blank
  3. LCS
  4. CCVS after every 10 samples
  5. CCVS and method blank at end of run
- 9.3 If necessary to insure non-carryover between samples, run a blank between every sample.

4500-CN<sup>-</sup> M. Thiocyanate

## 1. General Discussion

When wastewater containing thiocyanate (SCN<sup>-</sup>) is chlorinated, highly toxic cyanogen chloride (CNCl) is formed. At an acidic pH, ferric ion (Fe<sup>3+</sup>) and SCN<sup>-</sup> form an intense red color suitable for colorimetric determination.

*a. Interference:*

1) Hexavalent chromium (Cr<sup>6+</sup>) interferes and is removed by adding ferrous sulfate (FeSO<sub>4</sub>) after adjusting to pH 1 to 2 with nitric acid (HNO<sub>3</sub>). Raising the pH to 9 with 1*N* sodium hydroxide (NaOH) precipitates Fe<sup>3+</sup> and Cr<sup>3+</sup>, which are then filtered out.

2) Reducing agents that reduce Fe<sup>3+</sup> to Fe<sup>2+</sup>, thus preventing formation of ferric thiocyanate complex, are destroyed by adding a few drops of hydrogen peroxide (H<sub>2</sub>O<sub>2</sub>). Avoid excess H<sub>2</sub>O<sub>2</sub> to prevent reaction with SCN<sup>-</sup>.

3) Industrial wastes may be highly colored or contain various interfering organic compounds. To eliminate these interferences,<sup>1</sup> use the pretreatment procedure given in ¶ 4c below. It is the analyst's responsibility to validate the method's applicability without pretreatment (¶ 4b). If in doubt, pretreat sample before proceeding with analysis (¶ 4c).

4) If sample contains cyanide amenable to chlorination and would be preserved for the cyanide determination at a high pH, sulfide could interfere by converting cyanide to SCN<sup>-</sup>. To preserve SCN<sup>-</sup> and CN<sup>-</sup>, precipitate the sulfide by adding lead salts according to 4500-CN<sup>-</sup>.B.2 before adding alkali; filter to remove precipitate.

5) Thiocyanate is biodegradable. Preserve samples at pH <2 by adding mineral acid and refrigerate.

6) If interferences from industrial wastes are not removed as directed in ¶ 4c below, consider adopting a solvent extraction technique with colorimetric or atomic absorption analysis of the extract.<sup>2,3</sup>

*b. Application:* 0.1 to 2.0 mg CN<sup>-</sup>/L in natural or wastewaters. For higher concentrations, use a portion of diluted sample.

## 2. Apparatus

*a. Spectrophotometer or filter photometer,* for use at 460 nm, providing a light path of 5 cm.

*b. Glass adsorption column:* Use a 50-mL buret with a glass-wool plug, and pack with macroporous resin (¶ 3f) approximately 40 cm high. For convenience, apply a powder funnel of the same diameter as the buret to the top with a short piece of plastic tubing.

## 3. Reagents

*a. Ferric nitrate solution:* Dissolve 404 g Fe(NO<sub>3</sub>)<sub>3</sub>·9H<sub>2</sub>O in about 800 mL distilled water. Add 80 mL conc HNO<sub>3</sub> and dilute to 1 L.

*b. Nitric acid solution, 0.1*N*:* Mix 6.4 mL conc HNO<sub>3</sub> in about 800 mL distilled water and dilute to 1 L.

*c. Stock thiocyanate solution:* Dissolve 1.673 g potassium thiocyanate (KSCN) in distilled water and dilute to 1000 mL; 1.00 mL 1.00 mg SCN<sup>-</sup>.

*d. Standard thiocyanate solution:* Dilute 10 mL stock solution to 1 L with distilled water; 1.00 mL = 0.01 mg SCN<sup>-</sup>.

*e. Sodium hydroxide solution, 4 g/L:* Dissolve 4 g NaOH in about 800 mL distilled water and dilute to 1 L.

*f. Macroporous resin, 18 to 50 mesh:*<sup>\*</sup> The available resin may not be purified. Some samples have shown contamination with waxes and oil, giving poor permeability and adsorption. Purify as follows:

Place sufficient resin to fill the column or columns in a beaker and add 5 times the resin volume of acetone. Stir gently for 1 h. Pour off fines and acetone from settled resin and add 5 times the resin volume of hexane. Stir for 1 h. Pour off fines and hexane and add 5 times the resin volume of methanol. Stir for 15 min. Pour off methanol and add 3 times the resin volume of 0.1*N* NaOH. Stir for 15 min. Pour off NaOH solution and add 3 times the resin volume of 0.1*N* HNO<sub>3</sub>. Stir for 15 min. Pour off HNO<sub>3</sub> solution and add 3 times the resin volume of distilled water. Stir for 15 min. Drain excess water and use purified resin to fill the column. Store excess purified resin after covering it with distilled water. Keep in a closed jar.

*g. Methyl alcohol.*

## 4. Procedure

*a. Preparation of calibration curve:* Prepare a series of standards containing from 0.02 mg to 0.40 mg SCN<sup>-</sup> by pipetting measured volumes of standard KSCN solution into 200-mL volumetric flasks and diluting with water. Mix well. Develop color according to ¶ b below. Plot absorbance against SCN<sup>-</sup> concentration expressed as mg/50 mL sample. The absorbance plot should be linear.

*b. Color development:* Use a filtered sample or portion from a diluted solution so that the concentration of SCN<sup>-</sup> is between 0.1 and 2 mg/L. Adjust pH to 2 with conc HNO<sub>3</sub>, added dropwise. Pipet 50-mL portion to a beaker, add 2.5 mL ferric nitrate, and mix.

Fill a 5-cm absorption cell and measure absorbance against a reagent blank at 460 nm or close to the maximum absorbance found with the instrument being used. Measure absorbance of the developed color against a reagent blank within 5 min from adding the reagent. (The color develops within 30 s and fades on standing in light.)

*c. Sample pretreatment:*

1) Color and various organic compounds interfere with absorbance measurement. At pH 2, macroporous resin removes these interfering materials by adsorption without affecting thiocyanate.

2) To prepare the adsorption column, fill it with resin, rinse with 100 mL methanol, and follow by rinses with 100 mL 0.1*N* NaOH, 100 mL 0.1*N* HNO<sub>3</sub>, and finally with 100 mL distilled water. If previously purified resin is used, omit these preparatory steps.

3) When washing, regenerating, or passing a sample through the column, as solution level approaches resin bed, add and drain five separate 5-mL volumes of solution or water (depending on which is used in next step) to approximate bed height. After last

\* Amberlite® XAD-8. Rohm & Haas Company, or equivalent.

5-mL volume, fill column with remaining liquid. This procedure prevents undue mixing of solutions and helps void the column of the previous solution.

4) Acidify 150 mL sample (or a dilution) to pH 2 by adding conc HNO<sub>3</sub> dropwise while stirring. Pass it through the column at a flow rate not to exceed 20 mL/min. If the resin becomes packed and the flow rate falls to 4 to 5 mL/min, use gentle pressure through a manually operated hand pump or squeeze bulb on the column. In this case, use a separator funnel for the liquid reservoir instead of the powder funnel. Alternatively use a vacuum bottle as a receiver and apply gentle vacuum. Do not let liquid level drop below the adsorbent in the column.

5) When passing a sample through the column, measure 90 mL of sample in a graduated cylinder, and from this use the five 5-mL additions as directed in ¶ 3), then pour the remainder of the 90 mL into the column. Add rest of sample and collect 60 mL eluate to be tested after the first 60 mL has passed through the column.

6) Prepare a new calibration curve using standards prepared according to ¶ 4a, but acidify standards according to ¶ 4b, and pass them through the adsorption column. Develop color and measure absorbance according to ¶ 4b against a reagent blank prepared by passing acidified, distilled water through the adsorption column.

7) Pipet 50 mL from the collected eluate to a beaker, add 2.5 mL ferric nitrate solution, and mix. Measure absorbance according to ¶ 4b against a reagent blank [see ¶ 6) above].

8) From the measured absorbance value, determine thiocyanate content of the sample or dilution using the absorbance plot.

9) Each day the column is in use, test a mid-range standard to check absorption curve.

10) Regenerate column between samples by rinsing with 100 mL 0.1N NaOH; 50 mL 0.1N HNO<sub>3</sub>; and 100 mL water. Insure that the water has rinsed empty glass section of the buret. Occasionally rinse with 100 mL methanol for complete regeneration. Adsorbed weak organic acids and thiocyanate residuals from earlier tests are eluted by the NaOH rinse. Leave the column covered with the last rinse water for storage.

## 5. Calculation

Compute slope (*m*) and intercept (*b*) of standard curve as directed in 4500-CN<sup>-</sup>.E.5.

Calculate thiocyanate concentration as follows:

$$\text{mg SCN}^-/\text{L} = (ma_1 + b) \times \text{dilution factor}$$

where:

*a*<sub>1</sub> = absorbance of sample solution.

## 6. Precision and Bias<sup>4</sup>

a. *Precision*: Based on the results of twelve operators in nine laboratories, at four levels of concentration, the precision of the test method within its designated range is linear with concentration and may be expressed as follows:

$$\begin{aligned}\text{Reagent water: } S_T &= 0.093x + 0.0426 \\ S_o &= 0.045x + 0.010\end{aligned}$$

$$\begin{aligned}\text{Water matrix: } S_T &= 0.055x + 0.0679 \\ S_o &= 0.024x + 0.182\end{aligned}$$

where:

*S<sub>T</sub>* = overall precision, mg/L.

*S<sub>o</sub>* = pooled single-operator precision, mg/L. and

*x* = thiocyanate concentration, mg/L.

b. *Bias*: Recoveries of known amounts of thiocyanate from Type II reagent water and selected water matrices including natural waters, laboratory effluent, steel mill effluent, and dechlorinated and treated sanitary effluents were as follows:

Medium	Added mg/L	Recovered mg/L	<i>n</i>	<i>S<sub>T</sub></i>	Bias	% Bias
Reagent water	1.42	1.411	30	0.181	-0.009	-0.6
	0.71	0.683	27	0.091	-0.027	-4
	0.35	0.329	30	0.084	-0.021	-6
	0.07	0.068	30	0.052	-0.002	-3
Selected water matrices	1.42	1.408	26	0.151	-0.012	-0.8
	0.71	0.668	29	0.096	-0.042	-6
	0.35	0.320	29	0.085	-0.030	-9
	0.07	0.050	29	0.079	-0.020	-29

For other matrices these data may not apply.

## 7. References

1. SPENCER, R.R., J. LEENHEER & V.C. MARTI. 1980. Automated colorimetric determination of thiocyanate, thiosulfate and tetrathionate in water. 94th Annu. Meeting. Assoc. Official Agricultural Chemists, Washington, D.C. 1981.
2. DANCHICK, R.S. & D.F. BOLTZ. 1968. Indirect spectrophotometric and atomic absorption spectrometric methods in determination of thiocyanate. *Anal. Chem.* 43:2215.
3. LUTHY, R.G. 1978. Manual of Methods: Preservation and Analysis of Coal Gasification Wastewaters. FE-2496-16, U.S. Dep. Energy, National Technical Information Serv., Springfield, Va.
4. AMERICAN SOCIETY FOR TESTING & MATERIALS. 1989. Research Rep. D4193:19-1099. American Soc. Testing & Materials, Philadelphia, Pa.

**DRAFT**

**CH2M HILL  
Montgomery Laboratory  
Standard Operating Procedures  
Wet Chemistry Department**

**Method for Total and Amenable  
Cyanide Analysis in Water**

Method SW846 9010A and SW846 9012A (Manual Spectrophotometric; Semi-Automated Spectrophotometric)

**1. SCOPE AND APPLICATION**

- 1.1 This method applies to the determination of cyanide in drinking, surface and saline waters, and domestic and industrial wastes
- 1.2 The titration procedure using silver nitrate with p-dimethylaminobenzalrhodanine indicator is used for standardization of intermediate standard cyanide solution.
- 1.3 The manual colorimetric procedure is used for concentrations below 1 mg/L of cyanide and is sensitive to about 5 ug/L (Option A, 8.4).

**2. SUMMARY OF METHOD**

- 2.1 The cyanide as (HRN) hydrocyanic acid (HCN) is released from cyanide complexes by means of a reflux-distillation operation and adsorbed in a scrubber containing sodium hydroxide solution. The cyanide ion in the absorbing solution is then determined by volumetric titration or colorimetrically.
- 2.2 In the colorimetric measurement, the cyanide is converted to cyanogen chloride, CNCl, by reaction with chloramine-T at a pH less than 8 without hydrolyzing to the cyanate. After the reaction is complete, color forms upon the addition of pyridinebarbituric acid reagent. The absorbance is read at 578 nm for pyridine-barbituric acid. To obtain colors of comparable intensity, it is essential to have the same salt content in both the sample and the standards.
- 2.3 The titrimetric measurement uses a standard solution of silver nitrate to titrate cyanide in the presence of a silver sensitive indicator.



### 3. DEFINITIONS

- 3.1 Cyanide is defined as cyanide ion and complex cyanides converted to hydrocyanic acid (HCN) by reaction in a reflux system of a mineral acid in the presence of magnesium ion.

### 4. SAMPLE HANDLING AND PRESERVATION

- 4.1 All bottles must be thoroughly cleansed and rinsed to remove soluble material from containers.
- 4.2 Oxidizing agents such as chlorine decompose most of the cyanides. Test a drop of the sample with potassium iodide-starch test paper (KI-starch paper); a blue color indicates the need for treatment. Add ascorbic acid a few crystals at a time until a drop of sample produces no color on the indicator paper. Then add an additional 0.6 g of ascorbic acid for each liter of sample volume.
- 4.3 Samples are preserved with 2 ml of 10 N sodium hydroxide per liter of sample (ph > 12) at the time of collection (Exhibit D, Section II).
- 4.4 Samples must be stored at 4°C ( $\pm 2^\circ\text{C}$ ) and must be analyzed within the holding time specified in Exhibit D, Section II (14 days).

### 5. INTERFERENCES

- 5.1 Interferences are eliminated or reduced by using the distillation procedure described in Procedure 8.1.
- 5.2 Sulfides adversely affect the colorimetric and titration procedures. If a drop of the distillate on lead acetate test paper shows the presence of sulfides, treat 25 ml more of the sample than that required for the cyanide determination with powdered cadmium carbonate. Yellow cadmium sulfide precipitates if the sample contains sulfide. Repeat this operation until a drop of the treated sample solution does not darken the lead acetate test paper. Filter the solution through a dry filter paper into a dry beaker, and from the filtrate measure the sample to be used for analysis. Avoid a large excess of cadmium carbonate and a long contact time in order to minimize a loss by complexation or occlusion of cyanide on the precipitated material. Sulfides should be removed before the solution is preserved with sodium hydroxide as described in 4.3.
- 5.3 The presence of surfactants may cause the sample to foam during refluxing. If this occurs, adding an agent such as Dow Corning 544 antifoam agent will prevent the foam from collecting in the condenser. Fatty acids will distill and form soaps under alkaline titration conditions, making the end point almost impossible to detect. When this reaction occurs, one of the spectrophotometric methods should be used.

## 6. APPARATUS

- 6.1 Reflux distillation apparatus such as shown in Figure 1. The boiling flask should be 1 liter in size with an inlet tube and provision for a condenser.
- 6.2 Microburette, 5.0 ml (for titration)
- 6.3 Spectrophotometer suitable for measurements at 578 nm with a 1.0 cm cell or larger (for manual spectrophotometric method).
- 6.4 Lachat QuikChem Automated Flow Injection Analyzer which includes:
  - 6.4.1 Automatic Sampler
  - 6.4.2 Proportioning Pump
  - 6.4.3 Injection Valve Module with a 150 cm 0.8 mm i.d. sample loop
  - 6.4.4 Flow Cell, 10 mm, 80  $\mu$ L
  - 6.4.5 Interference Filter Wavelength, 570 nm
  - 6.4.6 Heater Module
  - 6.4.7 Reaction Module 10-204-00-1-A

## 7. REAGENTS

- 7.1 Distillation and Preparation Reagents
  - 7.1.1 Sodium hydroxide solution 0.25N. Dissolve 20 g of NaOH in distilled water, and dilute to 2 liters with distilled water.
  - 7.1.2 Cadmium carbonate: powdered
  - 7.1.3 Ascorbic acid: crystals
  - 7.1.4 Sulfuric acid: concentrated
  - 7.1.5 Magnesium chloride solution: Weigh 510 g of  $\text{MgCl}_2 \times 6\text{H}_2\text{O}$  into a 1,000 ml flask, dissolve, and dilute to 1 liter with distilled water.
  - 7.1.6 Calcium hypochlorite solution: Dissolve 5 g of calcium hypochlorite  $[\text{Ca}(\text{OCl})_2]$  in 100 ml of reagent water.
- 7.2 Stock Standards and Titration Reagents
  - 7.2.1 Stock cyanide solution: Dissolve 2.51 g of KCN and 2 g KOH in 1 liter of distilled water. Standardize with 0.0192 N  $\text{AgNO}_3$ .
  - 7.2.2 Standard cyanide solution, intermediate: Dilute 50.0 ml of stock (1 ml = 1 mg CN) to 1000 ml with distilled water.

Insert Figure 1

7.2.3 Standard silver nitrate solution, 0.0192 N: Prepare by crushing approximately 5 g  $\text{AgNO}_3$  crystals and drying to constant weight at  $40^\circ\text{C}$ . Weigh out 3.2647 g of dried  $\text{AgNO}_3$ , dissolve it in distilled water, and dilute it to 1,000 ml (1 ml = 1 mg CN).

7.2.4 Rhodanine indicator: Dissolve 20 mg of p-dimethylaminobenzalrhodanine in 100 ml of acetone.

### 7.3 Manual Spectrophotometric Reagents

7.3.1 Sodium dihydrogenphosphate, 1 M: Dissolve 138 g of  $\text{NaH}_2\text{PO}_4 \cdot \text{H}_2\text{O}$  in a liter of distilled water. Refrigerate this solution.

7.3.2 Chloramine-T solution: Dissolve 1.0 g of white, water soluble chloramine-T in 100 ml of distilled water and refrigerate until ready to use. Prepare fresh daily.

#### 7.3.3 Color Reagent--

7.3.3.1 Pyridine-barbituric acid reagent: Place 15 g of barbituric acid in a 250 ml volumetric flask and add just enough distilled water to wash the sides of the flask and wet the barbituric acid. Add 75 ml of pyridine and mix. Add 15 ml of HCl (sp gr 1.19), mix, and cool to room temperature. Dilute to 250 ml with distilled water and mix. This reagent is stable for approximately 6 months if stored in a cool, dark place.

### 7.4 Semi-Automated Spectrophotometric Reagents

7.4.1 Chloramine-T solution: Dissolve 1.00 g of chloramine-T in distilled water and dilute to 100 mL. Prepare fresh daily.

7.4.2 Phosphate buffer: Dissolve 138 g of  $\text{NaH}_2\text{PO}_4 \cdot \text{H}_2\text{O}$  in distilled water and dilute to 1 liter. Store at  $4^\circ\text{C}$  ( $\pm 2^\circ\text{C}$ ).

7.4.3 Pyridine-barbituric acid solution: Transfer 15 g of barbituric acid into a 1 liter volumetric flask. Add about 100 mL of distilled water and swirl the flask. Add 74 mL of pyridine and mix. Add 15 mL of concentrated HCl and mix. Dilute to about 900 mL with distilled water and mix until the barbituric acid is dissolved. Dilute to 1 liter with distilled water. Store at  $4^\circ\text{C}$  ( $\pm 2^\circ\text{C}$ )

7.4.4 Sampler wash: Dissolve 10 g of NaOH in distilled water and dilute to 1 liter.

## 8. PROCEDURE

### 8.1 Pretreatment for cyanides amenable to chlorination:

- 8.1.1 Two sample aliquots are required to determine cyanides amenable to chlorination. To one 500-mL aliquot, or to a volume diluted to 500 mL, add calcium hypochlorite solution dropwise while agitating and maintaining the pH between 11 and 12 with sodium hydroxide (Step 5.3).

**CAUTION:** The initial reaction product of alkaline chlorination is the very toxic gas *cyanogen chloride*; therefore, it is recommended that this reaction be performed in a hood. For convenience, the sample may be agitated in a 1-liter beaker by means of a magnetic stirring device.

- 8.1.2 Test for residual chlorine with KI-starch paper and maintain this excess for 1 hr, continuing agitation. A distinct blue color on the test paper indicates a sufficient chlorine level. If necessary, add additional hypochlorite solution.

- 8.1.3 After 1 hr, add 0.5 g portions of ascorbic acid until KI-starch paper shows no residual chlorine. Add an additional 0.5 g of ascorbic acid to ensure the presence of excess reducing agent.

- 8.1.4 Test for total cyanide in both the chlorinated and unchlorinated aliquots. (The difference of total cyanide in the chlorinated and unchlorinated aliquots is the cyanide amenable to chlorination.)

### 8.2 Distillation

- 8.2.1 Place 500 ml of sample, or an aliquot diluted to 500 ml, in the 1 liter boiling flask. Add exactly 100 ml of sodium hydroxide (7.1.1) to the absorbing tube. Connect the boiling flask, condenser, absorber, and trap in the train.

- 8.2.2 Start a slow stream of air entering the boiling flask by adjusting the vacuum source. Adjust the vacuum so that approximately one bubble of air per second enters the boiling flask through the air inlet tube.

**NOTE:** The bubble rate will not remain constant after the reagents have been added and while heat is being applied to the flask. It will be necessary to readjust the air rate occasionally to prevent the solution in the boiling flask from backing up into the air inlet tube.

- 8.2.3 Slowly add 25 ml concentrated sulfuric acid (7.1.4) through the air inlet tube. Rinse the tube with distilled water and allow the airflow to mix the flask contents for 3 minutes. Pour 20 ml of magnesium chloride solution (7.1.5) into the air inlet and wash it down with a stream of water.
- 8.2.4 Heat the solution to boiling, taking care to prevent the solution from backing up into and overflowing from the air inlet tube. Reflux for one hour. Turn off heat and continue the airflow for at least 15 minutes. After cooling the boiling flask, disconnect absorber and close off the vacuum source.
- 8.3 Titrimetric Determination for Standardization of Intermediate Standard Cyanide Solution
- 8.3.1 Transfer 100 ml of intermediate standard to a 500 ml Erlenmeyer flask. Add 10-12 drops of the benzalrhodanine indicator.
- 8.3.2 Titrate with standard silver nitrate to the first change in color from yellow to brownish-pink. Titrate a distilled water blank using the same amount of sodium hydroxide and indicator as in the standard.
- 8.3.3 The analyst should familiarize himself with the end point of the titration and the amount of indicator to be used before actually titrating the samples. A 5 or 10 ml microburette may be conveniently used to obtain a more precise titration.
- 8.4 Manual Spectrophotometric Determination (Option A)
- 8.4.1 Withdraw 50 ml or less of the solution from the absorbing tube and transfer to a 100 ml volumetric flask. If less than 50 ml is taken, dilute to 50 ml with 0.25 N sodium hydroxide solution. Add 15.0 ml of sodium phosphate solution (7.3.1) and mix.
- 8.4.1.1 Pyridine-barbituric acid method: Add 2 ml of chloramine-T (7.3.2) and mix., After 1 to 2 minutes, add 5 ml of pyridine-barbituric acid solution (7.3.3.1) and mix. Dilute to mark with distilled water and mix again. Allow 8 minutes for color development, then read absorbance at 578 nm in a 1 cm cell within 15 minutes.
- 8.4.2 Prepare a minimum of 5 standards and a blank by pipetting suitable volumes of standard solution into 100 ml volumetric flasks. NOTE: One calibration standard must be at the Contract Required Detection Limit (CRDL). To each standard, add 50 ml of 0.25 N sodium hydroxide. Standards must bracket the concentration of the samples. If dilution is required, use the blank solution.

As an example, standard solutions could be prepared as follows:

<u>ul of Standard Solution</u>	<u>Conc. ug CN</u>
<u>7.2.2</u>	
0	Blank
50	2.5
100	5
200	10
500	25
1,000	50
2,000	100

8.4.2.2 It is not imperative that all standards be distilled in the same manner as the samples. At least one standard (mid-range) must be distilled and compared to similar values on the curve to ensure that the distillation technique is reliable. If the distilled standard does not agree with  $\pm 15\%$  of the undistilled standards, the operator should find and correct the cause of the apparent error before proceeding.

8.4.2.2 Prepare a standard curve by plotting absorbance of standard vs. cyanide concentrations.

#### 8.5 Semi-Automatic Spectrophotometric Determination (Option B)

8.5.1 Set up the manifold as shown in manifold diagram. Pump the reagents through the system until a steady baseline is obtained.

8.5.2 Calibration standards: Prepare a blank and at least five calibration standards over the range of the analysis. One calibration standard must be at the CRDL. For a working range of 0-100 ug/L, the following standards may be used:

8.5.2.1 It is not imperative that all standards be distilled in the same manner as the samples. At least one standard (mid-range) must be distilled and compared to similar values on the curve to ensure that the distillation technique is reliable. If the distilled standard does not agree within  $\pm 15\%$  percent of the undistilled standards, the operator should find and correct the cause of the apparent error before proceeding.

<u>uL Standard Solution (7.2.2) diluted to 100 ml</u>	<u>Concentration ug CN/L</u>
---	----------------------------------

0	0
50	2.5
100	5.0
200	10.0
500	25.0
1,000	50.0
2,000	100.0

Add 1.0 g of NaOH to each standard. Store at 4°C ( $\pm 2^\circ\text{C}$ ).

8.5.3 Place calibration standards, blanks, and control standards in the sampler tray, followed by distilled samples, distilled duplicates, distilled standards, distilled spikes, and distilled blanks.

8.5.4 Set Injection Timing With:

8.5.4.1	Pump speed: 35
8.5.4.2	Cycle period: 40 s
8.5.4.3	Sample Loop Length: 150 cm
8.5.4.4	Load period: 20 s
8.5.4.5	Inject period: 20 s
8.4.4.6	Inject to start of peak period: 25 s
8.4.4.7	Inject to end of peak period: 61 s

8.5.5 Set System IV Gain: 340 x 1

8.5.6 System operation

8.5.6.1	Inspect modules for proper connections.
8.5.6.2	Turn on power to all modules. Allow heater to warm up to 60°C.
8.5.6.3	Place reagent transmission lines into proper containers. Rain tension levers on pump tube cassettes.
8.5.6.4	Pump system until a stable baseline is attained.
8.5.6.5	Set baseline. If necessary, manually inject a high standard to set gain on colorimeter.



- 8.5.6.6 Program data system to initial parameters or those empirically determined.
- 8.5.6.7 Place calibration standards and blank in sample tray in descending order of concentration followed by unknowns, and check standards.
- 8.5.6.8 At end of run, place all transmission lines in water, flush system and pump dry.
- 8.5.6.9 Turn off pump, all modules, and release pump tube cassettes.

## 9. CALCULATIONS

9.1 Using the titrimetric procedure, calculate concentration of CN as follows:


$$\text{CN, mg/L} = \frac{(A-B) 1,000 \text{ ml/L}}{\text{ml orig. sample}} \times \frac{100 \text{ ml}}{\text{ml of aliquot titrated}}$$

where: A = volume of AgNO<sub>3</sub> for titration of sample  
(1 ml = 1 mg Ag)

B = volume of AgNO<sub>3</sub> for titration of blank  
(1 ml = 1 mg Ag)

AND: 100 ml = distillate volume (see 8.2.5)  
1,000 ml = conversion ml to L  
ml original sample (See 8.2.1)  
ml of aliquot titrated (See 8.3.1)

## Manifold Diagram



**CARRIER** is 0.25 M sodium hydroxide, Reagent 1.

1"	is	70.0	cm of tubing on a 1 in coil support
2"	is	135	cm of tubing on a 2 in coil support
2.5"	is	168	cm of tubing on a 2.5 in coil support
3"	is	202	cm of tubing on a 3 in coil support
4"	is	255	cm of tubing on a 4 in coil support
8"	is	550	cm of tubing on a 8 in coil support

Heated tubing is shown inside a box with the temperature next to the box. heated tubing is 650 cm unless otherwise specified.

All manifold tubing is 0.8 mm (0.032 in) i.d. This is 5.2 uL/cm.

## 10.0 QUALITY CONTROL

- 10.1 Verify calibration with an independent calibration standard (EPA traceable). If the standards are not within 15% of the expected value, recalibration is required. Verify calibration at the beginning of the analysis (initial calibration verification—ICV) and every 10 analysis (continuing calibration verification—CCV).
- 10.2 A matrix spike should be prepared to check the efficiency of sample distillation by adding cyanide from the intermediate standard to 500 mL of sample to ensure a concentration of approximately 40 µg/L. Both the matrix duplicate and matrix spike duplicate are brought through the entire sample preparation and analytical process.
- 10.3 The method of standard additions can be used for the analysis of all samples that suffer from matrix interferences.
- 10.4 Standard curve will be derived from data consisting of one reagent blank and all the concentrations of standards. The response for each prepared standard shall be based upon the average of three replicate readings of each standard.
- 10.5 Standard curve must be verified with a standard within  $\pm 10\%$  of true value.
- 10.6 A reagent blank must be run at the beginning of analysis (initial calibration blank—ICB), and with every 10 analysis (continuing calibration blank—CCB)).
- 10.7 A method blank will be distilled and analyzed with each sample distillation batch. If the method blank result is not below the reporting limit, the batch must be redistilled and reanalyzed.
- 10.8 A laboratory control sample (EPA traceable) will be distilled and analyzed with the sample distillation batch. If the laboratory control sample result is not within  $\pm 15\%$  of true value, the batch must be redistilled and reanalyzed.
- 10.9 A high and a low standard that is distilled must be analyzed with each analysis batch with results within  $\pm 10\%$  of true value.
- 10.10 Sample matrix interference caused by sulfides and chlorides should be removed before preservation and distillation.

4500-CN<sup>-</sup> I. Weak Acid Dissociable Cyanide

## 1. General Discussion

Hydrogen cyanide (HCN) is liberated from a slightly acidified (pH 4.5 to 6.0) sample under the prescribed distillation conditions. The method does not recover CN<sup>-</sup> from tight complexes that would not be amenable to oxidation by chlorine. The acetate buffer used contains zinc salts to precipitate iron cyanide as a further assurance of the selectivity of the method. In other respects the method is similar to 4500-CN<sup>-</sup>.C.

## 2. Interferences

See 4500-CN<sup>-</sup>.B.3.

Protect sample and apparatus from ultraviolet light to prevent photodecomposition of some metal-cyanide complexes and an increase in concentration of weak acid dissociable cyanide.

If procedure is used to determine low concentrations of cyanide in samples of ferri- and ferrocyanide, add more, e.g., fivefold excess, zinc acetate solution before adding acid and distilling.

## 3. Apparatus

See Section 4500-CN<sup>-</sup>.C.2 and Figure 4500-CN<sup>-</sup>.1, and also Section 4500-CN<sup>-</sup>.D.2, 4500-CN<sup>-</sup>.E.2, or 4500-CN<sup>-</sup>.F.2, depending on method of estimation.

## 4. Reagents

a. *Reagents listed in Section 4500-CN<sup>-</sup>.C.3.*

b. *Reagents listed in Section 4500-CN<sup>-</sup>.D.3, 4500-CN<sup>-</sup>.E.3, or 4500-CN<sup>-</sup>.F.3, depending on method of estimation.*

c. *Acetic acid, 1 + 9:* Mix 1 volume of glacial acetic acid with 9 volumes of water.

d. *Acetate buffer:* Dissolve 410 g sodium acetate trihydrate (NaC<sub>2</sub>H<sub>3</sub>O<sub>2</sub>·3H<sub>2</sub>O) in 500 mL water. Add glacial acetic acid to yield a solution pH of 4.5 (approximately 500 mL).

e. *Zinc acetate solution, 100 g/L:* Dissolve 120 g Zn(C<sub>2</sub>H<sub>3</sub>O<sub>2</sub>)<sub>2</sub>·H<sub>2</sub>O in 500 mL water. Dilute to 1 L.

f. *Methyl red indicator.*

## 5. Procedure

Follow procedure described in 4500-CN<sup>-</sup>.C.4, but with the following modifications:

a. Do not add sulfamic acid, because NO<sub>2</sub><sup>-</sup> and NO<sub>3</sub><sup>-</sup> do not interfere.

b. Instead of H<sub>2</sub>SO<sub>4</sub> and MgCl<sub>2</sub> reagents, add 20 mL each of the acetate buffer and zinc acetate solutions through air inlet tube. Also add 2 to 3 drops methyl red indicator. Rinse air inlet tube with water and let air mix contents. If the solution is not pink, add acetic acid (1 + 9) dropwise through air inlet tube until a pink color persists.

c. Follow instructions beginning with 4500-CN<sup>-</sup>.C.4d.

d. For determining CN<sup>-</sup> in the absorption solution, use the preferred finish method (4500-CN<sup>-</sup>.D, E, or F).

6. Precision and Bias<sup>1</sup>

The precision and bias information given in this section may not apply to waters of untested matrices.

a. *Precision:*

1) *Colorimetric*—Based on the results of nine operators in nine laboratories, the overall and single-operator precision of this test method within its designated range may be expressed as follows:

$$\text{Reagent water: } S_T = 0.09x + 0.010$$

$$S_o = 0.08x + 0.005$$

$$\text{Selected water matrices: } S_T = 0.08x + 0.012$$

$$S_o = 0.05x + 0.008$$

2) *Electrode*—Based on the results of six operators in five laboratories, the overall and single-operator precision of this test method within its designated range may be expressed as follows:

$$\text{Reagent water: } S_T = 0.09x + 0.004$$

$$S_o = 0.02x - 0.009$$

$$\text{Selected water matrices: } S_T = 0.08x + 0.005$$

$$S_o = 0.02x + 0.004$$

3) *Titrimetric*—Based on the results of six operators in three laboratories, the overall and single-operator precision of this test method within its designated range may be expressed as follows:

$$\text{Reagent water: } S_T = 0.532 - 0.10x$$

$$S_o = 0.151 - 0.01x$$

$$\text{Selected water matrices: } S_T = 0.604 - 0.06x$$

$$S_o = 0.092 + 0.02x$$

where:

$S_T$  = overall precision.

$S_o$  = single-operator precision, and

$x$  = cyanide concentration, mg/L.

b. *Bias:* Recoveries of known amounts of cyanide from Type II reagent water and selected water matrices are shown below.

Medium	Technique	Added mg/L	Recovered mg/L	n	$S_T$	Bias	% Bias
Reagent water	Colorimetric	0.030	0.030	25	0.0089	0.000	0
		0.100	0.117	27	0.0251	0.017	17
		0.400	0.361	27	0.0400	-0.039	-10
	Electrode	0.030	0.030	21	0.0059	0.000	0
		0.100	0.095	21	0.0163	-0.005	-5
		0.400	0.365	21	0.0316	-0.035	-9
		1.000	0.940	21	0.0903	-0.060	-6
	Titrimetric	1.00	1.35	18	0.4348	0.35	35
		1.00	1.38	18	0.3688	0.38	38
Selected water matrices	Colorimetric	4.00	3.67	18	0.1830	-0.33	-8
	Colorimetric	0.030	0.029	15	0.0062	0.001	3
		0.100	0.118	24	0.0312	0.018	18
		0.400	0.381	23	0.0389	-0.019	-5
	Electrode	0.030	0.029	20	0.0048	-0.001	-3
		0.100	0.104	21	0.0125	0.004	4
		0.400	0.357	21	0.0372	-0.043	-11
		1.000	0.935	21	0.0739	-0.065	-7
	Titrimetric	1.00	1.55	18	0.5466	0.55	55
		1.00	1.53	18	0.4625	0.53	53
		4.00	3.90	18	0.3513	-0.10	-3

## 7. Reference

1. AMERICAN SOCIETY FOR TESTING & MATERIALS. 1987. Research Rep. D2036:19-1131. American Soc. Testing & Materials. Philadelphia, Pa.

## ***Appendix L***

### ***HydroPunch Method***

# HYDRO PUNCH

## Site Investigation Without Wells

The HydroPunch® system enables drill rig operators to locate, measure and sample ground water and floating layers of gasoline and other hydrocarbons—rapidly and economically, without installing wells.

### *HydroPunch Collects Samples of Ground Water & Floating Layer*

#### **QUALITY SAMPLES IN AN HOUR OR LESS—AT MUCH LOWER COST**

HydroPunch technology is a breakthrough in site investigation. Sampling is so rapid, you can have *reliable data in hours*, not the weeks or months required by traditional monitoring well surveys. Unlike geophysical or soil gas techniques, HydroPunch delivers actual samples of ground water and hydrocarbons—not indirect and sometimes misleading readings.

HydroPunch samples are consistent with monitoring requirements for *all priority pollutants*. HydroPunch II hydrocarbon samples accurately identify and show relative thickness of floating layers.

Best yet, HydroPunch sampling costs 50-90% less than drilling, casing, and developing conventional monitoring wells. HydroPunch sampling is not intended to replace wells for long-term monitoring; it helps optimize location and minimize the number of wells needed for effective monitoring—greatly speeding up site assessment.

#### **ENVIRONMENTALLY SAFE, WITH NO PERMANENT INSTALLATION**

HydroPunch operates with minimal disturbance to environmentally sensitive areas. There's no need to dispose of well development water, or of drill cuttings when pushed directly from the surface. The unobtrusive technique won't interfere with normal site operations.

HydroPunch boreholes can be easily abandoned or pressure-grouted from the bottom up. This leaves no permanent well to be monitored unnecessarily, and helps protect against possible short-circuiting of contamination between vertical zones.



# HYDROPUNCH

## HOW IT WORKS

The HydroPunch is driven to the desired depth in unconsolidated soils. The HydroPunch system can be used in formations suitable for a standard 2" split barrel (spoon) soil sampler—such as unconsolidated clays, silts, sands, and fine gravels.

Preliminary borings, an initial site test sample, or other information helps estimate sampling depth. An auger or split barrel sampler may provide a "pilot hole" to the area just above the sampling zone. (In some conditions, the tool can be driven directly from the surface for faster sampling.)

## HYDROPUNCH I—GROUND WATER SAMPLING

The sampling tool is assembled with clean O-rings, screens, and check balls. With the drive cone/inlet assembly retracted, the tool is driven to the proper depth—at least 5 feet below the static water level, to allow sufficient hydrostatic pressure for the sample chamber to fill.

The tool is pulled back approximately 12", exposing the screened sample zone and isolating the collection point from layers above and below. After filling (time varies according to submergence and formation yield), the whole HydroPunch is withdrawn to the surface, where 500 ml of sample is discharged through a stopcock.

## HYDROPUNCH II—GROUND WATER SAMPLING

Check valves, stainless steel screen, and O-rings are inserted in the tool body (HP11), then the replaceable point is attached. The tool is driven to the proper depth and pulled back approximately 18". After filling, the tool is withdrawn to discharge 1250 ml of sample, leaving the steel point in the ground.

## HYDROPUNCH II—FLOATING LAYER SAMPLING

After inserting the replaceable polypropylene or PVC screen and attaching the point, the tool is driven to the proper depth. It is then withdrawn about 48", and a 1" O.D. hydrocarbon bailer is lowered through the hollow casing to provide the floating layer thickness estimate and sample.

### HYDROPUNCH OR HYDROPUNCH II:

#### How To Choose

For most applications, the HydroPunch II (patent pending) will probably be the tool of choice. It is more rugged, simpler to operate, samples hydrocarbons as well as ground water, delivers a larger sample volume, and costs no more.

The original HydroPunch (U.S. Patent No. 4,669,554) will be the choice when it is not permissible to leave expendable drive cones (and/or screens) in the ground, or when the tool is to be driven by cone penetrometer equipment rather than a drill rig.

#### HYDROPUNCH I

- Collects ground water samples only (not floating layer)
- Permanently-attached drive cone and screen (leaves nothing in the ground)
- Can be used with cone penetrometer or drill rig
- Expendable supplies (O-rings, screens, clamps) sold separately

#### HYDROPUNCH II

- Collects floating layer and ground water samples
- Replaceable cones and screens are left in ground (note: screens may be retrievable)
- Stronger for tough duty; used with drill rig
- Expendable supplies (points, screens, O-rings) sold separately




### HYDROPUNCH ON VIDEO

#### Sampling Ground Water And Hydrocarbons Without Wells

This 15-minute tape shows how the HydroPunch system collects ground water and floating hydrocarbon samples for field investigation and plume definition without installing permanent wells, with 50-90% savings in cost and time. Economics, speed, and accuracy are explored with animation, graphics, and interviews with consultants, drillers, and industrial end users, explaining the advantages of this new technology.

#### HydroPunch II User's Guide

This easy-to-use video, included with every HP1000 kit, provides detailed, step-by-step instructions covering all aspects of HydroPunch II use. Major areas include: how the system works; assembly and operation in both ground water and hydrocarbon sampling modes; decontamination procedures; drillers' rules; and field trouble-shooting techniques.



Hydrocarbon bailer for floating layer sampling with HydroPunch II (or in wells).



HydroPunch II expendable screens—(left to right) PVC and standard polypropylene for floating layers, stainless steel for ground water.

# HYDROPUNCH

## HYDROPUNCH I

### SPECIFICATIONS:

O.D.: 1.75  
 Length: 64.50" (closed)  
 Top thread: AW box  
 Weight: 24 lbs.  
 Sample volume: 500 ml  
 Materials:  
 Body & fittings: 304 S.S.  
 Check balls: S.S.  
 Screen: S.S.  
 Barbed point: S.S.  
 Stopcock: Teflon\*  
 Discharge tubing: Teflon  
 O-rings: Viton


### SYSTEM COMPONENTS:

MODEL NO	DESCRIPTION
HP0500	HydroPunch Kit—Includes HydroPunch w/ barbed point; cleaning brush & handle set; top discharge w/ Teflon stopcock & tubing; 12 extra O-ring sets, 12 S.S. screen sets, and check balls; instruction book; carrying case.
35500	Basic HydroPunch without case or accessories

### OPERATING SUPPLIES:

(One set of each per drive)

35540	O-ring Kit—12 sets
35760	Screen Kit—12 screens w/ clamps



## HYDROPUNCH II

### SPECIFICATIONS:

O.D.: 2.00"  
 Length: 60" (closed)  
 Top thread: AW Box and EW Casing  
 Weight: 26 lbs. (ground water mode)  
 24 lbs. (hydrocarbon mode)  
 Sample volume: 1250 ml (ground water mode)  
 Unlimited (floating layer)  
 Materials:  
 Body & fittings: 304 S.S.  
 Drive shoes: Carbon Steel (S.S. optional)  
 Adaptors: Carbon Steel  
 Check valves: Ethylenepropylene  
 Screens: S.S. (ground water),  
 Polypropylene or PVC (hydrocarbon)  
 Points: Lead-free Carbon Steel  
 O-rings: Viton  
 Stopcock: Teflon  
 Discharge tubing: Teflon

### SYSTEM COMPONENTS:

MODEL NO	DESCRIPTION
HP1000	HydroPunch II Kit—Includes HP11; cleaning brush & handle set; top discharge w/ Teflon stopcock & tubing; hydrocarbon bailer; 5 sets check valves (reusable); 10 sets O-rings; instruction book; how-to-use video; carrying case. (Does not include points & screens).
36047	Basic HydroPunch II without case or accessories

### OPERATING SUPPLIES:

(One each per drive in appropriate mode)

#### Both modes:

36050	Drive Point Kit—10 ea.
36049	O-ring Kit—10 sets

#### Ground Water mode:



36051	S.S. Screen Kit (4" length)—10 ea.
-------	---------------------------------------

#### Hydrocarbon mode: (choice of)

36102	Standard Polypropylene Screen Kit (5' length, 0.40" slot)—10 ea.
36103	PVC Screen Kit (5' length, .010" slot)—10 ea.

### ACCESSORIES:

35509	1" O.D. Teflon Bailer
36164	1" O.D. Hydrocarbon Bailer
8340100	Bailer Reel w/ 100' Cable
36106	Sub AW Box—EW Casing
36107	EW Casing, 5' length
36171	EW Casing, 2' length
36172	EW Casing, 3' length
36173	Sub EW Pin—NWML Box



\* Teflon is a registered trademark of E.I duPont De Nemours Company, Inc.



## ***Appendix M***

### ***Surface Water Sampling Standard Operating Procedures***

## APPENDIX M-1

### STANDARD OPERATING PROCEDURE FOR SOUNDING DEPTHS

A Hummingbird Depth Sounder will be used for sounding depths at surface water sampling locations. The Hummingbird Depth Sounder does not require calibration. To determine the depth of water at a location:

1. Attach the sounding device to the boat. Orient the device so that it is perpendicular to the bottom of the water body.
2. Turn the device on and record the depth as it appears on the instrument.

## APPENDIX M-2

### STANDARD OPERATING PROCEDURE FOR RETRIEVING SURFACE WATER SAMPLES FROM DEPTH WITH A KEMMERER BOTTLE

The Kemmerer bottle is a messenger-activated water sampling device. In the open position water flows easily through the device. Once lowered to the desired depth a messenger is dropped down the sample line tripping the release mechanism and closing the bottle. In the closed position, the bottle is sealed, both top and bottom, from any additional contact with the water column and can be retrieved. A stainless steel and teflon Kemmerer bottle will be used for collecting surface water samples from depth.

#### Procedure

1. Measure and then mark sample line at desired sampling depth.
2. Open bottle by lifting top stopper-trip head assembly.
3. Place messenger on sample line and release.
4. Retrieve sampler; hold sampler by center stem to prevent accidental opening of bottom stopper.
5. Recover sample by grasping lower stopper and sampler body with one hand, and transfer sample by either lifting the top stopper with the other hand and carefully pouring contents into sample bottle, or holding drain valve (if present) over sample bottle and opening valve.